

I:\PROJECTS\81488\Design\Roadway\81488GQ002.dgn 24-JUN-2014 1:14PM tbarr

SLM		LENGTH	SIDE	202	606						209	659		626	REMARKS		
				GUARDRAIL REMOVED	GUARDRAIL, TYPE MGS	ANCHOR ASSEMBLY, MGS				MGS BRIDGE TERMINAL ASSEMBLY		LINEAR GRADING	SEEDING AND MULCHING			BARRIER REFLECTOR	
						TYPE B	TYPE E	TYPE A	TYPE T	TYPE 1	TYPE 2						
FROM	TO	FT		FT	FT	EACH	EACH	EACH	EACH	EACH	EACH	MILE	WIDTH (FT)	SQ YD	EACH		
NORTHBOUND																	
20.15	20.44	1400.00	RT	1400.00	1387.50				1						15	CONNECT TO EXISTING RAIL AT BEGINNING OF PROJECT	
21.04	21.17	687.50	RT	687.50	625.00		1		1						8		
21.19	21.42	1225.00	RT	1225.00	1162.50		1		1						14		
21.57	21.87	1600.00	RT	1600.00	1537.50		1		1						17		
21.90	22.31	2162.50	RT	2162.50	2137.50					1					23	CONNECT TO EXISTING RAIL, SEE DETAIL ON THIS SHEET. CONNECT TYPE 1 BTA TO EXIST. BRIDGE BEL-7-2230	
22.34	22.52	950.00	RT	950.00	900.00					1	1				11	CONNECT TYPE 2 BTA TO EXIST. BRIDGE BEL-7-2230 CONNECT TYPE 1 BTA TO EXIST. BRIDGE BEL-7-2251	
22.59	23.45	4550.00	RT	4550.00	4525.00						1				47	CONNECT TYPE 2 BTA TO EXIST. BRIDGE BEL-7-2251 CONNECT TO EXISTING RAIL AT END OF PROJECT	
20.08	20.84	4013.00	RT									0.76	4	1783			
20.84	20.99		RT													SUSPEND WORK	
20.99	21.85	4541.00	RT									0.86	4	2018		RESUME WORK	
21.85	22.01		RT													SUSPEND WORK	
22.01	23.45	7603.00	RT									1.44	4	3379		RESUME WORK	
SOUTHBOUND																	
20.83	20.86	187.50	LT	187.50	125.00		1		1						3		
21.46		25.00	LT	25.00													
22.24	22.31	375.00	LT	375.00	337.50				1		1				5	CONNECT TYPE 2 BTA TO EXIST. BRIDGE BEL-7-2230	
22.34	22.37	137.50	LT	137.50	62.50		1			1					3	CONNECT TYPE 1 BTA TO EXIST. BRIDGE BEL-7-2230	
22.44	22.52	400.00	LT	400.00	362.50				1		1				5	CONNECT TYPE 2 BTA TO EXIST. BRIDGE BEL-7-2251	
22.59	22.63	200.00	LT	200.00	112.50		1		1	1					3	CONNECT TYPE 1 BTA TO EXIST. BRIDGE BEL-7-2251	
20.08	20.84	4013.00	LT									0.76	4	1783			
20.84	20.99		LT													SUSPEND WORK	
20.99	21.85	4541.00	LT									0.86	4	2018		RESUME WORK	
21.85	22.01		LT													SUSPEND WORK	
22.01	23.45	7603.00	LT									1.44	4	3379		RESUME WORK	
TOTALS CARRIED TO GENERAL SUMMARY					13900	13275		6		8	4	4	6.00		14360	154	

