

SHEET NUM.											PART.			ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
	3	4	5	6		8	9	10	12		01/NHS/05								
											1,000			832	30000	1,000	EACH	EROSION CONTROL	
																		PAVEMENT	
	1,500					141,466					1,500			251	01021	1,500	SY	PARTIAL DEPTH PAVEMENT REPAIR (442), AS PER PLAN	P.3
	28,293										141,466			254	01000	141,466	SY	PAVEMENT PLANING, ASPHALT CONCRETE, 1.5"	
	240										28,293			255	01600	28,293	SY	PATCHING PLANED SURFACE	
	990										240			255	16001	240	SY	FULL DEPTH PAVEMENT REMOVAL AND RIGID REPLACEMENT, TYPE 2, CLASS QC MS, AS PER PLAN	P.3
											990			255	20000	990	FT	FULL DEPTH PAVEMENT SAWING	
	LS										LS			SPECIAL	40010000	LS		PAVER MOUNTED THERMAL PROFILING	P.3
						12,732					12,732			407	10000	12,732	GAL	TACK COAT	
						5,895					5,895			442	10301	5,895	CY	ASPHALT CONCRETE SURFACE COURSE, 12.5 MM, TYPE A (447), AS PER PLAN	P.3
		1									1			616	10000	1	MGAL	WATER	
						13.08					13.08			618	40600	13.08	MILE	RUMBLE STRIPS, SHOULDER (ASPHALT CONCRETE)	
	LS										LS			SPECIAL	69098400	LS		INTELLIGENT COMPACTION	P.3
																		TRAFFIC CONTROL	
								432			432			621	00100	432	EACH	RPM	
								432			432			621	54000	432	EACH	RAISED PAVEMENT MARKER REMOVED	
							0.15				0.15			644	00104	0.15	MILE	EDGE LINE, 6"	
							0.05				0.05			644	00300	0.05	MILE	CENTER LINE	
							84				84			644	00500	84	FT	STOP LINE	
							13.08				13.08			807	14010	13.08	MILE	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING, EDGE LINE, 6"	
							6.54				6.54			807	14110	6.54	MILE	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING, LANE LINE, 6"	
							2,771				2,771			807	14410	2,771	FT	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING, DOTTED LINE, 6"	
							0.12				0.12			807	12010	0.12	MILE	WET REFLECTIVE EPOXY PAVEMENT MARKING, EDGE LINE, 6"	
							0.06				0.06			807	12110	0.06	MILE	WET REFLECTIVE EPOXY PAVEMENT MARKING, LANE LINE, 6"	
							19.62				19.62			850	10010	19.62	MILE	GROOVING FOR 6" RECESSED PAVEMENT MARKING, (ASPHALT)	
							0.18				0.18			850	20010	0.18	MILE	GROOVING FOR 6" RECESSED PAVEMENT MARKING, (CONCRETE)	
																		STRUCTURE REPAIR (JAC-35-25.43SR SFN: 4000722)	
								152			152			202	23500	152	SY	WEARING COURSE REMOVED	
								86			86			409	30000	86	FT	SAWING AND SEALING ASPHALT CONCRETE PAVEMENT JOINTS	
								77			77			SPECIAL	51822300	77	FT	STEEL DRIP STRIP	P.1
								10			10			519	12304	10	SY	PATCHING CONCRETE BRIDGE DECK - TYPE C	
								16			16			856	10000	16	CY	BRIDGE DECK WATERPROOFING ASPHALT CONCRETE, 1.5"	
																		STRUCTURE REPAIR (JAC-35-26.10L SFN: 4000757)	
								30			30			516	31001	30	FT	JOINT SEALER, AS PER PLAN	P.12
								5			5			519	12304	5	SY	PATCHING CONCRETE BRIDGE DECK - TYPE C	
																		STRUCTURE REPAIR (JAC-35-26.10R SFN: 4000781)	
								10			10			516	31001	10	FT	JOINT SEALER, AS PER PLAN	P.12
								2			2			519	12304	2	SY	PATCHING CONCRETE BRIDGE DECK - TYPE C	
																		MAINTENANCE OF TRAFFIC	
				70							70			614	11110	70	hour	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE	
			12								12			614	12484	12	EACH	WORK ZONE INCREASED PENALTIES SIGN	
			4								4			614	18601	4	SNMT	PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN	P.5
		13.2									13.2			614	20560	13.2	MILE	WORK ZONE LANE LINE, CLASS III, 6", 642 PAINT	
		0.55									0.55			614	22210	0.55	MILE	WORK ZONE EDGE LINE, CLASS I, 6", 740.06, TYPE I	
		26.4									26.4			614	22360	26.4	MILE	WORK ZONE EDGE LINE, CLASS III, 6", 642 PAINT	
		2,880									2,880			614	24612	2,880	FT	WORK ZONE DOTTED LINE, CLASS III, 6", 642 PAINT	
		168									168			614	26610	168	FT	WORK ZONE STOP LINE, CLASS III, 642 PAINT	
			16								16			808	18700	16	SNMT	DIGITAL SPEED LIMIT (DSL) SIGN ASSEMBLY	
																		INCIDENTALS	
											LS			614	11000	LS		MAINTAINING TRAFFIC	
											LS			623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
											LS			624	10000	LS		MOBILIZATION	

GENERAL SUMMARY

DESIGN AGENCY



DESIGNER

ZDR

REVIEWER

MCM 12-26-24

PROJECT ID

118773

SHEET

P.7

TOTAL

12

PAVEMENT MARKING SUBSUMMARY	
	
DESIGNER ZDR	
REVIEWER MCM 12-26-24	
PROJECT ID 118773	
SHEET P.9	TOTAL 12