

WAY-3/301-7.15/1.60

MODEL: GENSUM1 PAPER SIZE: 34x22 (in.) DATE: 4/22/2025 TIME: 4:01:11 PM USER: j baker5
 www:\vhidori-pw.bentley.com:ohidori-pw-02\Documents\01 Active Projects\District 03\Wayne\115028\400-Engineering\Roadway\Sheets\115028_GG001.dgn

SHEET NUMBER											PART.	ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
4	5	6	8	9	14	24	33	34	SR3.RW.3	SR301.RW.3	01/STR/06						
					LS						LS	201	11000	LS		ROADWAY	
					297						297	202	23000	297	SY	CLEARING AND GRUBBING	
						80	30				110	202	35100	110	FT	PAVEMENT REMOVED	
					400						400	202	38000	400	FT	PIPE REMOVED, 24" DIAMETER AND UNDER	
					3						3	202	42000	3	EACH	GUARDRAIL REMOVED	
																ANCHOR ASSEMBLY REMOVED, TYPE A	
					1						1	202	42040	1	EACH	ANCHOR ASSEMBLY REMOVED, TYPE T	
							56				56	SPECIAL	20270110	56	FT	PIPE CLEANOUT, 24" AND UNDER	6
					105						105	202	75000	105	FT	FENCE REMOVED	
							LS				LS	202	98000	LS		REMOVAL MISC.: CONCRETE PAD	6
					4						4	202	98100	4	EACH	REMOVAL MISC.: BOULDER	4
					529						529	203	10000	529	CY	EXCAVATION	
					786						786	203	20000	786	CY	EMBANKMENT	
					310						310	204	10000	310	SY	SUBGRADE COMPACTION	
					562.5						562.5	606	15100	562.5	FT	GUARDRAIL, TYPE MGS WITH LONG POSTS	
					7						7	606	26150	7	EACH	ANCHOR ASSEMBLY, MGS TYPE E, MASH 2016	
					1						1	606	26550	1	EACH	ANCHOR ASSEMBLY, MGS TYPE T, MASH 2016	
					112						112	607	98000	112	FT	FENCE, MISC.: TEMPORARY FENCING	4
									2	2	4	623	38500	4	EACH	MONUMENT ASSEMBLY, TYPE C	
LS											LS	623	50000	LS		PRECONSTRUCTION SURVEY MONUMENT VERIFICATION AND REPORT	
LS											LS	623	51000	LS		POST CONSTRUCTION SURVEY MONUMENT VERIFICATION AND REPORT	
								1			1	SPECIAL	69050200	1	EACH	MAILBOX SUPPORT SYSTEM, DOUBLE	34
						11.7	3.5				15.2	601	11000	15.2	SY	EROSION CONTROL	
						32					32	601	21050	32	SY	RIPRAP, TYPE D	
						21					21	601	32000	21	SY	TIED CONCRETE BLOCK MAT WITH TYPE 1 UNDERLAYMENT	
							4				4	601	32100	4	CY	ROCK CHANNEL PROTECTION, TYPE A WITH FILTER	
	0.34										0.34	601	32100	4	CY	ROCK CHANNEL PROTECTION, TYPE B WITH FILTER	
																COMMERCIAL FERTILIZER	
	2										2	659	00100	2	EACH	SOIL ANALYSIS TEST	
	272										272	659	00300	272	CY	TOPSOIL	
	2,453										2,453	659	10000	2,453	SY	SEEDING AND MULCHING	
	123										123	659	14000	123	SY	REPAIR SEEDING AND MULCHING	
	123										123	659	15000	123	SY	INTER-SEEDING	
	0.51										0.51	659	31000	0.51	ACRE	LIME	
	13.58										13.58	659	35000	13.58	MGAL	WATER	
						1,060	611				1,671	670	00530	1,671	SY	SLOPE EROSION PROTECTION MAT, TYPE C	
											500	832	30000	500	EACH	EROSION CONTROL	
						40					40	605	31100	40	FT	DRAINAGE	
						45					45	611	04900	45	FT	AGGREGATE DRAINS	
						95					95	611	07600	95	FT	12" CONDUIT, TYPE D	
																18" CONDUIT, TYPE C	
							22				22	611	10200	22	FT	24" CONDUIT, TYPE A, 706.02	
						85					85	611	23600	85	FT	60" CONDUIT, TYPE A, 706.02, 707.33, 707.02 (0.168) WITH CONCRETE FIELD PAVING	
							7				7	611	97200	7	EACH	CONDUIT, MISC.: INTERNAL JOINT SEAL	6
							56				56	611	97400	56	FT	CONDUIT, MISC.: VIDEO LOG	6
						1					1	611	98300	1	EACH	CATCH BASIN, NO. 5	
					230						230	254	01000	230	SY	PAVEMENT	
					73						73	301	56000	73	CY	PAVEMENT PLANING, ASPHALT CONCRETE (3.0")	
					35						35	304	20000	35	CY	ASPHALT CONCRETE BASE, PG64-22, (449) (9.0")	
					51						51	304	20000	51	CY	AGGREGATE BASE (3.0")	
					16						16	304	20000	16	CY	AGGREGATE BASE (6.0")	
																AGGREGATE BASE (8.0")	
					76						76	407	10000	76	GAL	TACK COAT	
					140						140	408	10001	140	GAL	PRIME COAT, AS PER PLAN (0.4 GAL/SY)	6
					44						44	442	22001	44	CY	ASPHALT CONCRETE SURFACE COURSE, 9.5 MM, TYPE A (449), AS PER PLAN (PG64-22) (3.0")	6

GENERAL SUMMARY

DESIGN AGENCY	
DISTRICT 3	
	
ENGINEERING TEAM FOUR	
DESIGNER	
JLB	
REVIEWER	
NRF 02/01/25	
PROJECT ID	
115028	
SHEET	TOTAL
12	37