


SHEET NUMBER									PART.	ITEM	ITEM	GRAND	UNIT	DESCRIPTION	SEE SHEET NO.
					P.3	P.6	P.7	01/NFP		EXT	TOTAL				
														<b>ROADWAY</b>	
					180				180	SPECIAL	20253000	180	EACH	PARKING BLOCK REMOVED AND REPLACED	P.3
					300				300	SPECIAL	20253010	300	EACH	PARKING BLOCK REMOVED AND RESET	P.3
						172	1,510		1,682	203	10000	1,682	CY	EXCAVATION	
					200				200	203	98600	200	EACH	ROADWAY, MISC.: BLOCK REMOVED AND RESET	P.3
					LS				LS	SPECIAL	69091000	LS		AS-BUILT CONSTRUCTION PLANS	P.3
									3,000	832	30000	3,000	EACH	<b>EROSION CONTROL</b>	
														<b>EROSION CONTROL</b>	
														<b>DRAINAGE</b>	
					5				5	611	98634	5	EACH	CATCH BASIN RECONSTRUCTED TO GRADE	
					400				400	SPECIAL	61199820	400	LB	MISCELLANEOUS METAL	P.3
														<b>PAVEMENT</b>	
					6,300				6,300	251	01000	6,300	SY	PARTIAL DEPTH PAVEMENT REPAIR (441)	
						42,353	60,341		102,694	254	01000	102,694	SY	PAVEMENT PLANING, ASPHALT CONCRETE (T=1.5")	
						69	604		673	301	56000	673	CY	ASPHALT CONCRETE BASE, PG64-22, (449) (T=5")	
						83	725		808	304	20000	808	CY	AGGREGATE BASE (T=6")	
						2,571	3,882		6,453	407	20000	6,453	GAL	NON-TRACKING TACK COAT @ 0.06 GAL/SY	
							11,112		11,112	423	00204	11,112	SY	CRACK SEALING, TYPE II	
						1,786	2,696		4,482	441	70100	4,482	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (449), PG70-22M (T=1.5")	
							1,667		1,667	886	11000	1,667	GAL	FOG SEAL @ 0.15 GAL/SY	
														<b>TRAFFIC CONTROL</b>	
					0.15				0.15	642	00310	0.15	MILE	CENTER LINE, TYPE 1A	
					95				95	642	00500	95	FT	STOP LINE, TYPE 1	
					1,850				1,850	642	00700	1,850	FT	TRANSVERSE/DIAGONAL LINE, TYPE 1	
					29,645				29,645	642	01200	29,645	FT	PARKING LOT STALL MARKING, TYPE 1	
					12				12	642	01300	12	EACH	LANE ARROW, TYPE 1	
					33				33	642	01702	33	EACH	HANDICAP SYMBOL MARKING, TYPE 1	
														<b>INCIDENTALS</b>	
									LS	614	11000	LS		MAINTAINING TRAFFIC	
									3	619	16010	3	MNTH	FIELD OFFICE, TYPE B	
									LS	623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
									LS	624	10000	LS		MOBILIZATION	

GENERAL SUMMARY

DESIGN AGENCY



DESIGNER  
**CMS**

REVIEWER  
**MJP 01-13-26**

PROJECT ID  
**111258**

SHEET TOTAL  
P.5 | 7