SHEET NUMBER									PART.					ALT	ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
11	12	16	17	21	22	42	74	76	01/NHS	02/S5K	03/NFP	05/SAF	06/NFA	(X)						
																			PAVEMENT	
	492										492				251	01043	492	CY	PARTIAL DEPTH PAVEMENT REPAIR (ASPHALT CONCRETE BASE), AS PER PLAN (LONGITUDINAL)	12
	211										211				251	01043	211	CY	PARTIAL DEPTH PAVEMENT REPAIR (ASPHALT CONCRETE BASE), AS PER PLAN (TRANSVERSE)	12
	50				12						50		12		253	02001	62	CY	PAVEMENT REPAIR, AS PER PLAN (LONGITUDINAL)	12
	21										21				253	02001	21	CY	PAVEMENT REPAIR, AS PER PLAN (TRANSVERSE)	12
				194,132					112,860	81,272					254	01000	194,132	SY	PAVEMENT PLANING, ASPHALT CONCRETE(1.50")	
	9,908								5,812	4,096					254	01600	9,908	SY	PATCHING PLANED SURFACE	
				17,472					10,158	7,314					407	20000	17,472	GAL	NON-TRACKING TACK COAT	
				3,581					3,581						408	10001	3,581	GAL	PRIME COAT, AS PER PLAN	12
				8,090					4,703	3,387					442	00201	8,090	CY	ASPHALT CONCRETE SURFACE COURSE, 9.5 MM, TYPE A (446), AS PER PLAN(PG64-22)	12
				497					497						617	10100	497	CY	COMPACTED AGGREGATE	
																			WATER WORK	
24										24					638	10800	24	EACH	VALVE BOX ADJUSTED TO GRADE	
																			TRAFFIC CONTROL	
					11						11				626	00102	11	EACH	BARRIER REFLECTOR, TYPE 1, 1 WAY, (W)	
					11							11			626	00102	11	EACH	BARRIER REFLECTOR, TYPE 1, BIDIRECTIONAL, (Y/Y)	
					20						10		10		626	00102	20	EACH	BARRIER REFLECTOR, TYPE 1, BIDIRECTIONAL, (W/W)	
					1	2					2	1			630	85100	3	EACH	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION	
					1	2					2	1			630	86010	3	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND REERECTION	
							8,040		6,800	1,240					644	00404	8,040	FT	CHANNELIZING LINE, 12"	
							772		463	309					644	00500	772	FT	STOP LINE	
							1,942			1,942					644	00620	1,942	FT	CROSSWALK LINE, 12"	
							174		174						644	00700	174	FT	TRANSVERSE/DIAGONAL LINE(WHITE)	
							778			778					644	00700	778	FT	TRANSVERSE/DIAGONAL LINE(YELLOW)	
							160		100	60					644	00900	160	SF	ISLAND MARKING	
							4			4					644	01110	4	EACH	SCHOOL SYMBOL MARKING, 96"	
							125		87	38					644	01300	125	EACH	LANE ARROW	
							1,631		761	870					644	50300	1,631	FT	PAVEMENT MARKING, MISC.:CROSSWALK LINE, 18", AS PER PLAN	13
							170			170					646	10510	170	FT	CROSSWALK LINE, 12"	
							0.16		0.16						646	10010	0.16	MILE	EDGE LINE, 6"(WHITE)	
							0.16		0.16						646	10010	0.16	MILE	EDGE LINE, 6"(YELLOW)	
							0.16		0.16						646	10110	0.16	MILE	LANE LINE, 6"	
																			TRAFFIC CONTROL ALTERNATES (US 20)	
							4.61		4.61					X	642	00104	4.61	MILE	EDGE LINE, 6", TYPE 1(WHITE) (ALTERNATIVE 1)	
							4.61		4.61					X	642	00104	4.61	MILE	EDGE LINE, 6", TYPE 1(YELLOW) (ALTERNATIVE 1)	
							4.61		4.61					X	642	00204	4.61	MILE	LANE LINE, 6", TYPE 1(ALTERNATIVE 1)	
							0.03		0.03					X	642	00300	0.03	MILE	CENTER LINE, TYPE 1(ALTERNATIVE 1)	
							4.61		4.61					X	644	00104	4.61	MILE	EDGE LINE, 6"(WHITE) (ALTERNATIVE 2)	
							4.61		4.61					X	644	00104	4.61	MILE	EDGE LINE, 6"(YELLOW) (ALTERNATIVE 2)	
							4.61		4.61					X	644	00204	4.61	MILE	LANE LINE, 6"(ALTERNATIVE 2)	
							0.03		0.03					X	644	00300	0.03	MILE	CENTER LINE(ALTERNATIVE 2)	
																			TRAFFIC CONTROL ALTERNATES (SR 301)	
							3.74			3.74				X	642	00204	3.74	MILE	LANE LINE, 6", TYPE 1(ALTERNATIVE 1)	
							2.92			2.92				X	642	00300	2.92	MILE	CENTER LINE, TYPE 1(ALTERNATIVE 1)	
							3.74			3.74				X	644	00204	3.74	MILE	LANE LINE, 6"(ALTERNATIVE 2)	
							2.92			2.92				X	644	00300	2.92	MILE	CENTER LINE(ALTERNATIVE 2)	

GENERAL SUMMARY

DESIGN AGENCY
DISTRICT 3
ENGINEERING TEAM ONE

DESIGNER
ERC

REVIEWER
ACM 11/14/25

PROJECT ID
112691

SHEET P.19 TOTAL 76

LOR-20/301-16.93/19.54

MODEL: GS 2 PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 1:46:51 PM PLTDRV: OHDOT_PDF.pltcfg PENTBL: OHDOT_Pen.tbl USER: Ethan.Caudill@dot.ohio.gov WORKSPACE: OHDOTCE\v02 WORKSET: 112691 PRODUCT: OpenRoadsDesigner 24.00.00.205
pw:\\ohiodot-pw.bentley.com:ohiodot-pw-02\Documents\01 Active Projects\District 03\Lorain\112691\400-Engineering\Roadway\Sheets\112691_GG001.dgn