



NOTES

1. FOR AREAS WHERE FULL DEPTH PAVEMENT WIDENING IS PROPOSED, SUBGRADE COMPACTION SHALL BE PERFORMED. FOR THE PROPOSED LIMITS FOR FULL DEPTH WIDENING, SEE THE TYPICAL SECTIONS ON SHEETS P.4 THRU P.14.

* - CONTRACTOR SHALL IDENTIFY EX. CONDUIT DURING THE REVIEW OF DRAINAGE FACILITIES, AS NOTED ON SHEET 16. CONTRACTOR SHALL PROCEED WITH EXTREME CAUTION DIGGING IN IDENTIFIED AREAS, NOT TO DISTURB THE EX. STORM SEWER.

Item 204 - Granular Material, Type B with Geotextile Fabric

Sheet Totals			SHEET	TOTAL
Seeding	Cut	Fill		
67.3	484.7	1.4	P.189	439

CROSS SECTIONS - U.S. 224
STA. 962+50.00 TO STA. 963+50.00

DESIGN AGENCY

PRIME
8415 Pulsar Place Suite 300
Columbus Ohio 43240

DESIGNER

MGW

REVIEWER

SA 03/27/26

PROJECT ID

115790