


SHEET NUM.									PART.			ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
11	22	23	24	25	80	90			01/STR	02/BRO	03/BRO						
																DRAINAGE	
		667							394	273		202	35100	667	FT	PIPE REMOVED, 24" DIAMETER AND UNDER	
		1								1		202	58000	1	EACH	MANHOLE REMOVED	
		1								1		202	58100	1	EACH	CATCH BASIN REMOVED	
		1								1		602	20000	1	CY	CONCRETE MASONRY	
			21							21		605	13410	21	FT	6" UNCLASSIFIED PIPE UNDERDRAINS WITH GEOTEXTILE FABRIC, 707.31	
				1,019					678	341		605	14020	1,019	FT	6" BASE PIPE UNDERDRAINS WITH GEOTEXTILE FABRIC, 707.31	
16									16			605	31100	16	FT	AGGREGATE DRAINS	
25									25			611	00400	25	FT	4" CONDUIT, TYPE E	
25									25			611	00406	25	FT	4" CONDUIT, TYPE F	
			122						72	50		611	00510	122	FT	6" CONDUIT, TYPE F FOR UNDERDRAIN OUTLETS	
50									50			611	03100	50	FT	10" CONDUIT, TYPE B	
		59							59			611	04400	59	FT	12" CONDUIT, TYPE B	
		20								20		611	04600	20	FT	12" CONDUIT, TYPE C	
		82								82		611	07600	82	FT	18" CONDUIT, TYPE C	
		1								1		611	98150	1	EACH	CATCH BASIN, NO. 3	
		1							1			611	98450	1	EACH	CATCH BASIN, NO. 2-2A	
		3								3		611	98630	3	EACH	CATCH BASIN ADJUSTED TO GRADE	
		2								2		611	99574	2	EACH	MANHOLE, NO. 3	
			2						2			611	99710	2	EACH	PRECAST REINFORCED CONCRETE OUTLET	
																PAVEMENT	
		608							386	222		301	56000	608	CY	ASPHALT CONCRETE BASE, PG64-22, (449)	
		564		29					373	220		304	20000	593	CY	AGGREGATE BASE	
		287		8					185	110		407	10000	295	GAL	TACK COAT	
		20							20			411	10000	20	CY	STABILIZED CRUSHED AGGREGATE	
		271							184	87		441	70000	271	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (449), PG64-22	
				7					2	5		441	70500	7	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (449), (DRIVEWAYS)	
				6					2	4		441	70600	6	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (449), (DRIVEWAYS)	
	12			362						309	65	452	12010	374	SY	8" NON-REINFORCED CONCRETE PAVEMENT, CLASS QC 1P	
	629									629		609	12000	629	FT	COMBINATION CURB AND GUTTER, TYPE 2	
																WATER WORK	
		216								216		SPECIAL	20270000	216	FT	FILL AND PLUG EXISTING CONDUIT, 12"	12
		35							35			SPECIAL	20270000	35	FT	FILL AND PLUG EXISTING CONDUIT, 20"	12
		195							195			SPECIAL	63811614	195	FT	20" WATER MAIN DIP AND FITTINGS, CITY OF BOWLING GREEN SPECIFICATIONS	67-72
		1							1			SPECIAL	63820666	1	EACH	20" BUTTERFLY VALVE WITH VALVE BOX, CITY OF BOWLING GREEN SPECIFICATIONS	72
		1							1			638	98000	1	EACH	WATER WORK, MISC.: 1" WATER SERVICE (SHORT), CITY OF BOWLING GREEN SPECIFICATIONS	73
		2							2			638	98000	2	EACH	WATER WORK, MISC.: CONNECT TO EXISTING WATER MAIN, CITY OF BOWLING GREEN SPECIFICATIONS	67-72
																SANITARY SEWER	
374					LS						374	202	35700	374	FT	ASBESTOS PIPE REMOVED	
											LS	611	97300	LS		CONDUIT, MISC.: SANITARY SEWER BYPASS PUMPING	80
		190									190	611	97400	190	FT	CONDUIT, MISC.:10" SANITARY SEWER DUCTILE IRON PIPE, CEMENT LINED, RESTRAINED JOINTS, NWWSD SPECIFICATIONS	11
		184									184	611	97400	184	FT	CONDUIT, MISC.:10" SANITARY SEWER PVC PRESSURE PIPE, AWWA C900 OR C909, NWWSD SPECIFICATIONS	80
		1									1	SPECIAL	69098000	1	EACH	2" X 10" TAPPING SADDLE, NWWSD SPECIFICATIONS	80
						8					8	625	00450	8	EACH	LIGHTING	
						4					4	625	10481	4	EACH	CONNECTION, FUSED PULL APART	
						939					939	625	23302	939	FT	LIGHT POLE, AESTHETIC, AS PER PLAN, AT02B30	89
						456					456	625	23400	456	FT	NO. 6 AWG 2400 VOLT DISTRIBUTION CABLE	
						141					141	625	25400	141	FT	NO. 10 AWG POLE AND BRACKET CABLE	
																CONDUIT, 2", 725.04	
						107					107	625	25408	107	FT	CONDUIT, 2", 725.051	
						4					4	625	27551	4	EACH	LUMINAIRE, DECORATIVE, AS PER PLAN, LED, POST-TOP LANTERN, ARM MOUNTED, 3000K, IES III, BLACK, W/AESTHETICS	89
						107					107	625	29002	107	FT	TRENCH, 24" DEEP	
						4					4	625	29920	4	EACH	STRUCTURE JUNCTION BOX	
						2					2	625	30700	2	EACH	PULL BOX, 725.08, 18"	
						1					1	625	32000	1	EACH	GROUND ROD	
						1					1	625	34001	1	EACH	POWER SERVICE, AS PER PLAN	89
						107					107	625	36010	107	FT	UNDERGROUND WARNING/MARKING TAPE	

GENERAL SUMMARY

DESIGN AGENCY



DESIGNER

GCB

REVIEWER

DTC 01/22/25

PROJECT ID

107711

SHEET

P.19

TOTAL

164