



STATION	SIDE	LENGTH	AVERAGE WIDTH	AREA	NOTE	254	407	407	441	441	614	614	614	632	632	644	644	644
						PAVEMENT PLANING, ASPHALT CONCRETE, ASPER PLAN, 3.0"	NON-TRACKING TACK COAT (0.085 GAL/SY MILLED SURFACE)	NON-TRACKING TACK COAT (0.055 GAL/SY INTERMEDIATE COURSE)	ASPHALT CONCRETE SURFACE COURSE, TYPE 1 (449), PG64-22, 1.25"	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2 (449), 1.75"	WORK ZONE CENTERLINE, CLASS III, 642 PAINT (3 APPLICATIONS)	WORK ZONE STOP LINE, CLASS III, 642 PAINT (3 APPLICATIONS)	WORK ZONE MARKING SIGN	DETECTOR LOOP	LOOP DETECTOR LEAD-IN CABLE	EDGE LINE, 4"	CENTERLINE	STOP LINE
		FT	FT	SF		SY	GAL	GAL	CY	CY	MILE	FT	EACH	EACH	FT	MILE	MILE	FT
<b>CR 5 - SUGAR ST</b>												45	2	1	10			15
0.000	0.032	169	29.6	5001	ROADWAY	556	48	31	20	28	0.10							0.04
0.032	0.059	143	28.3	4034	ROADWAY	449	39	25	16	22	0.09							0.03
0.059	0.077	95	27.6	2623	ROADWAY	292	25	17	11	15	0.06							0.02
0.077	0.158	428	30.5	13044	ROADWAY	1450	124	80	51	71	0.25							0.09
0.158	0.174	84	30.6	2585	ROADWAY	288	25	16	10	14	0.05							0.02
0.174	0.289	607	28.2	17123	ROADWAY	1903	162	105	67	93	0.35							0.12
0.289	0.318	153	27.1	4150	ROADWAY	462	40	26	17	23	0.09							0.03
0.318	0.321	16	24.4	386	ROADWAY	43	4	3	2	3	0.01							0.01
0.321	0.365	232	22.3	5181	ROADWAY	576	49	32	20	28	0.14							0.05
0.365	0.404	206	23.3	4798	ROADWAY	534	46	30	19	26	0.12							0.04
0.404	0.407	16	22.5	356	ROADWAY	40	4	3	2	2	0.01							0.01
0.407	0.439	169	22.2	3751	ROADWAY	417	36	23	15	21	0.10							0.04
0.439	0.552	597	21.9	13066	ROADWAY	1452	124	80	51	71	0.34							0.12
0.552	0.590	201	20.1	4033	ROADWAY	449	39	25	16	22	0.12					0.08	0.04	
<b>TOTALS CARRIED TO GENERAL SUMMARY</b>						<b>8911</b>	<b>765</b>	<b>496</b>	<b>317</b>	<b>439</b>	<b>1.83</b>	<b>45</b>	<b>2</b>	<b>1</b>	<b>10</b>	<b>0.08</b>	<b>0.66</b>	<b>15</b>

PAVEMENT SUBSUMMARY