SHEET NUM. 5	7	8	11	12	16	20	21	22	23	24	PART. 01/NHS/05	PART. 02/SAF/21	ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
																	MAINTENANCE OF TRAFFIC	
	500										500		614	11110	500	HOUR	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE	
	25										25		614	12600	25	EACH	REPLACEMENT DRUM	
		8									8		614	18601	8	SNMT	PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN	7
							116				116		614	26610	116	FT	WORK ZONE STOP LINE, CLASS III, 642 PAINT	
							23				23		614	30650	23	EACH	WORK ZONE ARROW, CLASS III, 642 PAINT	
							0.21				0.21		614	98000	0.21	MILE	WORK ZONE PAVEMENT MARKING, MISC.: CENTER LINE, CLASS 1, 6", 807 PAINT	21
							53.09				53.09		614	98000	53.09	MILE	WORK ZONE PAVEMENT MARKING, MISC.: EDGE LINE, CLASS 1, 6", 807 PAINT	21
							20.83				20.83		614	98000	20.83	MILE	WORK ZONE PAVEMENT MARKING, MISC.: LANE LINE, CLASS 1, 6", 807 PAINT	21
							18,167				18,167		614	98100	18,167	FT	WORK ZONE PAVEMENT MARKING, MISC.: CHANNELIZING LINE, CLASS 1, 12", 807 PAINT	21
							1,043				1,043		614	98100	1,043	FT	WORK ZONE PAVEMENT MARKING, MISC.: DOTTED LINE, CLASS 1, 12", 807 PAINT	21
							12,766				12,766		614	98100	12,766	FT	WORK ZONE PAVEMENT MARKING, MISC.: DOTTED LINE, CLASS 1, 6", 807 PAINT	21
		48									48		808	18700	48	SNMT	DIGITAL SPEED LIMIT (DSL) SIGN ASSEMBLY	
																	INCIDENTALS	
											LS		614	11000	LS		MAINTAINING TRAFFIC	
											LS		624	10000	LS		MOBILIZATION	

GENERAL SUMMARY

DESIGN AGENCY

DESIGNER
TMK

REVIEWER
BJA 8-16-24

PROJECT ID
109773

SHEET P.10 TOTAL 24

CLA-68-4.43

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 2/10/2025 TIME: 11:25:00 AM USER: bankrom3
pw:\\ohiodot-pw.bentley.com:ohiodot-pw-02\Documents\01 Active Projects\District 07\Clark\109773\400-Engineering\Roadway\Sheets\109773_GG002.dgn

PAVEMENT MARKING SUBSUMMARY

PARTICIPATION	ROUTE	SLM / LOCATION FROM	SLM / LOCATION TO	LANE WIDTH FT	SOLID LINE EQUIVALENT MILE	614 WORK ZONE PAVEMENT MARKING, MISC.: LANE LINE, CLASS 1, 6", 807 PAINT MILE	614 WORK ZONE PAVEMENT MARKING, MISC.: CENTER LINE, CLASS 1, 6", 807 PAINT MILE	614 WORK ZONE PAVEMENT MARKING, MISC.: EDGE LINE WHITE, CLASS 1, 6", 807 PAINT MILE	614 WORK ZONE PAVEMENT MARKING, MISC.: EDGE LINE YELLOW, CLASS 1, 6", 807 PAINT MILE	614 WORK ZONE PAVEMENT MARKING, MISC.: CHANNELIZING LINE, CLASS 1, 12", 807 PAINT FT	614 WORK ZONE PAVEMENT MARKING, MISC.: DOTTED LINE, CLASS 1, 6", 807 PAINT FT	614 WORK ZONE PAVEMENT MARKING, MISC.: DOTTED LINE, CLASS 1, 12", 807 PAINT FT	614 WORK ZONE STOP LINE, CLASS III, 642 PAINT FT	614 WORK ZONE ARROW, CLASS III, 642 PAINT, LEFT EACH	614 WORK ZONE ARROW, CLASS III, 642 PAINT, RIGHT EACH	614 WORK ZONE ARROW, CLASS III, 642 PAINT,THRU/LEFT EACH	614 WORK ZONE ARROW, CLASS III, 642 PAINTWRONG WAY EACH
1	CLA-68	4.43	4.55	12.00			0.20	0.24									
1	CLA-68	4.55	15.04	12.00		20.83		18.35	21.22								
1	CLA-68	SLM 4.98 TO 5.58 @ IR-70 INTG								3513.00	2850.00						
1	CLA-68	SLM 7.11 TO 7.96 @ US-40 INTG						3.59	0.71	4418.00	2693.00	643.00	25.00		2.00	2.00	
1	CLA-68	SLM 8.40 TO 9.22 @ SR-41 INTG						1.79	0.90	3699.00	3100.00		25.00	5.00	2.00		4.00
1	CLA-68	SLM 12.38 @ SR-334 INTG						2.46	1.73	4617.00	2444.00	400.00	34.00				4.00
1	CLA-68	SLM 14.87 @ COUNTY LINE RD INTG						1.38	0.72	1920.00	1679.00		32.00				4.00
					PART.					*SUBTOTALS*							
					1	*20.83*	*0.21*	*27.81*	*25.28*	*18167*	*12766*	*1043*	*116*	*5*	*4*	*2*	*12*
TOTALS CARRIED TO GENERAL SUMMARY						20.83	0.21	27.81	25.28	18167	12766	1043	116	5	4	2	12

CLA-68-4.43

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 2/10/2025 TIME: 11:25:08 AM USER: bankrom3
pw:\\ohiodot-pw.bentley.com:ohiodot-pw-02\Documents\01 Active Projects\District 07\Clark\109773\400-Engineering\Traffic\Sheets\109773_TS001.dgn

DESIGN AGENCY

DESIGNER
BAC

REVIEWER
TMK 8-16-24

PROJECT ID
109773

SHEET P.21 TOTAL 24