



SHEET NUMBER								PART.	ITEM	ITEM	GRAND	UNIT	DESCRIPTION	SEE SHEET
2	5	6	17	18	20	25		01/MS		EXT	TOTAL			NO.
													TRAFFIC CONTROL	
50								50	621	00301	50	EACH	RPM REFLECTOR, AS PER PLAN	2
100								100	626	00102	100	EACH	BARRIER REFLECTOR, TYPE 1, (1WAY)	
			68,270					68,270	645	30000	68,270	FT	REMOVAL OF PAVEMENT MARKINGS	
			6.4					6.4	646	10010	6.4	MILE	EDGE LINE, 6"	
			6					6	646	10111	6	MILE	LANE LINE, 6", AS PER PLAN	2
			1,804					1,804	646	10310	1,804	FT	CHANNELIZING LINE, 12"	
			502					502	646	10620	502	FT	CHEVRON MARKING	
			5,018					5,018	646	20504	5,018	FT	DOTTED LINE, 6"	
													STRUCTURE REPAIR (CUY-480-17.723R)	
150								150	512	10100	150	SY	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)	
						34,375		34,375	512	73500	34,375	SY	TREATING CONCRETE BRIDGE DECKS WITH GRAVITY FED RESIN	
150								150	512	74000	150	SY	REMOVAL OF EXISTING COATINGS FROM CONCRETE SURFACES	
30								30	518	62200	30	EACH	STRUCTURE DRAINAGE, MISC.: SCUPPER CLEANOUT	2
													STRUCTURE REPAIR (CUY-480-18.723C)	
150								150	512	10100	150	SY	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)	
					37,109			37,109	512	73500	37,109	SY	TREATING CONCRETE BRIDGE DECKS WITH GRAVITY FED RESIN	
150								150	512	74000	150	SY	REMOVAL OF EXISTING COATINGS FROM CONCRETE SURFACES	
30								30	518	62200	30	EACH	STRUCTURE DRAINAGE, MISC.: SCUPPER CLEANOUT	2
													STRUCTURE REPAIR (CUY-480-18.723L)	
150								150	512	10100	150	SY	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)	
					33,660			33,660	512	73500	33,660	SY	TREATING CONCRETE BRIDGE DECKS WITH GRAVITY FED RESIN	
150								150	512	74000	150	SY	REMOVAL OF EXISTING COATINGS FROM CONCRETE SURFACES	
30								30	518	62200	30	EACH	STRUCTURE DRAINAGE, MISC.: SCUPPER CLEANOUT	2
													MAINTENANCE OF TRAFFIC	
								500	614	11110	500	hour	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE	
								16	614	18601	16	SNMT	PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN	6
								300	630	97800	300	SF	SIGNING, MISC.: ADDITIONAL SIGNS, GROUND MOUNTED, AS DIRECTED BY ENGINEER	5
													INCIDENTALS	
								LS	614	11000	LS		MAINTAINING TRAFFIC	
								LS	623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
								LS	624	10000	LS		MOBILIZATION	



GENERAL SUMMARY

DESIGN AGENCY



DESIGNER
TSR

REVIEWER
PAT 08/01/25

PROJECT ID
120625

SHEET TOTAL
P.14 | 27

02

REF NO.	SHEET NO.	STATION TO STATION			645	646	646	646	646	646	646														
					REMOVAL OF PAVEMENT MARKINGS FT	EDGE LINE, 6", YELLOW FT	EDGE LINE, 6", WHITE FT	LANE LINE, 6", AS PER PLAN MILE	CHANNELIZING LINE, 12" FT	CHEVRON MARKING FT	DOTTED LINE, 6" FT														
CV1	15	987+53	TO	1004+96						502															
EW1	15 - 16	995+97	TO	1038+03	4,206		4,206																		
LL1	15 - 16	995+97	TO	1013+25	1,728			0.33																	
CH1	15	995+97	TO	1003+96	799				799																
CH2	15	995+97	TO	1003+96	799				799																
LL2	15 - 16	995+97	TO	1038+03	4,206			0.80																	
EY1	15 - 16	995+97	TO	1038+03	4,206	4,206																			
EW2	15 - 16	995+91	TO	1038+09	4,218		4,218																		
LL3	15 - 16	995+91	TO	1038+09	4,218			0.80																	
EY2	15 - 16	995+91	TO	1038+09	4,218	4,218																			
EW3	15 - 16	995+97	TO	1038+03	4,206		4,206																		
LL4	15 - 16	995+97	TO	1038+03	4,206			0.80																	
CH3	15	995+97	TO	997+00	205				205																
DL1	15 - 16	997+00	TO	1022+40	2,540					2,540															
LL5	15 - 16	995+97	TO	1038+03	4,206			0.80																	
EY3	15 - 16	995+97	TO	1038+03	4,206	4,206																			
EW4	15 - 16	995+91	TO	1038+09	4,218		4,218																		
LL6	15 - 16	995+91	TO	1038+09	4,218			0.80																	
EY4	15 - 16	995+91	TO	1038+09	4,218	4,218																			
LL7	15 - 16	1003+96	TO	1038+03	3,407			0.65																	
DL2	16	1013+25	TO	1038+03	2,478					2,478															
LL8	16	1022+40	TO	1038+03	1,563			0.30																	
SUBTOTALS					68,270	16,848	16,848	6	1,804	502	5,018														
TOTALS CARRIED TO GENERAL SUMMARY					68,270	6.4 MI		6	1,804	502	5,018														

TRAFFIC CONTROL SUBSUMMARY

DESIGN AGENCY	
DESIGNER	
REVIEWER	TLO
PROJECT ID	09/26/25
SHEET	120625
TOTAL	27
P.17	