

SHEET NUM.											PART.			ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
P.4	P.5	P.8	P.9							01/NFA									
																	ROADWAY		
LS											LS			201	11000	LS		CLEARING AND GRUBBING	
		13,263	1,575								14,838			202	38000	14,838	FT	GUARDRAIL REMOVED	
			300								300			202	38001	300	FT	GUARDRAIL REMOVED, AS PER PLAN	9
		3,225									3,225			202	38101	3,225	FT	GUARDRAIL REMOVED FOR STORAGE, AS PER PLAN	8
		73	24								97			202	42000	97	EACH	ANCHOR ASSEMBLY REMOVED, TYPE A	
		1									1			202	42010	1	EACH	ANCHOR ASSEMBLY REMOVED, TYPE E	
		7									7			202	42040	7	EACH	ANCHOR ASSEMBLY REMOVED, TYPE T	
		1									1			202	42050	1	EACH	ANCHOR ASSEMBLY REMOVED, TYPE B	
		2	5								7			202	47000	7	EACH	BRIDGE TERMINAL ASSEMBLY REMOVED	
		205	29								234			209	60201	234	STA	LINEAR GRADING, AS PER PLAN	8
		2,105	291								2,396			209	70000	2,396	CY	BORROW	
		300	300								600			517	75600	600	FT	DEEP BEAM BRIDGE RETROFIT RAILING	
		300	450								750			606	13000	750	FT	GUARDRAIL, TYPE 5	
		13,894	1,063								14,957			606	15050	14,957	FT	GUARDRAIL, TYPE MGS	
		2,713	175								2,888			606	15100	2,888	FT	GUARDRAIL, TYPE MGS WITH LONG POSTS	
		75									75			606	17350	75	FT	GUARDRAIL, TYPE MGS, 25' LONG-SPAN	
		1									1			606	26000	1	EACH	ANCHOR ASSEMBLY, TYPE B	
		1									1			606	26050	1	EACH	ANCHOR ASSEMBLY, MGS TYPE B	
			8								8			606	26100	8	EACH	ANCHOR ASSEMBLY, TYPE E	
		67	16								83			606	26150	83	EACH	ANCHOR ASSEMBLY, MGS TYPE E, MASH 2016	
		14									14			606	26550	14	EACH	ANCHOR ASSEMBLY, MGS TYPE T	
		6	12								18			606	35140	18	EACH	BRIDGE TERMINAL ASSEMBLY, TYPE 4	
		6									6			SPECIAL	69050100	6	EACH	MAILBOX SUPPORT SYSTEM, SINGLE	8
		6									6			SPECIAL	69050350	6	EACH	MAILBOX REMOVED AND RESET	8
																		EROSION CONTROL	
	19,500										19,500			659	10000	19,500	SY	SEEDING AND MULCHING	
	975										975			659	14000	975	SY	REPAIR SEEDING AND MULCHING	
	2.64										2.64			659	20000	2.64	TON	COMMERCIAL FERTILIZER	
	4.03										4.03			659	31000	4.03	ACRE	LIME	
	105										105			659	35000	105	MGAL	WATER	
											1,000			832	30000	1,000	EACH	EROSION CONTROL	
																		TRAFFIC CONTROL	
		353	43								396			614	13314	396	EACH	BARRIER REFLECTOR, TYPE 3 BI-DIRECTIONAL	
	100										100			630	03100	100	FT	GROUND MOUNTED SUPPORT, NO. 3 POST	
	23										23			630	85100	23	EACH	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION	
											LS			614	11000	LS		INCIDENTALS	
											LS			624	10000	LS		MOBILIZATION	