# LOCATION 2 – ADDITIONAL NOTES (IN ADDITION TO PROJECT GENERAL NOTES)

#### **Project Location 2 Description**

This project location consists of resurfacing SR-8 (Northfield Rd.) from SLM 00.00 to SLM 1.25

#### Location 2 - (S.R.-8 - Resurfacing)

Utilize standard drawings to close lanes during the working hours, As Directed By The Engineer. Outside of working hours, all lanes shall be open to traffic.

The items of work will include:

- 1. Perform partial depth pavement repairs.
- 2. Plane asphalt
- 3. Perform casting adjustments
- 4. Placement of temporary pavement markings.
- 5. Place asphalt concrete surface course and temporary markings.
- 6. Place final pavement markings.

#### **Maintenance of Traffic**

Work Hours:

The Contractor is permitted to work at night.

Proposed work for this Location, including pavement repairs, pavement milling, pavement paving and placing pavement markings shall be performed between The hours of 7:00 PM and 6:00 AM, Monday thru Friday.

To complete the casting adjustments, the Contractor is permitted to work during the day utilizing lane closures with the following restrictions:

- 1. Outside lanes shall be closed non-concurrently.
- 2. Inside lanes shall be closed concurrently.
- 3. Lane closures will be allowed for a two week period only. If the adjustments are not completed at the end of the two weeks, the remaining adjustments shall be completed utilizing weekend lane closures that adhere to point 1 and 2 above.

#### **Notification**

The Contractor shall conduct their operations to construct the proposed work with a minimum of hazard, delay and inconvenience to the motorists using the highway affected by the work being done under this contract.

The Village of Walton Hills shall be notified at least TWO (2) weeks prior to the actual start of construction by the Contractor.

### <u>Item 251 – Partial Depth Pavement Repair (441), As Per Plan</u>

Use this item to repair unsound, cold-patch, or pop-out areas of longitudinal and transverse joints As Directed By The Engineer.

## Perform repairs after planing at: (Location 2 -SR 8)

Make standard repairs at a depth of 3" and at a minimum width of 12". Center the repair over the existing joint.

Use Type 2 material for this item.

For estimating purposes,

(Location 2 -SR 8: Partial Depth Pavement Repair (441), As Per Plan: 325 SY)

The following quantity have been carried to the General Summary:

Item 251 - Partial Depth Pavement Repair (441), As Per Plan ......... 325 SY

DESIGN AGENCY



DESIGNER
JAG

REVIEWER
DAB 10/11/24

PROJECT ID
113132

SHEET TOTAL
P.36 42

D12-PPM-FY2025