

TOBIN - MCFARLAND SURVEYING, INC.
SURVEYORS AND CARTOGRAPHERS
111 WEST WHEELING STREET - SUITE 202
LANCASTER, OHIO 43130

THOMAS E. TOBIN, P.S.
RODNEY G. MCFARLAND, P.S.

FAX (614) 687-0877
PHONE (614) 687-1710

142
90

40
12088

Description of 2.023 Acres

Situated in the State of Ohio, County of Fairfield, Greenfield Township, Township 15, Range 19, Section 14.

Being a part of the property described in deed volume 582, page 254 to Ray L. Cramblit and being more fully described as follows:

Beginning at a 5/8 inch rebar set at the southwesterly corner of the Randy S. and Cynthia K. Henwood tract as described in deed volume 501, page 483, said point is located South 89° 14' 00" East a distance of 1704.03 feet and North 00° 00' 00" East a distance of 1260.33 feet from the southwest corner of the southeast quarter of section 14;

thence South 89° 42' 01" East a distance of 546.00 feet to point;

thence South 00° 26' 27" West, passing a 5/8 inch rebar set at 3.10 feet, a distance of 161.30 feet to a 3/4 inch iron pipe found;


thence North 89° 42' 01" West a distance of 546.83 feet to a 5/8 inch rebar set;

thence North 00° 44' 12" East a distance of 161.30 feet to the point of beginning containing 2.023 acres.

Bearings are based on the centerline of Coonpath Road being North 89° 14' 00" West (assumed). Rebars set are 5/8 inch by 36 inches and have a yellow plastic identification cap stamped "Tobin-McFarland". For additional information see plat of survey made in conjunction with and considered an integral part of this description.

Description is based on a survey made by Tobin-McFarland Surveying Inc. in June of 1990 and was prepared by Thomas E. Tobin, Registered Professional Surveyor No. 6363.

40
12088


Thomas E. Tobin, P.S.
June 8, 1990