

HAM-75-1.05 Linn Street

PID 122048

May 14, 2025

Updated September 22, 2025

Altafiber

Altafiber has facilities within the project limits. All underground cables will be abandoned after relocation is complete. Conduit and cable attached to Linn Street bridge to remain after relocation and to be removed by ODOT contractor. Relocation work to be completed by December 31, 2025. The contact on this project Breck Cowan at 513-565-7187.

Duke Energy Electric Distribution

Duke Energy Electric has facilities within project limits. Conduit crossing interstate at approximately Sta. 758+50 of Centerline of Winchell will be rerouted and abandoned. Duke Energy will be rerouting to Linn Street to Liberty Street to Western Avenue with a combination of overhead and underground. This work will be complete by February 28, 2026.

The Duke electric lines along the south side of Gest Street will likely conflict with the clearance requirements for construction equipment for removal and/or installation of the Linn Street bridge. Contractor must maintain at least 20 feet of clearance between equipment and electric lines. If clearance cannot be maintained, Contractor must reach out to Duke a minimum of thirty (30) days prior to work commencing for Duke to de-energize the lines.

The contact on this project is Shane Erhart at 513-508-9609.

Duke Energy - Gas

Duke Energy Gas has facilities within the project limits. There are conflicts on Court Street with relocation plans to eliminate conflicts with new work. This work will be completed by February 1, 2026.

Duke also has a main that is in conflict with the south abutment of the Linn Street bridge. Duke will relocate this main and work will be complete by February 1, 2026. The contact on this project is Brian Hollmann at 513-906-0128.

Greater Cincinnati Water Works

Greater Cincinnati Water Works (GCWW) has facilities within project limits. GCWW will relocate their 36" main to a 42" main along the east side of I-75. GCWW will cross under I-75 to the north of Linn Street and then run of Gest Street before tying in. Water main at Court Street to be relocated to avoid conflicts. This work will be complete by July 1, 2026. Bore pit areas as shown in the plans are not available until July 2026. The contact on this project is Dan Louis at 513-352-3723.

Lumen

Lumen has facilities within project limits. Lumen's underground cable crossing just north of Linn Street bridge was placed via directional drilling. Their conduits are deep enough to not be in conflict with the bridge removal and construction of Wall No. 2. The contact on this project is Brad Lenhart at 419-234-1028.

Charter Communications

Charter has facilities within project limits. Charter is located on the Duke poles within the vicinity of the project. Charter will follow Duke's path. This work will be completed by April 30, 2026. The contact on this project is Kent Rieger at 513-386-5499.

Cincinnati Metropolitan Sewer District

Cincinnati Metropolitan Sewer District (MSD) has facilities within project limits. Relocation of sewer conduits are included in the plans for Court Street to address conflicts. The contact on this project is Ray Schork at 513-244-3914.

MCI/Verizon

MCI/Verizon has facilities within project limits. MCI/Verizon has 2 lines that cross under I-75 just north of the Linn Street bridge. MCI/Verizon relocations will be required due to the construction of Wall No. 2 and the Linn St structure. The schedule for this relocation is to be determined by October 1, 2025. The contact on this project is Bob Dillow at 614-816-0361.

AT&T Metro/LNS

AT&T Metro / LNS has facilities within project limits. AT&T will relocate their line that crosses under I-75 in the existing Duke trench. This work will be completed on or before October 31, 2026. The contact on this project is Tim Lapointe at 281-352-3631.

Windstream-KDL

Windstream has facilities within project limits. Windstream will relocate their line that crosses under I-75 in the existing Duke trench. This work will be completed on or before October 31, 2026. The contact on this project is Leon Taylor at 937-260-3062.

Crown Castle Fiber

Crown Castle Fiber has facilities within project limits. Crown Castle will relocate their line that is currently attached to the Linn Street bridge. The schedule for this relocation is to be determined by October 1, 2025. contact on this project is Craig Snell at 513-898-1595.

Zayo Bandwidth

Zayo Bandwidth has facilities within project limits. Zayo Bandwidth is located within the Lumen conduits which are not in conflict. The contact on this project is Waylon Higgins at 765-341-1199.

AT&T Ohio

AT&T Ohio has existing facilities within project limits, not to be disturbed. The contact person is Alan Stutes at 937-708-1026.

AT&T Transmission

AT&T Transmission has facilities within project limits. AT&T will relocate their line that crosses under I-75 in the existing Duke trench. This work will be completed on or before October 31, 2026. The contact on this project is Chad Harkness at 770-584-7083.

Duke Energy Fiber

Duke Energy fiber has facilities within project limits. Duke fiber will relocate their line that crosses under I-75 in the existing Duke trench. This work will be completed on or before October 31, 2026. The contact on this project is Chris Gee.