

 GENERAL SUMMARY	
DESIGN AGENCY	
	
DESIGNER	
BCP	
REVIEWER	
GF	3-12-25
PROJECT ID	
122964	
SHEET	TOTAL
P.4	14

ESTIMATED QUANTITIES - STRUCTURE No.: HAM-22-1141 (SFN 3100901)										
ITEM	EXTENSION	TOTAL	UNIT	DESCRIPTION			ABUT.	PIERS	SUPER.	GEN. SEE SHEET #
202	11401	229	LB	PORTIONS OF STRUCTURE REMOVED, AS PER PLAN (SECONDARY MEMBERS)					229	P. 5
513	10201	399	LB	STRUCTURAL STEEL MEMBERS, LEVEL UF, AS PER PLAN					399	P. 5
513	95000	16	FT	STRUCTURAL STEEL, MISC.: REPAIR OF DAMAGED SECONDARY MEMBERS, FILLET WELDING						16 P. 5
513	95000	1.3	FT	STRUCTURAL STEEL, MISC.: REPAIR OF DAMAGED SECONDARY MEMBERS, COMPLETE PENETRATION WELDING						1.3 P. 6
513	95030	120	EACH	STRUCTURAL STEEL, MISC.: REPLACE SPLICE BOLTS						120 P. 6
514	20001	15	SF	FIELD PAINTING OF DAMAGED STRUCTURAL STEEL, AS PER PLAN (THREE COAT)						15 P. 5
516	47001		LS	JACKING AND TEMPORARY SUPPORT OF SUPERSTRUCTURE, AS PER PLAN						P. 5
843	50000	1	SF	PATCHING CONCRETE STRUCTURES WITH TROWELABLE MORTAR				1		P. 14
849	10000		LS	DAMAGE ASSESSMENT						
849	10500		LS	SURFACE PREPARATION						LS
849	10600	4	hour	REPAIRING DAMAGED MEMBERS BY GRINDING						4 P. 13
849	10700		LS	STRAIGHTENING DAMAGED MEMBERS						
885	00504	4	MNHR	GRINDING FINS, TEARS, SLIVERS ON EXISTING STRUCTURAL STEEL						4 P. 13

STRUCTURES SUBSUMMARY

DESIGN AGENCY



DESIGNER
BCP

REVIEWER
GF 3-12-25

PROJECT ID
122964

SHEET	TOTAL
P.8	14

