

SHEET NUMBER													PART.	ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION
	P.06	P.07			P.25	P.26	P.27			P.29	P.30		01/NFA					
																		ROADWAY
							1,907						1,907	202	23500	1,907	SY	WEARING COURSE REMOVED
		1,363											1,363	204	13000	1,363	CY	EXCAVATION OF SUBGRADE
		4,089											4,089	204	50000	4,089	SY	GEOTEXTILE FABRIC
						7.79							7.79	209	60500	7.79	MILE	LINEAR GRADING
						7.79							7.79	209	72051	7.79	MILE	PREPARING SUBGRADE FOR SHOULDER PAVING, AS PER PLAN
										2			2	SPECIAL	69050100	2	EACH	MAILBOX SUPPORT SYSTEM, SINGLE
										1			1	SPECIAL	69050200	1	EACH	MAILBOX SUPPORT SYSTEM, DOUBLE
																		EROSION CONTROL
		2											2	659	00100	2	EACH	SOIL ANALYSIS TEST
		16,000											16,000	659	10000	16,000	SY	SEEDING AND MULCHING
		800											800	659	14000	800	SY	REPAIR SEEDING AND MULCHING
		2.16											2.16	659	20000	2.16	TON	COMMERCIAL FERTILIZER
		3.31											3.31	659	31000	3.31	ACRE	LIME
		87											87	659	35000	87	MGAL	WATER
													8,000	832	30000	8,000	EACH	EROSION CONTROL
																		DRAINAGE
	LS												LS	611	97300	LS		CONDUIT, MISC.:REVIEW OF DRAINAGE FACILITIES
																		PAVEMENT
		1,363											1,363	304	20000	1,363	CY	AGGREGATE BASE
					6,088	474							6,562	407	10000	6,562	GAL	JACK COAT
						3,641							3,641	408	10001	3,641	GAL	PRIME COAT, AS PER PLAN
					1,916	159							2,075	441	10100	2,075	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (446), PG70-22M
					5,741	248							5,989	441	10200	5,989	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (446)
							84						84	441	70501	84	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (449), (DRIVEWAYS), AS PER PLAN
													1,015	617	10101	1,015	CY	COMPACTED AGGREGATE, AS PER PLAN
					55,087	2,278							57,365	827	10000	57,365	SY	PAVEMENT REMOVED
					1,922	79							2,001	827	11000	2,001	TON	CEMENT
					54,769	2,262							57,031	827	12000	57,031	SY	CURING COAT
					54,769	2,262							57,031	827	20000	57,031	SY	FULL DEPTH RECLAIMED BASE COURSE, 12" DEEP
													LS	827	21000	LS		MIXTURE DESIGN FOR FULL DEPTH RECLAIMED BASE
					273	14							287	827	22000	287	TON	CORRECTIVE MATERIAL
					400	19							419	827	23000	419	TON	COVER AGGREGATE
													LS	827	30000	LS		JUST-IN-TIME TRAINING
																		TRAFFIC CONTROL
										513			513	621	00100	513	EACH	RPM
										513			513	621	54000	513	EACH	RAISED PAVEMENT MARKER REMOVED
										9			9	630	03100	9	FT	GROUND MOUNTED SUPPORT, NO. 3 POST
										9			9	630	80100	9	SF	SIGN, FLAT SHEET
										1			1	630	84900	1	EACH	REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL
										1			1	630	86002	1	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL
										7.78			7.78	646	10010	7.78	MILE	EDGE LINE, 6"
										3.89			3.89	646	10200	3.89	MILE	CENTER LINE
										1			1	646	20000	1	EACH	RAILROAD SYMBOL MARKING
										134			134	646	20504	134	FT	DOTTED LINE, 6"

GENERAL SUMMARY

DESIGN AGENCY



DESIGNER

DMW

REVIEWER

SAH 04-01-25

PROJECT ID

107501

SHEET

P.13

TOTAL

30

SHOULDER DATA																																
COUNTY	ROUTE	STA		FEET	TYPICAL (SEE SHEET P.05)	PROPOSED WIDTH (FEET)				PAVEMENT AREA	209		407		408	441				617		827				COMMENTS	FUNDING					
											LINEAR GRADING	PREPARING SUBGRADE FOR SHOULDER PAVING, AS PER PLAN	TACK COAT		PRIME COAT, AS PER PLAN	IN.	ASPHALT CONCRETE SURFACE COURSE TYPE 1 (446), PG70-22M	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (446), (PG70-22M)	IN.	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (446)	IN.	COMPACTED AGGREGATE, AS PER PLAN	FULL DEPTH RECLAIMED BASE COURSE, 12 INCHES DEEP	PAVEMENT REMOVED	CURING COAT			CEMENT	CORRECTIVE MATERIAL	COVER AGGREGATE		
		LEFT	RIGHT			SQ. YD.	MILE	MILE	0.055 GAL/SY				0.085 GAL/SY	0.40 GAL/SY																	CU. YD.	CU. YD.
		FROM	TO			A	B	A	B	SQ. YD.	MILE	MILE	GAL	GAL	GAL																	
HOL	179	00+13.00	00+25.00	12	2	0.5		0.5		1			1	1		1 ¼	1	1	3 ¾	1				1								
HOL	179	0+25.00	34+19.00	3394	1	0.5	2.0	0.5	2.0	377	0.010	0.01	42	33		1 ¼	13	10	3 ¾	39	4	1	377	377	377	13	2	3				
HOL	179	34+19.00	34+33.00	14	2	0.5	2.0	0.5	2.0	2	0.01	0.01	1	1		1 ¼	1	1	3 ¾	1	4	1		2					BR. HOL-179-0.67			
HOL	179	34+33.00	50+87.00	1654	1	0.5	2.0	0.5	2.0	184	0.62	0.62	20	16		1 ¼	6	5	3 ¾	19	4	82	184	184	184	6	1	1				
HOL	179	50+87.00	50+93.00	6	2	0.5	2.0	0.5	2.0	1	0.01	0.01	1	1		1 ¼	1	1	3 ¾	1	4	1		1					CFN: 1805946			
HOL	179	50+93.00	59+63.00	870	1	0.5	2.0	0.5	2.0	97	0.32	0.32	11	9		1 ¼	3	2	3 ¾	10	4	43	97	97	97	3	1	1				
HOL	179	59+63.00	59+69.00	6	2	0.5	2.0	0.5	2.0	1			1	1		1 ¼	1	1	3 ¾	1	4	1		1					CFN: 1805945			
HOL	179	59+69.00	66+26.00	657	1	0.5	2.0	0.5	2.0	73			8	7		1 ¼	3	2	3 ¾	8	4	32	73	73	73	3	1	1				
HOL	179	66+26.00	66+40.00	14	2	0.5	2.0	0.5	2.0	2	0.01	0.01	1	1		1 ¼	1	1	3 ¾	1	4	1		2					BR. HOL-179-01.31			
HOL	179	66+40.00	88+33.00	2193	1	0.5	2.0	0.5	2.0	244	0.84	0.84	27	21		1 ¼	8	6	3 ¾	25			244	244	244	9	1	2				
HOL	179	88+33.00	88+54.00	21	2	0.5	2.0	0.5	2.0	2	0.01	0.01	1	1		1 ¼	1	1	3 ¾	1	4	1		2					BR. HOL-179-01.67			
HOL	179	88+54.00	112+33.00	2379	1	0.5	2.0	0.5	2.0	264	0.90	0.90	30	23		1 ¼	9	7	3 ¾	28	4	117	264	264	264	9	1	2				
HOL	179	112+33.00	112+40.00	7	2	0.5	2.0	0.5	2.0	1	0.01	0.01	1	1		1 ¼	1	1	3 ¾	1	4	1		1					CFN: 1805943			
HOL	179	112+40.00	135+16.00	2276	1	0.5	2.0	0.5	2.0	253	0.86	0.86	28	22		1 ¼	9	6	3 ¾	26	4	112	253	253	253	9	1	2				
HOL	179	135+16.00	135+22.00	6	2	0.5	2.0	0.5	2.0	1	0.01	0.01	1	1		1 ¼	1	1	3 ¾	1	4	1		1					CFN: 1976237			
HOL	179	135+22.00	138+02.00	280	1	0.5	2.0	0.5	2.0	31	0.10	0.10	4	3		1 ¼	2	1	3 ¾	4			31	31	31	1	1	1				
HOL	179	138+02.00	138+10.00	8	2	0.5	2.0	0.5	2.0	1	0.01	0.01	1	1		1 ¼	1	1	3 ¾	1	4	1		1					CFN: 1810500			
HOL	179	138+10.00	166+75.00	2865	1	0.5	2.0	0.5	2.0	318	1.08	1.08	35	28		1 ¼	11	8	3 ¾	33	4	141	318	318	318	11	2	2				
HOL	179	166+75.00	167+05.00	30	2	0.5	2.0	0.5	2.0	3	0.01	0.01	1	1		1 ¼	1	1	3 ¾	1	4	1		3					CFN: 1996275			
HOL	179	167+05.00	169+65.00	260	1	0.5	2.0	0.5	2.0	29	0.10	0.10	4	3		1 ¼	2	1	3 ¾	4	4	13	29	29	29	1	1	1				
HOL	179	169+65.00	169+71.00	6	2	0.5	2.0	0.5	2.0	1	0.01	0.01	1	1		1 ¼	1	1	3 ¾	1	4	1		1					CFN: 1805941			
HOL	179	169+75.00	205+00.00	3525	1	0.5	2.0	0.5	2.0	392	1.34	1.34	44	34		1 ¼	14	10	3 ¾	41	4	174	392	392	392	14	2	3				
TOTALS CARRIED TO GENERAL SUMMARY											7.79	7.79	474		3,641		159		248		1,015	2,262	2,278	2,262	79	14	19				01/NFA	

