



LAW-7-2.17

	<u>Length</u>	<u>Width</u>	<u>Height</u>	<u>No.</u>	<u>Total</u>	<u>Unit</u>	<u>Sheet No.</u>
Item 203, Excavation	24.00	3515.00		1	3124	cy	1
Item 503, Unclassified Excavation							3 & 7
Inlet	2027.00		11.00	1	826	cy	
Outlet	332.00		10.00	1	123	cy	
					949	cy	
Item 509, Epoxy Coated Steel Reinforcement						lb	8 & 9
Item 511, Class QC1 Concrete, Retaining/Wingwall Not Including Footing							4 & 7
Inlet	91.25	2.00	27.00	1.0	183	cy	
	24.00	2.00	13.00	-0.5	-12		
	38.00	2.00	12.00	-0.5	-17		
	380.13	1.00	2.00	-1.0	-28		
Outlet		1258.66		1	47	cy	
					173	cy	
Item 511, Class QC1 Concrete, Footing							3
Inlet	1783.75		3.00	1	198	cy	
Key	89.00	2.00	3.00	1	20	cy	
					218	cy	
Item 512, Type A Waterproofing	448.00	1.00	57.61	1	2868	sy	
Item 512, Sealing of Concrete Surfaces (Epoxy-Urethane)							5 & 7
Inlet	1268.10		1.00	1	141	sy	
Outlet	136.24		1.00	1	39	sy	
					180	sy	
Item 518, Porous Backfill with Geotextile Fabric	75.91	2.00	13.23	1	74	cy	3
Item 518, 6" Perforated Corrugated Plastic Pipe							3
	28.70	1.00	1.00	1	29	ft	
	45.55	1.00	1.00	1	46	ft	
					74	ft	
Item 518, 6" Non-Perforated Corrugated Plastic Pipe, including Specials	15.00	1.00	1.00	2	30	ft	3
Item 601, Riprap, Type D, As Per Plan	970.00 sf		1.00	1	108	sy	1
Item 601, Rock Channel Protection, Type B with Geotextile Fabric							1
Inlet	1086.00		2.50	1	101	cy	
Outlet	2385.72		2.50	1	221	cy	
					321	cy	
Item 601, Rock Channel Protection, Type C without filter	452.00	46.70		1	782	cy	1
Item 611, Conduit, Misc.: 22' Dia., Type A, 707.03, As Per Plan	452.00	1.00	1.00	1	452	ft	1