



OHIO DEPARTMENT OF TRANSPORTATION

PLANNING & ENGINEERING DEPARTMENT, DISTRICT 4



Project **MAH-680-4.58**

Desc Retaining Wall Sealing


Calc By **MA** Date 9/10/25

Chk By _____ Date _____

PID/PROJ **121474**


- Seal face and top of wall
- Top of wall $\approx 1.5'$

Ramp L (Market St. to I-680 WB)



$$945 - 923.5 = 21.5'$$

$$x = \sqrt{21.5^2 + 117.89^2} = \sqrt{462.25 + 13,898.05} = 119.83'$$



$$944.83 - 943.18 = 1.65'$$

$$y = \sqrt{1.65^2 + 10^2} = 10.14'$$

$$A_L = (117.89' \times 3.86') + \frac{1}{2} (117.89' \times 21.5') + (21.5' \times 21.5') + (10' \times 21.5') - \frac{1}{2} (1.65' \times 10') + 1.5' (3.86' + 119.83' + 21.5' + 10.14')$$

rectangle
under
triangle

top of wall

$$= 455.06 + 1,267.32 + 462.25 + 215 - 8.25 + 232.99$$

$$= 2,624.37 \text{ SF}$$

$$\approx \boxed{292 \text{ SY}}$$



OHIO DEPARTMENT OF TRANSPORTATION
PLANNING & ENGINEERING DEPARTMENT, DISTRICT 4



Project **MAH-680-4.58**

Desc _____

Calc By **MA** Date _____

Chk By _____ Date _____

PID/PROJ **121474**

Ramp K (I-680 EB to Market St.)

$L = 404.57'$

First 227.45' :

$h_{avg} \approx 21'$

$$A_1 = (227.45 \times 21') + (1.5' \times 227.45') = 4,776.45 + 341.18 = \underline{5,117.63 \text{ SF}}$$

Last 177.12' :

$h_{avg} \approx 12.5'$

$$A_2 = (177.12' \times 12.5') + (1.5' \times 177.12') = 2,214 + 265.68 = \underline{2,479.68 \text{ SF}}$$

$$A_K = A_1 + A_2 = 5,117.63 + 2,479.68 = 7,597.31 \text{ SF}$$

$\approx \boxed{845 \text{ SY}}$



OHIO DEPARTMENT OF TRANSPORTATION
PLANNING & ENGINEERING DEPARTMENT, DISTRICT 4



Project **MAH-680-4.58**

Desc _____

Calc By **MA** Date _____

Chk By _____ Date _____

PID/PROJ **121474**

Ramp N (Woodward Rd to I-680 WB between Market St. and Woodland Ave. bridges)

First 120' :

$h_{avg} \approx 24.5'$ (assuming ground is 1' above footer)

$$A_1 = (24.5' \times 120') + (1.5' \times 120') = 2,940 + 180 = \underline{3,120 \text{ SF}}$$

Next 150' :

$h_{avg} \approx 25.5'$

$$A_2 = (25.5' \times 150') + (1.5' \times 150') = \underline{4,050 \text{ SF}}$$

Last 120' :

$h_{avg} \approx 21.5'$

$$A_3 = (21.5' \times 120') + (1.5' \times 120') = \underline{3,450 \text{ SF}}$$

$$A_N = A_1 + A_2 + A_3 = 10,620 \text{ SF} = \boxed{1,180 \text{ SY}}$$



OHIO DEPARTMENT OF TRANSPORTATION
PLANNING & ENGINEERING DEPARTMENT, DISTRICT 4



Project **MAH-680-4.58**

Desc _____

Calc By **MA** Date _____

Chk By _____ Date _____

PID/PROJ **121474**

Ramp M (I-680 EB to Market St.)

First 120':

avg $\approx 25'$


$$A_1 = (25' \times 120') + (1.5' \times 120') = \underline{530 \text{ SF}}$$

Next 120':

avg $\approx 23'$

$$A_2 = (23' \times 120') + (1.5' \times 120') = \underline{2,940 \text{ SF}}$$

Last 83.25'



$$961.20 - 944.56 = 16.64'$$

$$x = \sqrt{16.64^2 + 31.35^2} = \sqrt{276.89 + 982.82} = 35.49'$$

avg of rectangle $\approx 21'$

assumed exposed below triangle

top of wall

$$A_3 = \frac{1}{2}(31.35 \times 16.64) + (31.35 \times 21') + (21' \times 52') + 1.5'(21' + 31.35' + 52')$$

$$= 260.83 + 62.70 + 1,092 + 128.03 = 1,543.56 \text{ SF}$$

$$\approx \boxed{1725 \text{ SF}}$$