GENERAL SUMMARY

SHEET NUM.													PART.	ITEM	ITEM	GRAND	UNIT	DESCRIPTION	SEE SHEET
OFFICE CALCS	P.5	P.7	P.8	P.31	P.32	P.105	P.106	P.107	P.116				01/SAF/21		EXT	TOTAL			NO.
																		ROADWAY	
													LS	201	11000	LS		CLEARING AND GRUBBING	P.5
616				75									691	202	23000	691	SY	PAVEMENT REMOVED	
				285									285	202	30700	285	FT	CONCRETE BARRIER REMOVED	
				216									216	202	30701	216	FT	CONCRETE BARRIER REMOVED, AS PER PLAN	P.6
				275									275	202	32601	275	FT	GUTTER REMOVED, AS PER PLAN	P.6
				95	10								105	202	35100	105	FT	PIPE REMOVED, 24" DIAMETER AND UNDER	
					1								1	202	98100	1	EACH	REMOVAL MISC.:PRECAST REINFORCED CONCRETE OUTLET	P.41
				173									173	202	38000	173	FT	GUARDRAIL REMOVED	
					1								1	202	58100	1	EACH	CATCH BASIN REMOVED	
				10									10	202	75000	10	FT	FENCE REMOVED	
				20									20	202	75200	20	FT	FENCE REMOVED FOR REUSE EXIST R/W WIRE FENCE & END POST	
				2									2	202	98100	2	EACH	REMOVAL MISC.: BOLLARD	
				1									1	202	98100	1	EACH	REMOVAL MISC.:EXIST WOOD POST	
841													841	203	10000	841	CY	EXCAVATION	
1,166													1,166	203	20000	1,166	CY	EMBANKMENT	
2,118													2,118	204	10000	2,118	SY	SUBGRADE COMPACTION	
	2												2	204	45000	2	HOUR	PROOF ROLLING	
1,179				1,168									2,347	255	20000	2,347	FT	FULL DEPTH PAVEMENT SAWING	
				25									25	606	15050	25	FT	GUARDRAIL, TYPE MGS	
				2									2	606	35002	2	EACH	MGS BRIDGE TERMINAL ASSEMBLY, TYPE 1	
				2									2	606	60028	2	EACH	IMPACT ATTENUATOR, TYPE 2 (BIDIRECTIONAL) 35 MPH, 24" WIDE	
				2									2	606	60022	2	EACH	IMPACT ATTENUATOR, TYPE 2 (UNIDIRECTIONAL) 35 MPH, 60" WIDE	
3,844													3,844	608	10000	3,844	SF	4" CONCRETE WALK	
				892									892	608	52000	892	SF	CURB RAMP	
				30									30	609	26000	30	FT	CURB, TYPE 6	
				2									2	622	10201	2	EACH	BARRIER TRANSITION, AS PER PLAN	P.6
													LS	878	25000	LS		INSPECTION AND COMPACTION TESTING OF UNBOUND MATERIALS	
																		EROSION CONTROL	
					3.6								3.6	601	21050	3.6	SY	TIED CONCRETE BLOCK MAT WITH TYPE 1 UNDERLAYMENT	
267					5.6								272.6	601	32100	272.6	CY	ROCK CHANNEL PROTECTION, TYPE B WITH FILTER	
	2												2	659	00100	2	EACH	SOIL ANALYSIS TEST	
	706				98								804	659	00300	804	CY	TOPSOIL	
	6,359												6,359	659	00500	6,359	SY	SEEDING AND MULCHING, CLASS 1	
	318												318	659	14000	318	SY	REPAIR SEEDING AND MULCHING	
	318												318	659	15000	318	SY	INTER-SEEDING	
	0.89												0.89	659	20000	0.89	TON	COMMERCIAL FERTILIZER	
	1.32												1.32	659	31000	1.32	ACRE	LIME	
	36												36	659	35000	36	MGAL	WATER	
					884								884	670	00500	884	SY	SLOPE EROSION PROTECTION	
													LS	832	15000	LS		STORM WATER POLLUTION PREVENTION PLAN	
													LS	832	15002	LS		STORM WATER POLLUTION PREVENTION INSPECTIONS	
													LS	832	15010	LS		STORM WATER POLLUTION PREVENTION INSPECTION SOFTWARE	
30,000													30,000	832	30000	30,000	EACH	EROSION CONTROL	
																		DRAINAGE	
					0.49								0.49	511	46610	0.49	CY	CLASS QC1 CONCRETE, HEADWALL	
					5								5	518	42010	5	FT	8" NON-PERFORATED CORRUGATED PLASTIC PIPE, INCLUDING SPECIALS	
					273								273	601	38000	273	FT	PAVED GUTTER, TYPE 1-4	
					468								468	605	14000	468	FT	6" BASE PIPE UNDERDRAINS	
					32								32	611	00510	32	FT	6" CONDUIT, TYPE F FOR UNDERDRAIN OUTLETS	
					144								144	611	04400	144	FT	12" CONDUIT, TYPE B	
					9								9	611	04600	9	FT	12" CONDUIT, TYPE C	
					267								267	611	52204	267	FT	14" X 23" CONDUIT, TYPE C, 706.04	
					1								1	611	98180	1	EACH	CATCH BASIN, NO. 3A	
					4								4	611	98470	4	EACH	CATCH BASIN, NO. 2-2B	
					5								5	611	98635	5	EACH	CATCH BASIN RECONSTRUCTED TO GRADE, AS PER PLAN	P.6
					5								5	611	99574	5	EACH	MANHOLE, NO. 3	
					5								5	611	99654	5	EACH	MANHOLE ADJUSTED TO GRADE	

MAR-95-17.90

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/30/2026 TIME: 12:05:35 PM USER: bshepherd
E:\ODOT\21-00473-010 MAR-95-17.90\114818\400-Engineering\Roadway\Sheets\114818_GG001.dgn

DESIGN AGENCY
Environmental Design Group

DESIGNER
WES

REVIEWER
JES 03/24/25

PROJECT ID
114818

SHEET P.28 | TOTAL P.142