| SHEET NUM. | | | | | | | | | | | | | PART. | ITEM | ITEM | GRAND | UNIT | DESCRIPTION | SEE SHEET NO. |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| OFFICE CALCS | P.5 | P.7 | P.8 | P.31 | P.32 | P.105 | P.106 | P.107 | P.116 | | | | 01/SAF/21 | | EXT | TOTAL | | | |
| | | | | | | | | | | | | | | | | | | **ROADWAY** | |
| | | | | | | | | | | | | | LS | 201 | 11000 | LS | | CLEARING AND GRUBBING | P.5 |
| 616 | | | | 75 | | | | | | | | | 691 | 202 | 23000 | 691 | SY | PAVEMENT REMOVED | |
| | | | | 285 | | | | | | | | | 285 | 202 | 30700 | 285 | FT | CONCRETE BARRIER REMOVED | |
| | | | | 216 | | | | | | | | | 216 | 202 | 30701 | 216 | FT | CONCRETE BARRIER REMOVED, AS PER PLAN | P.6 |
| | | | | 275 | | | | | | | | | 275 | 202 | 32601 | 275 | FT | GUTTER REMOVED, AS PER PLAN | P.6 |
| | | | | 95 | 10 | | | | | | | | 105 | 202 | 35100 | 105 | FT | PIPE REMOVED, 24" DIAMETER AND UNDER | |
| | | | | | 1 | | | | | | | | 1 | 202 | 98100 | 1 | EACH | REMOVAL MISC.:PRECAST REINFORCED CONCRETE OUTLET | P.41 |
| | | | | 173 | | | | | | | | | 173 | 202 | 38000 | 173 | FT | GUARDRAIL REMOVED | |
| | | | | | 1 | | | | | | | | 1 | 202 | 58100 | 1 | EACH | CATCH BASIN REMOVED | |
| | | | | 10 | | | | | | | | | 10 | 202 | 75000 | 10 | FT | FENCE REMOVED | |
| | | | | 20 | | | | | | | | | 20 | 202 | 75200 | 20 | FT | FENCE REMOVED FOR REUSE EXIST R/W WIRE FENCE & END POST | |
| | | | | 2 | | | | | | | | | 2 | 202 | 98100 | 2 | EACH | REMOVAL MISC.: BOLLARD | |
| | | | | 1 | | | | | | | | | 1 | 202 | 98100 | 1 | EACH | REMOVAL MISC.:EXIST WOOD POST | |
| 841 | | | | | | | | | | | | | 841 | 203 | 10000 | 841 | CY | EXCAVATION | |
| 1,166 | | | | | | | | | | | | | 1,166 | 203 | 20000 | 1,166 | CY | EMBANKMENT | |
| 2,118 | | | | | | | | | | | | | 2,118 | 204 | 10000 | 2,118 | SY | SUBGRADE COMPACTION | |
| | 2 | | | | | | | | | | | | 2 | 204 | 45000 | 2 | HOUR | PROOF ROLLING | |
| 1,179 | | | | 1,168 | | | | | | | | | 2,347 | 255 | 20000 | 2,347 | FT | FULL DEPTH PAVEMENT SAWING | |
| | | | | 25 | | | | | | | | | 25 | 606 | 15050 | 25 | FT | GUARDRAIL, TYPE MGS | |
| | | | | 2 | | | | | | | | | 2 | 606 | 35002 | 2 | EACH | MGS BRIDGE TERMINAL ASSEMBLY, TYPE 1 | |
| | | | | 2 | | | | | | | | | 2 | 606 | 60028 | 2 | EACH | IMPACT ATTENUATOR, TYPE 2 (BIDIRECTIONAL) 35 MPH, 24" WIDE | |
| | | | | 2 | | | | | | | | | 2 | 606 | 60022 | 2 | EACH | IMPACT ATTENUATOR, TYPE 2 (UNIDIRECTIONAL) 35 MPH, 60" WIDE | |
| 3,844 | | | | | | | | | | | | | 3,844 | 608 | 10000 | 3,844 | SF | 4" CONCRETE WALK | |
| | | | | 892 | | | | | | | | | 892 | 608 | 52000 | 892 | SF | CURB RAMP | |
| | | | | 30 | | | | | | | | | 30 | 609 | 26000 | 30 | FT | CURB, TYPE 6 | |
| | | | | 2 | | | | | | | | | 2 | 622 | 10201 | 2 | EACH | BARRIER TRANSITION, AS PER PLAN | P.6 |
| | | | | | | | | | | | | | LS | 878 | 25000 | LS | | INSPECTION AND COMPACTION TESTING OF UNBOUND MATERIALS | |
| | | | | | | | | | | | | | | | | | | **EROSION CONTROL** | |
| | | | | | 3.6 | | | | | | | | 3.6 | 601 | 21050 | 3.6 | SY | TIED CONCRETE BLOCK MAT WITH TYPE 1 UNDERLAYMENT | |
| 267 | | | | | 5.6 | | | | | | | | 272.6 | 601 | 32100 | 272.6 | CY | ROCK CHANNEL PROTECTION, TYPE B WITH FILTER | |
| | 2 | | | | | | | | | | | | 2 | 659 | 00100 | 2 | EACH | SOIL ANALYSIS TEST | |
| | 706 | | | | 98 | | | | | | | | 804 | 659 | 00300 | 804 | CY | TOPSOIL | |
| | 6,359 | | | | | | | | | | | | 6,359 | 659 | 00500 | 6,359 | SY | SEEDING AND MULCHING, CLASS 1 | |
| | 318 | | | | | | | | | | | | 318 | 659 | 14000 | 318 | SY | REPAIR SEEDING AND MULCHING | |
| | 318 | | | | | | | | | | | | 318 | 659 | 15000 | 318 | SY | INTER-SEEDING | |
| | 0.89 | | | | | | | | | | | | 0.89 | 659 | 20000 | 0.89 | TON | COMMERCIAL FERTILIZER | |
| | 1.32 | | | | | | | | | | | | 1.32 | 659 | 31000 | 1.32 | ACRE | LIME | |
| | 36 | | | | | | | | | | | | 36 | 659 | 35000 | 36 | MGAL | WATER | |
| | | | | | 884 | | | | | | | | 884 | 670 | 00500 | 884 | SY | SLOPE EROSION PROTECTION | |
| | | | | | | | | | | | | | LS | 832 | 15000 | LS | | STORM WATER POLLUTION PREVENTION PLAN | |
| | | | | | | | | | | | | | LS | 832 | 15002 | LS | | STORM WATER POLLUTION PREVENTION INSPECTIONS | |
| | | | | | | | | | | | | | LS | 832 | 15010 | LS | | STORM WATER POLLUTION PREVENTION INSPECTION SOFTWARE | |
| 30,000 | | | | | | | | | | | | | 30,000 | 832 | 30000 | 30,000 | EACH | EROSION CONTROL | |
| | | | | | | | | | | | | | | | | | | **DRAINAGE** | |
| | | | | | 0.49 | | | | | | | | 0.49 | 511 | 46610 | 0.49 | CY | CLASS QC1 CONCRETE, HEADWALL | |
| | | | | | 5 | | | | | | | | 5 | 518 | 42010 | 5 | FT | 8" NON-PERFORATED CORRUGATED PLASTIC PIPE, INCLUDING SPECIALS | |
| | | | | | 273 | | | | | | | | 273 | 601 | 38000 | 273 | FT | PAVED GUTTER, TYPE 1-4 | |
| | | | | | 468 | | | | | | | | 468 | 605 | 14000 | 468 | FT | 6" BASE PIPE UNDERDRAINS | |
| | | | | | 32 | | | | | | | | 32 | 611 | 00510 | 32 | FT | 6" CONDUIT, TYPE F FOR UNDERDRAIN OUTLETS | |
| | | | | | 144 | | | | | | | | 144 | 611 | 04400 | 144 | FT | 12" CONDUIT, TYPE B | |
| | | | | | 9 | | | | | | | | 9 | 611 | 04600 | 9 | FT | 12" CONDUIT, TYPE C | |
| | | | | | 267 | | | | | | | | 267 | 611 | 52204 | 267 | FT | 14" X 23" CONDUIT, TYPE C, 706.04 | |
| | | | | | 1 | | | | | | | | 1 | 611 | 98180 | 1 | EACH | CATCH BASIN, NO. 3A | |
| | | | | | 4 | | | | | | | | 4 | 611 | 98470 | 4 | EACH | CATCH BASIN, NO. 2-2B | |
| | | | | | 5 | | | | | | | | 5 | 611 | 98635 | 5 | EACH | CATCH BASIN RECONSTRUCTED TO GRADE, AS PER PLAN | P.6 |
| | | | | | 5 | | | | | | | | 5 | 611 | 99574 | 5 | EACH | MANHOLE, NO. 3 | |
| | | | | | 5 | | | | | | | | 5 | 611 | 99654 | 5 | EACH | MANHOLE ADJUSTED TO GRADE | |

# GENERAL SUMMARY

MAR-95-17.90

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/30/2026 TIME: 12:05:35 PM USER: bshepherd
E:\ODOT\21-00473-010 MAR-95-17.90\114818\400-Engineering\Roadway\Sheets\114818_GG001.dgn

DESIGN AGENCY
Environmental Design Group

DESIGNER
WES

REVIEWER
JES 03/24/25

PROJECT ID
114818

SHEET P.28 | TOTAL P.142