

DRAINAGE SUBSUMMARY

SHEET NO.	REFERENCE NO.	STATION			202	202	202	511	518	601		605	611										638	659	670												
		FROM	TO	SIDE	PIPE REMOVED, 24" AND UNDER FT	CATCH BASIN REMOVED EACH	PRECAST REINFORCED CONCRETE OUTLET REMOVED EACH	CLASS QC1 CONCRETE, HEADWALL CY	8" CORRUGATED POLYPROPYLENE SMOOTH LINED PIPE FT	ROCK CHANNEL PROTECTION, TYPE B WITH FILTER CY	TIED CONCRETE BLOCK MAT WITH TYPE 1 UNDERLAYMENT SY	PAVED GUTTER TYPE 1-4 FT	6" BASE PIPE UNDERDRAINS FT	6" CONDUIT, TYPE F FOR UNDERDRAIN OUTLETS FT	12" CONDUIT, TYPE B FT	12" CONDUIT, TYPE C FT	14" X 23" CONDUIT, TYPE C, 706.04 FT	CATCH BASIN, NO. 3A EACH	CATCH BASIN, NO. 2-2B EACH	CATCH BASIN RECONSTRUCTED TO GRADE, AS PER PLAN EACH	MANHOLE, NO. 3 EACH	MANHOLE ADJUSTED TO GRADE EACH	PRECAST REINFORCED CONCRETE OUTLET EACH	4" POLYVINYL CHLORIDE COMPOSITE PIPE FT	TOPSOIL CY	SLOPE EROSION PROTECTION SY											
P.34	D1	937+00.79		LT		1														1																	
P.34	D2	937+02.53		LT																																	
P.34	D3	939+26.12		LT																																	
P.34	D4	939+28.25		LT																																	
P.34	D5	939+08.06		LT																																	
P.34	D6	939+08.16	939+94.88	LT																																	
P.34	D7	939+94.88	941+82.99	LT																																	
P.34	D8	937+99.08		LT																																	
P.34	D9	8+47.90		LT																																	
P.34	D10	10+65.51		LT																																	
P.36	D15	941+82.99	942+01.84	LT																																	
P.36	D16	942+01.84		LT				0.20		5.6																											
P.41	D20	952+03.05	952+12.90	LT	10			0.29																													
P.41	D21	949+24.75	951+97.70	LT																																	
US 23 RAMP B																																					
P.78	E1	536+00.00	538+78.00	LT																																	
P.78	UD1	534+50.00	535+69.00	RT								1.8		119	10																						
P.78	UD2	536+00.00	539+38.95	RT								1.8		339	22																						
JAMES WAY																																					
P.90	D25	8+30.43		RT																																	
P.90	D26	8+47.90		LT																																	
P.90	D27	9+28.32		RT																																	
P.90	D28	9+06.89	9+28.32	LT																																	
P.90	D29	9+27.98		RT																																	
AMERICAN BLVD																																					
P.94	D35	3+07.00		LT																																	
P.94	D36	3+07.00		RT																																	
SR-95																																					
P.41	D40	953+02.24		LT																																	
P.41	D41	953+02.24	953+22.16	LT																																	
P.41	D42	953+02.24	953+03.13	LT																																	
P.41	D43	953+02.24	953+04.03	LT																																	
P.41	D44	953+02.24	952+98.23	LT																																	
<b>TOTALS CARRIED TO GENERAL SUMMARY</b>					10	1	1	0.49	5	5.6	3.6	273	468	32	144	9	267	1	4	5	5	2	6		98		884										

DRAINAGE SUBSUMMARY

DESIGN AGENCY  
**Environmental Design Group**  
 1000 S. GLENN AVENUE, COLUMBIA, SC 29904  
 P. 803.734.8800  
 F. 803.734.8801  
 WWW.EDGDESIGN.COM

DESIGNER  
 WES

REVIEWER  
 JES 03/24/25

PROJECT ID  
 114818

SHEET TOTAL  
 P.32 | P.142