


SHEET NUM.											PART.	ITEM	ITEM	GRAND	UNIT	DESCRIPTION	SEE SHEET NO.			
											01/NHS/13	EXT	TOTAL							
											11	13								
											6,410		6,410	202	11401	6,410	LB	STRUCTURE OVER 20 FOOT SPAN (MAR-231-3.42)	9	
											140		140	202	11401	140	LB	PORTIONS OF STRUCTURE REMOVED, AS PER PLAN (SECONDARY MEMBERS)	9	
												0.1	0.1	511	34410	0.1	CY	CLASS QC2 CONCRETE, SUPERSTRUCTURE, REPAIR		
											6,410		6,410	513	10201	6,410	LB	STRUCTURAL STEEL MEMBERS, LEVEL UF, AS PER PLAN (MAIN MEMBERS)	9	
											418		418	513	10201	418	LB	STRUCTURAL STEEL MEMBERS, LEVEL UF, AS PER PLAN (SECONDARY MEMBERS)	9	
														44	514	20001	44	SF	FIELD PAINTING OF DAMAGED STRUCTURAL STEEL, AS PER PLAN	9
														485	514	80020	485	SF	SHOP PAINTING AND FIELD TOUCH-UP OF STRUCTURAL STEEL	
											LS		LS	516	47001	LS		JACKING AND TEMPORARY SUPPORT OF SUPERSTRUCTURE, AS PER PLAN	9	
														129	519	11100	129	SF	PATCHING CONCRETE STRUCTURE	
														LS	849	10000	LS	DAMAGE ASSESSMENT		
														LS	849	10500	LS	SURFACE PREPARATION		
											LS		LS	849	10700	LS		STRAIGHTENING DAMAGED MEMBERS		
														LS	SPECIAL	53000200	LS	STRUCTURES, MISC, AS PER PLAN.: REMOVAL AND TESTING	9	

ESTIMATED STRUCTURE QUANTITIES
 BRIDGE NO. MAR-231-3.42
 OH 231 OVER US 23

SFN
 5103215
 DESIGN AGENCY



DESIGNER: CAB
 CHECKER: JM
 REVIEWER: DRO 03/13/25
 PROJECT ID: 122349
 SUBSET: 3 | TOTAL: 6
 SHEET: P.10 | TOTAL: P.13