

ESTIMATED QUANTITIES									
ITEM	EXTENSION	TOTAL	UNIT	DESCRIPTION	ABUT.	PIERS	SUPER.	GEN.	SHEET #
202	11301	14	CY	PORTIONS OF STRUCTURE REMOVED, AS PER PLAN (SUPERSTRUCTURE)			14		
202	11401	561	LB	PORTIONS OF STRUCTURE REMOVED, AS PER PLAN (SECONDARY MEMBERS)			561		
202	11401	6,410	LB	PORTIONS OF STRUCTURE REMOVED, AS PER PLAN (MAIN MEMBERS)			6,410		
509	10000	2,526	LB	EPOXY COATED REINFORCING STEEL			2,526		
511	34410	6	CY	CLASS QC2 CONCRETE, SUPERSTRUCTURE			6		
511	34448	8	CY	CLASS QC2 CONCRETE, BRIDGE DECK (PARAPET)			8		
512	10050	43	SY	SEALING OF CONCRETE SURFACES (NON-EPOXY)			43		
512	10300	6	SY	SEALING OF CONCRETE BRIDGE DECKS WITH HMWM RESIN			6		
513	10201	561	LB	STRUCTURAL STEEL MEMBERS, LEVEL UF, AS PER PLAN			561		
513	10241	6,410	LB	STRUCTURAL STEEL MEMBERS, LEVEL 2, AS PER PLAN			6,410		
514	80020	486	SF	SHOP PAINTING AND FIELD TOUCH-UP OF STRUCTURAL STEEL					
516	47001		LS	JACKING TEMPORARY SUPPORT OF SUPERSTRUCTURE, AS PER PLAN					
530	00200		LS	STRUCTURES, MISC, AS PER PLAN.; EXISTING BEAM REMOVAL AND TESTING					13
607	98000	55	FT	FENCE, MISC.: VANDAL PROTECTION FENCE REMOVAL AND REPLACEMENT			55		
849	10000		LS	DAMAGE ASSESSMENT					
849	10500		LS	SURFACE PREPARATION					
849	10700		LS	STRAIGHTENING DAMAGED MEMBERS					