STATION RANGE			TYPICAL SECTION	SIDE	DISTANCE (D)	AVERAGE WIDTH (W)	SURFACE AREA (A) A=DxW/9	CADD GENERATED AREA	441 ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (449), PG64-22	407 NON-TRACKING TACK COAT	441 ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (449)	301 ASPHALT CONCRETE BASE, PG64-22, (449)	304 AGGREGATE BASE	204 SUBGRADE COMPACTION			452 13" NON-REINFORCED CONCRETE PAVEMENT, CLASS QC 1P WITH QC/QA									
					FT	FT	SQ YD	SQ YD	CY	GAL	CY	CY	CY	SY			SY									
℄ RW SR-41																										
423+34.09	TO	423+54.23		LT				7.00					2.00	7.00			7.00									
423+54.23	TO	430+35.14		LT				899.04	38.00	99.00	44.00	150.00	150.00	899.04												
430+18.73	TO	430+63.12		LT				22.87					4.00	22.87			22.87									
433+98.75	TO	434+54.39		LT				12.40	1.00	2.00	1.00	3.00	3.00													
437+84.91	TO	438+51.49		LT				53.71	3.00	6.00	3.00	9.00	9.00	65.71												
438+51.73	TO	440+20.56		LT				279.26						279.26			279.26									
								288.49					49.00													
								306.96																		
440+67.44	TO	440+94.42		LT				22.78					4.00	34.78			22.78									
440+84.25	TO	440+92.99		LT				1.05	1.00	1.00	1.00	1.00	1.00													
440+94.42	TO	441+11.25		LT				2.83	1.00	1.00	1.00	1.00	1.00													
BL CONST. RAMP D																										
494+38.36 (I 75)	TO	25+66.88		BOTH				6701.52									6701.52									
								6881.78					1147.00													
														7505.00												
							SUBTOTALS		44.00	109.00	50.00	164.00	1370.00	8813.66			7033.43									
							TOTALS CARRIED TO GENERAL SUMMARY		44	109	50	164	1370	8814			7034									