

SHEET NUMBER							PARTICIPATION	ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
P.05	P.07	P.08	P.13	P.14	P.15	P.20	01/NFA/10						
												ROADWAY	
			116	173			LUMP	201	11000	LUMP		CLEARING AND GRUBBING	
							289	202	75000	289	FOOT	FENCE REMOVED	
					194	443	637	203	10000	637	CUBIC YARD	EXCAVATION	
					39	217	256	203	20000	256	CUBIC YARD	EMBANKMENT	
			368	525			893	204	10000	893	CUBIC YARD	SUBGRADE COMPACTION	
1							1	204	45000	1	HOUR	PROOF ROLLING	
				50			50	606	15050	50	FOOT	GUARDRAIL, TYPE MGS	
			3	4			7	606	26150	7	EACH	ANCHOR ASSEMBLY, MGS TYPE E	
			4	4			8	606	35002	8	EACH	MGS BRIDGE TERMINAL ASSEMBLY, TYPE 1	
			117				117	607	98000	117	FOOT	FENCE, MISC.: 5-STRAND HIGH TENSILE	P.06
												EROSION CONTROL	
			55	81			136	601	28101	136	CUBIC YARD	DUMPED ROCK FILL, AS PER PLAN	P.05
10							10	601	32200	10	CUBIC YARD	ROCK CHANNEL PROTECTION, TYPE C WITH FILTER	
2							2	659	00100	2	EACH	SOIL ANALYSIS TEST	
116							116	659	00300	116	CUBIC YARD	TOPSOIL	
					187	855	1,042	659	10000	1,042	SQUARE YARD	SEEDING AND MULCHING	
52							52	659	14000	52	SQUARE YARD	REPAIR SEEDING AND MULCHING	
0.14							0.14	659	20000	0.14	TON	COMMERCIAL FERTILIZER	
0.22							0.22	659	31000	0.22	ACRE	LIME	
6							6	659	35000	6	M GALLON	WATER	
							5,000	832	30000	5,000	EACH	EROSION CONTROL	
												DRAINAGE	
50							50	611	01400	50	FOOT	6" CONDUIT, TYPE E	
50							50	611	01500	50	FOOT	6" CONDUIT, TYPE F	
50							50	611	01800	50	FOOT	8" CONDUIT, TYPE B	
												PAVEMENT	
			52	73			125	304	20000	125	CUBIC YARD	AGGREGATE BASE	
												STRUCTURE OVER 20 FOOT SPAN	
												MOE-TR183-0.13 ESTIMATED QUANTITIES SEE SHEET P.26	
												MOE-TR183-0.50 ESTIMATED QUANTITIES SEE SHEET P.37	
												TRAFFIC CONTROL	
			7	8			15	626	00110	15	EACH	BARRIER REFLECTOR, TYPE 2, BIDIRECTIONAL	
			39.6	50.4			90.0	630	03100	90.0	FOOT	GROUND MOUNTED SUPPORT, NO. 3 POST	
			12.0	12.0			24.0	630	80100	24.0	SQUARE FOOT	SIGN, FLAT SHEET	
				5			5	630	85200	5	EACH	REMOVAL OF GROUND MOUNTED SIGN AND DELIVERY	
				6			6	630	86002	6	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL	
												MAINTENANCE OF TRAFFIC	
			341				341	204	10000	341	CUBIC YARD	SUBGRADE COMPACTION	
			350	57			407	304	20000	407	CUBIC YARD	AGGREGATE BASE	
							LUMP	615	10001	LUMP		ROADS FOR MAINTAINING TRAFFIC, AS PER PLAN	P.07
												INCIDENTALS	
							LUMP	614	11000	LUMP		MAINTAINING TRAFFIC	
							LUMP	623	10000	LUMP		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
							LUMP	624	10000	LUMP		MOBILIZATION	