

ITEM 614, MAINTAINING TRAFFIC

A MINIMUM OF **1-LANE** OF TRAFFIC IN EACH DIRECTION SHALL BE MAINTAINED AT ALL TIMES BY USE OF THE EXISTING PAVEMENT AND STANDARD DRAWING **MT-97.12**.

TWO-WAY TRAFFIC SHALL BE MAINTAINED AT ALL TIMES EXCEPT THAT ONE-WAY TRAFFIC WILL BE PERMITTED FOR MINIMUM PERIODS OF TIME CONSISTENT WITH THE REQUIREMENTS OF THE SPECIFICATIONS FOR PROTECTION OF COMPLETED ASPHALT CONCRETE COURSES INCLUDING REPAIRS.

LENGTH AND DURATION OF LANE CLOSURES AND RESTRICTIONS SHALL BE AT THE APPROVAL OF THE ENGINEER. THE MAXIMUM LANE CLOSURE LENGTH SHALL BE PER **MT-97.12**. IT IS THE INTENT TO MINIMIZE THE IMPACT TO THE TRAVELING PUBLIC. LANE CLOSURES OR RESTRICTIONS OVER SEGMENTS OF THE PROJECT, IN WHICH NO WORK IS ANTICIPATED WITHIN A REASONABLE TIME FRAME, AS DETERMINED BY THE ENGINEER, SHALL NOT BE PERMITTED. THE LEVEL OF UTILIZATION OF MAINTENANCE OF TRAFFIC DEVICES SHALL BE COMMENSURATE WITH THE WORK IN PROGRESS.

ALL WORK AND TRAFFIC CONTROL DEVICES SHALL BE IN ACCORDANCE WITH CMS 614 AND OTHER APPLICABLE PORTIONS OF THE SPECIFICATIONS, AS WELL AS THE OHIO MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES. PAYMENT FOR ALL LABOR, EQUIPMENT AND MATERIALS SHALL BE INCLUDED IN THE LUMP SUM CONTRACT PRICE FOR ITEM 614, MAINTAINING TRAFFIC, UNLESS SEPARATELY ITEMIZED IN THE PLAN.



NOTIFICATION OF ROAD CLOSURE OR RESTRICTIONS

THE CONTRACTOR WILL ADVISE THE PROJECT ENGINEER A MINIMUM OF TWENTY-ONE (21) DAYS PRIOR TO THE FOLLOWING: THE START OF CONSTRUCTION ACTIVITIES, LANE RESTRICTIONS, LANE CLOSURES, AND/OR ROAD CLOSURES. THE PROJECT ENGINEER WILL FORWARD THIS INFORMATION TO THE FOLLOWING:

DISTRICT PUBLIC INFORMATION OFFICER (PIO) BY FAX AT (614) 887-4510 OR EMAIL AT D05.PIO@DOT.OHIO.GOV

DISTRICT PERMIT SECTION BY FAX AT (614) 887-4525 OR EMAIL AT BRIAN.BOSCH@DOT.OHIO.GOV

CENTRAL OFFICE SPECIAL HAUL PERMITS SECTION BY FAX AT (614) 728-4099 OR EMAIL AT HAULING.PERMITS@DOT.OHIO.GOV

THE PIO WILL, IN TURN, NOTIFY THE PUBLIC, THE LOCAL EMERGENCY SERVICES, AFFECTED SCHOOLS AND BUSINESSES, AND ANY OTHER IMPACTED LOCAL PUBLIC AGENCY OF ANY OF THE ABOVE-MENTIONED ITEMS, VIA MEDIA SOURCES.

COOPERATION BETWEEN CONTRACTORS

THE STATE OF OHIO HAS CONTRACTED PROJECT **PER-345-6.49 PID 117969**, WHICH MAY BE CONSTRUCTED CONCURRENTLY WITH THIS PROJECT. IT IS IMPERATIVE THAT THE CONTRACTORS COOPERATE FULLY WITH EACH OTHER AS OUTLINED IN SECTION 105.08 OF THE CMS MANUAL. ALL MAINTENANCE OF TRAFFIC SHALL BE COORDINATED BETWEEN PROJECTS AND NOT CONFLICT WITH ONE ANOTHER.

ITEM 614, WORK ZONE PAVEMENT MARKINGS

THE CONTRACTOR SHALL PLACE ALL WORK ZONE PAVEMENT MARKINGS IN ACCORDANCE WITH **CMS 614.11** AND STANDARD DRAWING **MT-99.20** UNLESS OTHERWISE DIRECTED BY THE ENGINEER. THE QUANTITIES BELOW ARE FOR PLACEMENT OF TEMPORARY MARKINGS ON THE SURFACE AND INTERMEDIATE COURSES. **THREE APPLICATIONS FOR CHIP SEAL (INITIAL REMOVE AND REPLACE, AFTER COMPLETED CHIP SEAL, AFTER COMPLETED FOG SEAL)**

ITEM 614, WORK ZONE CENTER LINE, CLASS III, 642 PAINT
LOCATION 1: 27.33 MILE

ITEM 614, WORK ZONE STOP LINE, CLASS III, 642 PAINT (STATE ROUTES ONLY)
LOCATION 1: 192 FT

ITEM 614, WORK ZONE MARKING SIGN

THE CONTRACTOR SHALL PLACE ALL WORK ZONE MARKING SIGNS IN ACCORDANCE WITH CMS SECTION **614.04**, UNLESS OTHERWISE DIRECTED BY THE ENGINEER.

W8-H12a (NO EDGE LINES):
LOCATION 1: 14 EACH

R4-2 (PASS WITH CARE):
LOCATION 1: 7 EACH

R4-1 (DO NOT PASS):
LOCATION 1: 11 EACH

ALL “NO EDGE LINES” SIGN LOCATIONS SHALL BE APPROVED BY THE ENGINEER PRIOR TO INSTALLATION.

PASSING ZONE CLOSURES LISTED ON SHEET 7 SHALL BE REFLECTED IN THE WORK ZONE SIGNING.

ITEM 614, WORK ZONE MARKING SIGN
LOCATION 1: 32 EACH

DESIGN AGENCY



DESIGNER

CWN

REVIEWER

JSL 10/16/25

PROJECT ID

109748

SHEET

P.3

TOTAL

11