

SHEET NUM.											PART. 01/SAF	ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
P6	P7	P13	P14	P15	P23	P24	P25	P30	OFFICE								
LS											LS	201	11000	LS		ROADWAY	
		353	11								364	202	23000	364	SY	CLEARING AND GRUBBING	
		2,113	42								2,155	202	30000	2,155	SF	PAVEMENT REMOVED	
		392	28								420	202	32000	420	FT	WALK REMOVED	
	104										104	202	98200	104	FT	CURB REMOVED	P7
				251							251	204	10000	251	SY	REMOVAL MISC.: POLYMER MODIFIED ASPHALT EXPANSION JOINT SYSTEM	
		1,920	140								2,060	608	10000	2,060	SF	SUBGRADE COMPACTION	
		396	305								701	608	52000	701	SF	4" CONCRETE WALK	
			80								80	608	52001	80	SF	CURB RAMP	P7
			22								22	608	53021	22	SF	CURB RAMP, AS PER PLAN	P7
			3								3	620	00501	3	EACH	DETECTABLE WARNING, AS PER PLAN	
			3								3	620	31200	3	EACH	DELINEATOR, POST GROUND MOUNTED, AS PER PLAN	P7
		1	2								3	623	39500	3	EACH	REMOVAL OF DELINEATOR	
	65										65	846	00110	65	CF	MONUMENT ASSEMBLY ADJUSTED TO GRADE	
																POLYMER MODIFIED ASPHALT EXPANSION JOINT SYSTEM	
																EROSION CONTROL	
	0.04										0.04	654	11000	0.04	TON	COMMERCIAL FERTILIZER	
	2										2	659	00100	2	EACH	SOIL ANALYSIS TEST	
	30										30	659	00300	30	CY	TOPSOIL	
	271										271	659	00500	271	SY	SEEDING AND MULCHING, CLASS 1	
	14										14	659	14000	14	SY	REPAIR SEEDING AND MULCHING	
	14										14	659	15000	14	SY	INTER-SEEDING	
	0.06										0.06	659	31000	0.06	ACRE	LIME	
	2										2	659	35000	2	MGAL	WATER	
	1										1	659	40000	1	MSF	MOWING	
									4,517		4,517	832	30000	4,517	EACH	EROSION CONTROL	
		2	8								10	611	98645	10	EACH	DRAINAGE	P7
																CATCH BASIN GRATE, AS PER PLAN	
																PAVEMENT	
				7,695							7,695	254	01000	7,695	SY	PAVEMENT PLANING, ASPHALT CONCRETE, 1.50"	
				57							57	301	56000	57	CY	ASPHALT CONCRETE BASE, PG64-22, (449)	
				42							42	304	20000	42	CY	AGGREGATE BASE	
				720							720	407	20000	720	GAL	NON-TRACKING TACK COAT	
				2							2	441	70000	2	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (449), PG64-22	
				15							15	441	70300	15	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (449)	
				330							330	442	00201	330	CY	ASPHALT CONCRETE SURFACE COURSE, 9.5 MM, TYPE A (446), AS PER PLAN, PG64-22	P7
		344	28								372	609	26000	372	FT	CURB, TYPE 6	
																TRAFFIC CONTROL	
							309				309	630	03100	309	FT	GROUND MOUNTED SUPPORT, NO. 3 POST	
							1				1	630	79600	1	EACH	SIGN SUPPORT ASSEMBLY, BRIDGE MOUNTED, TYPE 1	
							126				126	630	80100	126	SF	SIGN, FLAT SHEET	
							7				7	630	84900	7	EACH	REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL	
							2				2	630	85100	2	EACH	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION	
								14			14	630	89902	14	EACH	REMOVAL OF MISCELLANEOUS TRAFFIC CONTROL ITEM: REMOVAL OF PUSHBUTTON, PEDESTRIAN SIGNAL HEAD, PEDESTAL	
							2				2	630	97700	2	EACH	SIGNING, MISC.: SOLAR POWERED RECTANGULAR RAPID FLASHING BEACON (RRFB) SIGN ASSEMBLY	P6
					0.46						0.46	644	00104	0.46	MILE	EDGE LINE, 6", WHITE	
					0.38						0.38	644	00300	0.38	MILE	CENTER LINE	
					1,483						1,483	644	00400	1,483	FT	CHANNELIZING LINE, 8"	
											144	644	00500	144	FT	STOP LINE	
							652				652	644	00620	652	FT	CROSSWALK LINE, 12"	
							513				513	644	00630	513	FT	CROSSWALK LINE, 24"	
							503				503	644	00700	503	FT	TRANSVERSE/DIAGONAL LINE, WHITE	
							46				46	644	00700	46	FT	TRANSVERSE/DIAGONAL LINE, YELLOW	
											11	644	01300	11	EACH	LANE ARROW	
											1	644	01400	1	EACH	WORD ON PAVEMENT, 72"	
							418				418	644	01510	418	FT	DOTTED LINE, 6"	
							11				11	644	19000	11	EACH	SHARED LANE MARKING	
							24				24	644	20800	24	FT	YIELD LINE	
																TRAFFIC SIGNALS	
								104			104	625	25504	104	FT	CONDUIT, 3", 725.051	

GENERAL SUMMARY

DESIGN AGENCY



DESIGNER

NJL

REVIEWER

MRT 10/18/24

PROJECT ID

117965

SHEET

P11

TOTAL

36

RIC-42-04.15

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 6/17/2025 TIME: 12:09:32 PM USER: lang
P:\PR61462\117965\400-Engineering\Roadway\Sheets\117965_GG001.dgn

[illegible]

GENERAL SUMMARY

DESIGN AGENCY

B&N

burgessniple.com

DESIGNER

NJL

REVIEWER

MRT 10/18/24

PROJECT ID

117965

SHEET	TOTAL
P12	36