

STATION		SIDE	LENGTH (L)		AVERAGE WIDTH (W)	SURFACE AREA (A) = LxW	202	204	204	252	301	304	304	407	408	441	441	452
							PAVEMENT REMOVED	SUBGRADE COMPACTION	GEOGRID	FULL DEPTH PAVEMENT SAWING	ASPHALT CONCRETE BASE, PG64-22 (449) (T=8")	AGGREGATE BASE (T=6")	AGGREGATE BASE (T=8")	TACK COAT (@ 0.055 GAL/SY)	PRIME COAT (@ 0.40 GAL/SY)	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), AS PER PLAN (PG64-22) (T=1.25")	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (448) (T=1.75")	8" NON-REINFORCED CONCRETE PAVEMENT, CLASS QC1P
FROM	TO		FT	FT	SF	SY	SY	SY	FT	CY	CY	CY	CY	GAL	GAL	CY	CY	SY
BEGIN PROJECT - STA. 10+18.74																		
10+18.74	10+21.31		CADD AREA		15.09	1.68			10.00									
10+18.74	11+90.06		171.32	10.00	1713.20									10.47		6.61	9.25	
10+18.74	11+90.06		171.32	11.00	1884.52			209.39				46.53			83.76			
10+18.74	11+90.06		171.32	13.00	2227.16			247.46										
11+90.06	12+72.09		82.03	13.00	1066.39			118.49	118.49		26.33			13.03		4.11	5.76	
12+72.09	17+98.28		526.19	10.00	5261.90									32.16		20.30	28.42	
12+72.09	17+98.28		526.19	11.00	5788.09			643.12				142.92			257.25			
12+72.09	17+98.28		526.19	13.00	6840.47			760.05										
STA. EQUATION - STA. 17+98.28 BK. = STA. 18+00.00 AHD																		
18+00.00	21+55.36		355.36	10.00	3553.60								21.72			13.71	19.19	
18+00.00	21+55.36		355.36	11.00	3908.96			434.33				96.52			173.73			
18+00.00	21+55.36		355.36	13.00	4619.68			513.30										
21+55.36	22+54.75		99.39	13.00	1292.07			143.56	143.56		31.90			15.79		4.98	6.98	
22+54.75	24+30.53		175.78	10.00	1757.80									10.74		6.78	9.49	
22+54.75	24+30.53		175.78	11.00	1933.58			214.84				47.74			85.94			
22+54.75	24+30.53		175.78	13.00	2285.14			253.90										
24+27.56	25+00.00		CADD AREA		1004.67	111.63			97.92									
24+27.56	25+00.00		CADD AREA		1007.42									6.16		3.89	5.44	
24+27.56	25+00.00		CADD AREA		1096.47							20.31			48.73			
24+27.56	25+00.00		CADD AREA		1245.91			138.43										
24+30.53	24+51.05		CADD AREA		205.17													22.80
24+30.53	24+51.05		CADD AREA		246.42							4.56						
24+30.53	24+51.05		CADD AREA		267.2			29.69										
SUSPEND PROJECT - STA. 25+00.00																		
RESUME PROJECT - STA. 53+11.19																		
53+11.19	53+22.55		CADD AREA		113.6									0.69		0.44	0.61	
53+11.19	53+22.55		CADD AREA		124.95				13.88			3.09			5.55			
53+11.19	53+22.55		CADD AREA		147.63			16.40										
53+22.55	53+75.00		52.45	10.00	524.50									3.21		2.02	2.83	
53+22.55	53+75.00		52.45	11.00	576.95				64.11			14.25			25.64			
53+22.55	53+75.00		52.45	13.00	681.85			75.76										
SUSPEND PROJECT - STA. 53+75.00																		
RESUME PROJECT - STA. 92+50.00																		
92+50.00	95+80.87		330.87	10.00	3308.70									20.22		12.77	17.87	
92+50.00	95+80.87		330.87	11.00	3639.57				404.40			89.87			161.76			
92+50.00	95+80.87		330.87	13.00	4301.31			477.92										
STA. EQUATION - STA. 95+80.87 BK. = STA. 95+74.60 AHD																		
95+74.60	97+46.07		171.47	10.00	1714.70									10.48		6.62	9.26	
95+74.60	97+46.07		171.47	11.00	1886.17				209.57			46.57			83.83			
95+74.60	97+46.07		171.47	13.00	2229.11			247.68										
STA. EQUATION - STA. 97+46.07 BK. = STA. 97+40.59 AHD																		
97+40.59	121+53.83		2413.24	10.00	24132.40									147.48		93.10	130.34	
97+40.59	121+53.83		2413.24	11.00	26545.64				2949.52			655.45			1179.81			
97+40.59	121+53.83		2413.24	13.00	31372.12			3485.79										
STA. EQUATION - STA. 121+53.83 BK. = STA. 121+53.87 AHD																		
121+53.87	123+30.23		176.36	10.00	1763.60									10.78		6.80	9.53	
121+53.87	123+30.23		176.36	11.00	1939.96				215.55			47.90			86.22			
121+53.87	123+30.23		176.36	13.00	2292.68			254.74										
STA. EQUATION - STA. 123+30.23 BK. = STA. 123+30.00 AHD																		
123+30.00	141+57.81		1827.81	10.00	18278.10									111.70		70.52	98.72	
123+30.00	141+57.81		1827.81	11.00	20105.91				2233.99			496.44			893.60			
123+30.00	141+57.81		1827.81	13.00	23761.53			2640.17										
STA. EQUATION - STA. 141+57.81 BK. = STA. 141+56.91 AHD																		
141+56.91	144+07.53		250.62	10.00	2506.20									15.32		9.67	13.54	
141+56.91	144+07.53		250.62	11.00	2756.82				306.31			68.07			122.53			
141+56.91	144+07.53		250.62	13.00	3258.06			362.01										
144+07.53	144+21.33		CADD AREA		137.86													15.32
144+07.53	144+21.33		CADD AREA		151.66							2.81						
144+07.53	144+21.33		CADD AREA		179.24			19.92										
SUSPEND PROJECT - STA. 144+21.33																		
RESUME PROJECT - STA. 144+48.49																		
144+48.49	144+58.49		CADD AREA		104.61													11.62
144+48.49	144+58.49		CADD AREA		115.07							2.13						
144+48.49	144+58.49		CADD AREA		135.99			15.11										
144+58.49	166+74.98		2216.49	10.00	22164.90													