STATE OF OHIO
DEPARTMENT OF TRANSPORTATION

# D03-TSG-FY2018 (C)

CITIES OF ASHLAND, OBERLIN & VERMILION

VILLAGE OF MILAN

BRONSON, BROWNHELM, CHIPPEWA, EAST UNION, MILAN, MONTGOMERY, NORWALK, PAINT, PITTSFIELD, RUGGLES, SUGAR CREEK, & WESTFIELD TOWNSHIPS

ASHLAND, ERIE, HURON, LORAIN, MEDINA, & WAYNE COUNTIES

#### INDEX OF SHEETS:

1110211 01 0112210	
TITLE SHEET	1
SCHEMATIC	2
GENERAL NOTES	4-
GENERAL SUMMARY	8
SIGNAL SLIMMARY	9

### EARTH DISTURBED AREAS

PROJECT DESCRIPTION

THIS PROJECT WILL INSTALL SUPPLEMENTAL SIGNAL

PROJECT EARTH DISTURBED AREA:

N/A ACRES (maintencance project)

ESTIMATED CONTRACTOR EARTH DISTURBED AREA: N/A ACRES (maintenance project)

NOTICE OF INTENT EARTH DISTURBED AREA: N/A ACRES (maintenance project)

#### LIMITED ACCESS

THIS IMPROVEMENT IS ESPECIALLY DESIGNED FOR THROUGH TRAFFIC AND HAS BEEN DECLARED A LIMITED ACCESS HIGHWAY OR FREEWAY BY ACTION OF THE DIRECTOR IN ACCORDANCE WITH THE PROVISIONS OF SECTION 5511.02 OF THE OHIO REVISED CODE.

#### 2016 SPECIFICATIONS

THE STANDARD SPECIFICATIONS OF THE STATE OF OHIO, DEPARTMENT OF TRANSPORTATION, INCLUDING SUPPLEMENTAL SPECIFICATIONS LISTED IN THE PLANS AND CHANGES LISTED IN THE PROPOSAL SHALL GOVERN THIS IMPROVEMENT.

I HEREBY APPROVE THESE PLANS AND DECLARE THAT THE MAKING OF THIS IMPROVEMENT WILL NOT REQUIRE THE CLOSING TO TRAFFIC OF THE HIGHWAY AND THAT PROVISIONS FOR THE MAINTENANCE AND SAFETY OF TRAFFIC WILL BE AS SET FORTH ON THE PLANS AND ESTIMATES.

DATE DISTRICT DEPUTY DIRECTOR

OHIO

Call Before You Dig

Call Before You Dig

Utilities Protection
SERVICE
(Non-members must be called directly)

OIL & GAS PRODUCERS
UNDERGROUND PROTECTION SERVICE
1-800-925-0988

SEE SHEET 2 & 3

LOCATION MAP

LATITUDE: 40°52′38" LONGITUDE: 82°17′41"

DESIGN EXCEPTIONS

NONE REQUIRED

ENGINEERS SEAL		STANDARD CONSTRUCTION DRAWINGS								
CRAIG CRAIG	DM-4.3	1/15/16	MT-85.10	7/21/17	TC-85.10	7/21/17	800-2016	4/20/18		
WILL E OF	DM-4.4	1/15/16	MT-95.30	7/21/17	TC-85.20	1/15/16	809	1/19/18		
IIIII A 7 O HILL			MT-95.31	7/21/17	TC-85.21	1/20/17	832	1/17/14		
CRAIG A.			MT-95.32	7/21/17	TC-85.22	1/19/18				
CRAIG E			MT-95.45	7/21/17						
<i>≦</i> . ∴ A										
EX: DEVORE XE										
≣ : E-70370 <i>: ≣</i>										
TO PAR SONES										
MON GISTEN WILL										
MILSSIONAL ENGILLI										
IGNED: The M. Carry										
DATE: 3-12-2018										

DATE \_\_\_\_\_\_ DIRECTOR, DEPARTMENT OF TRANSPORTATION

PLANS PREPARED BY:







Dacien/Baadway/Chaate/107507 CTOO1 dan Chaat

 $\bigcirc$ 

 $\bigcirc$ 





 $\bigcirc$ 

 $\bigcirc$ 

LISTED BELOW ARE ALL UTILITIES LOCATED WITHIN THE PROJECT CONSTRUCTION LIMITS TOGETHER WITH THEIR RESPECTIVE OWNERS

THE LOCATION OF THE UNDERGROUND UTILITIES SHOWN ON THE PLANS ARE AS OBTAINED FROM THE OWNERS AS REQUIRED BY SECTION 153.64 O.R.C.

Armstrong Utilities 1141 Lafayette Road Medina, OH 44256 330.722.3141

CHARTER COMMUNICATIONS 5520 WHIPPLE AVENUE NW NORTH CANTON, OH 44720 330.494.9200

CITY OF ASHLAND 206 CLAREMONT AVENUE ASHLAND, OH 44805 419.289.8331

**COMMUNICATION** AT&T OHIO 130 N ERIE STREET TOLEDO, OH 43604 419.245.7244

COMMUNICATION 175 ASHLAND ROAD, P.O. BOX 3555 MANSFIELD, OH 44907 419.755.7956

COMMUNICATION **EVERSTREAM SOLUTIONS** 800 W ST CLAIR, 2ND FLOOR CLEVELAND, OH 44113 216.581.7972

COUNTY ERIE COUNTY ENGINEERS 2700 COLUMBUS AVENUE SANDUSKY. OH 44870 419.627.7710

HURON COUNTY ENGINEER DEPT. 150 JEFFERSON STREET NORWALK, OH 44857 419.668.1997

ELECTRIC AEP OHIO 500 MAPLE STREET WOOSTER, OH 44691 330.202.3047

ELECTRIC OHIO EDISON 1717 ASHLAND ROAD MANSFIELD, OH 44905 419.521.6213

ASPIRE ENERGY 300 TRACY BIRDGE ROAD ORRVILLE, OH 44667 330.682.7726

COLUMBIA GAS OF OHIO 1800 BROAD AVENUE FINDLAY, OH 45840 419.427.3225

KINDER MORGAN 605 WESTLAKE DRIVE ASHLAND, OH 44805 714.560.4967

TRANSCANADA 589 N STATE ROAD MEDINA, OH 44256 330.721.4163

ODOT DISTRICT THREE 906 CLARK AVENUE ASHLAND, OH 44805 419.207.7045

ARMSTRONG UTILITIES 1215 CLAREMONT AVENUE ASHLAND, OH 44805

CABLE MASSILON CABLE TELEVISION P.O. BOX 917 WOOSTER, OH 44691

CITY OF ORRVILLE UTILITIES 207 NORTH MAIN STREET ORRVILLE, OH 44667 330.684.5000

COMMUNICATION AT&T TRANSMISSION 5980 WILCOX PLACE DUBLIN, OH 43016 614.760.8320

COMMUNICATION DOYLESTOWN TELEPHONE CO. 28 EAST MARION STREET DOYLESTOWN, OHIO 44230 330.658.6666

COMMUNICATION FRONTIER COM 83 TOWNSEND AVENUE NORWALK, OH 44857 419.744.3613

ERIE COUNTY SEWER 554 RIVER ROAD HURON, OH 44839 419.433.7303

COUNTY WAYNE COUNTY ENGINEER 3151 WEST OLD LINCOLN WAY WOOSTER, OH 44691 330.287.550

FIRELANDS ELECTRIC 1 ENERGY PLACE NEW LONDON, OH 44851 419.929.1571

ENVIRONMENTAL WAYNE COUNTY ENVIRONMENTAL 428 WEST LIBERTY STREET WOOSTER, OH 44691 330.263.5035

GAS COLUMBIA GAS OF OHIO 1021 N. MAIN ST MANSFIELD, OH 44903 419.528.1137

**DOMINION** 320 SPRINGSIDE DRIVE, SUITE 320 AKRON, OH 44333 *800.362.7557* 

NORTHEAST OHIO NATURAL GAS 9081 STATE ROUTE 250 STRASBURG, OH 44680 330.878.5589

**TOWNSHIP** EAST UNION TOWNSHIP 4337 S KANSAS ROAD APPLE CREEK, OH 44606 *330.698.0103* 

#### **UTILITIES (CONTINUED)**

VILLAGE VILLAGE OF MILAN 11 S. MAIN STREET MILAN. OH 44846 419.499.4161

WATER ERIE COUNTY WATER 2614 COLUMBUS AVENUE SANDUSKY, OH 44870 419.627.7666

42401 S.R. 303 LAGRANGE, OH 44050 440.355.6060

WATER

RLCWA

VILLAGE VILLAGE OF DOYLESTOWN 24 SOUTH PORTAGE STREET DOYLESTOWN, OHIO 44230

NORTHERN OHIO RURAL WATER P.O. BOX 96 COLLINS, OH 44826 419.668.7213

THE AFOREMENTIONED UTILITY COMPANIES AND AGENCIES HAVE VARIOUS FACILITIES IN THE AREA THAT WILL REMAIN IN PLACE DURING CONSTRUCTION.

EXTREME CAUTION SHOULD BE EXERCISED IN AREAS WITH UTILITIES.
SECTIONS 105.07 AND 107.16 OF THE DEPARTMENT OF TRANSPORTATION
CONSTRUCTION AND MATERIALS SPECIFICATIONS REQUIRE, AMONG OTHER
THINGS, THAT THE CONTRACTOR COOPERATE WITH ALL UTILITIES LOCATED
WITHIN THE LIMITS OF THIS CONSTRUCTION PROJECT AND TAKE RESPONSIBILITY FOR THE PROTECTION OF THE UTILITY PROPERTY AND

#### **GUARANTEE**

THE CONTRACTOR SHALL GUARANTEE THAT THE TRAFFIC CONTROL SYSTEM INSTALLED AS PART OF THIS CONTRACT SHALL OPERATE SATISFACTORILY FOR A PERIOD OF 180 DAYS FOLLOWING COMPLETION OF THE 10-DAY PERFORMANCE TEST. IN THE EVENT OF UNSATISFACTORY OPERATION THE CONTRACTOR SHALL CORRECT FAULTY INSTALLATIONS, MAKE REPAIRS AND REPLACE DEFECTIVE PARTS WITH NEW PARTS OF EQUAL OR BETTER QUALITY.

EQUIPMENT, MATERIAL AND LABOR COSTS INCURRED IN CORRECTING AN UNSATISFACTORY OPERATION SHALL BE BORNE BY THE CONTRACTOR.

THE GUARANTEE SHALL COVER THE FOLLOWING ITEMS OF THE TRAFFIC CONTROL SYSTEM: CONTROLLERS AND ASSOCIATED EQUIPMENT, DETECTOR UNITS, INTERCONNECTION ITEMS AND MASTER CONTROL EQUIPMENT.

CUSTOMARY MANUFACTURER'S GUARANTEES FOR THE FOREGOING ITEMS SHALL BE TURNED OVER TO THE STATE OR THE MAINTAINING AGENCY FOLLOWING ACCEPTANCE OF THE EQUIPMENT.

THE COST OF GUARANTEEING THE TRAFFIC CONTROL SYSTEM WILL BE INCIDENTAL TO AND INCLUDED IN THE CONTRACT UNIT PRICE OF THE VARIOUS ITEMS MAKING UP THE SYSTEM.

#### COORDINATION OF WORK BETWEEN CONTRACTORS

THE CONTRACTOR SHOULD BE AWARE THAT THERE MAY BE OTHER WORK BEING PERFORMED BY A SEPARATE CONTRACT. HUR-20 16.36 PM PID 87698, DO3 TSG FY 2018 (B) PID 101523, AND DO3 TSG FY 2018 (A) PID 103119 ARE SCHEDULED TO BEGIN WORK IN THE SAME CONSTRUCTION SEASON AS THIS PROJECT. COORDINATION OF WORK IS THE RESPONSIBILITY OF THE CONTRACTOR.

#### **GROUNDING AND BONDING**

THE REQUIREMENTS OF THE CONSTRUCTION AND MATERIAL SPECIFICATIONS (C&MS) AND THE TC SERIES OF STANDARD CONSTRUCTION DRAWINGS ARE MODIFIED AS FOLLOWS:

1. ALL METALLIC PARTS CONTAINING ELECTRICAL CONDUCTORS SHALL BE PERMANENTLY JOINED TO FORM AN EFFECTIVE GROUND FAULT CURRENT PATH BACK TO THE GROUNDED CONDUCTOR IN THE POWER SERVICE DISCONNECT

A. PROVIDE AN EQUIPMENT GROUNDING CONDUCTOR IN METALLIC CONDUITS (725.04) IN ADDITION TO THE CONDUCTORS SPECIFIED AND BOND THE CONDUIT TO THIS GROUNDING CONDUCTOR.

B. WHEN AN EQUIPMENT GROUNDING CONDUCTOR IS REQUIRED IN PLASTIC CONDUIT (725.05), THE INSTALLATION SHALL INCLUDE A SEPARATE EQUIPMENT GROUNDING CONDUCTOR IN ADDITION TO THE CONDUCTORS

C. METALLIC CONDUIT CARRYING THE LOOP WIRES FROM IN THE PAVEMENT TO THE PULL BOX SPLICE LOCATION WILL ONLY BE BONDED AT THE PULL BOX END, AND WILL NOT CONTAIN AN EQUIPMENT GROUNDING CONDUCTOR

D. IF MULTIPLE CONDUIT RUNS BEGIN AND END AT THE SAME POINTS, ONLY ONE EQUIPMENT GROUNDING CONDUCTOR IS REQUIRED.

E. IF AN EQUIPMENT GROUNDING CONDUCTOR IS NEEDED IN CONDUIT BETWEEN SIGNALIZED INTERSECTIONS FOR UNDERGROUND INTERCONNECT CABLE, THE GROUNDING SYSTEM FOR EACH SIGNALIZED INTERSECTION WILL BE SEPARATED ABOUT MIDWAY BETWEEN THE INTERSECTIONS.

F. THE MESSENGER WIRE AT SIGNALIZED INTERSECTIONS WILL BE USED AS THE CONDUCTIVE PATH FROM CORNER TO CORNER IF CONDUIT IS NOT PROVIDED UNDER THE ROADWAY. WHEN CONDUIT CONNECTS THE CORNERS OF AN INTERSECTION, AN EQUIPMENT GROUNDING CONDUCTOR SHALL BE USED IN THE

#### 2. CONDUITS.

A. THE 725.04 CONDUIT SHALL HAVE GROUNDING BUSHINGS INSTALLED AT ALL TERMINATION POINTS. THE BUSHING MATERIAL SHALL BE COMPATIBLE WITH GALVANIZED STEEL CONDUIT AND THE GROUNDING LUG MATERIAL SHALL BE COMPATIBLE FOR USE WITH COPPER WIRE. THREADED OR COMPRESSION TYPE BUSHINGS MAY BE USED.

B. THE 725.05 CONDUIT SHALL HAVE THE INSIDE AND OUTSIDE DIAMETERS OF THE CONDUIT DEBURRED AT ALL TERMINATION POINTS.

C. BOTH ENDS OF METALLIC CONDUIT SHALL BE BONDED TO THE EQUIPMENT GROUNDING CONDUCTOR.

D. METALLIC CONDUIT MAY BE BONDED TO METALLIC BOXES THROUGH THE USE OF CONDUIT FITTINGS UL APPROVED FOR THIS TYPE OF CONNECTION, WITH THE BOX BONDED TO THE EQUIPMENT GROUNDING CONDUCTOR.

3. WIRE FOR GROUNDING AND BONDING.

A. USE INSULATED, COPPER WIRE FOR THE EQUIPMENT GROUNDING CONDUCTOR. BONDING JUMPERS IN BOXES AND ENCLOSURES MAY BE BARE OR INSULATED COPPER WIRE. WIRE SIZE SHALL BE AS FOLLOWS:

I. USE 4 AWG BETWEEN THE POWER SERVICE AND SUPPORTS, POLES, PEDESTALS, CONTROLLER OR FLASHER CABINETS.

II. USE A MINIMUM 8 AWG BETWEEN LOOP DETECTOR PULL BOXES AND THE FIRST CONDUIT THAT REQUIRES A LARGER SIZE AS SPECIFIED IN 3.A.I ABOVF.

III. USE A MINIMUM 8 AWG BETWEEN THE "PREPARE TO STOP WHEN FLASHING" INSTALLATION (INCLUDING SUPPORT) AND THE FIRST CONDUIT THAT REQUIRES A LARGER SIZE AS SPECIFIED IN 3.A.I ABOVE.

IV. THE INSULATION SHALL BE GREEN OR GREEN WITH YELLOW STRIPE(S). FOR 4 AWG OR LARGER, INSULATION MAY ALSO BE BLACK WITH GREEN TAPE/LABELS INSTALLED AT ALL ACCESS POINTS.

B. IN A HIGHWAY LIGHTING SYSTEM, THE EQUIPMENT GROUNDING CONDUCTOR SHALL BE THE SAME WIRE SIZE AS THE DUCT CABLE OR DISTRIBUTION CABLE CIRCUIT CONDUCTORS, WITH THE MINIMUM CONDUCTOR SIZE OF 4 AWG. BONDING JUMPERS WILL BE MINIMUM SIZE 4 AWG.





Ö

#### GROUNDING AND BONDING (CONTINUED)

4. GROUND ROD.

A. A 3/4 INCH SCHEDULE 40 PVC CONDUIT WILL BE USED IN FOUNDATIONS AND CONCRETE WALLS FOR THE GROUNDING CONDUCTOR (GROUND WIRE) RACEWAY TO THE GROUND ROD. SHOULD METALLIC CONDUIT BE USED, BOTH ENDS OF THE CONDUIT SHALL BE BONDED TO THE GROUNDING CONDUCTOR.

B. THE TYPICAL GROUNDING CONDUCTOR (GROUND WIRE) SHALL BE 4 AWG INSULATED, COPPER.

5. THE GREEN CONDUCTOR IN SIGNAL CABLES (CONDUCTOR #4) SHALL NOT BE USED TO SUPPLY POWER TO A SIGNAL INDICATION. IT WILL BE CONNECTED TO THE SIGNAL BODY AS AN EQUIPMENT GROUND IN ALUNINUM HEADS AND IT WILL BE UNUSED IN PLASTIC HEADS. UNUSED CONDUCTORS SHALL BE GROUNDED IN THE CABINET. TYPICAL USE OF CONDUCTORS IS AS FOLLOWS:

COND. NO.	COLOR	VEHICLE SIGNAL	PEDESTRIAN SIGNAL
1	BLACK	GREEN BALL	#1 WALK
2	WHITE	AC NEUTRAL	AC NEUTRAL
3	RED	RED BALL	#1 DW/FDW
4	GREEN	EQUIPMENT GROUND	EQUIPMENT GROUND
5	ORANGE	YELLOW BALL	#2 DW/FDW
6	BLUE	GREEN ARROW	#2 WALK
7	WHITE/BLACK	STRIPE YELLOW ARROW	NOT USED

6. POWER SERVICE AND DISCONNECT SWITCH.

A. AT THE POWER SERVICE LOCATION, THE GROUNDING CONDUCTOR (GROUND WIRE) FROM THE DISCONNECT SWITCH NEUTRAL (AC-) BAR TO THE GROUND ROD SHALL BE A CONTINUOUS, UNSPLICED CONDUCTOR. IF SPLICED, IT SHALL BE AN EXOTHERMIC WELD BUTT SPLICE.

B. THE SERVICE NEUTRAL (AC-) SHALL ONLY BE CONNECTED TO GROUND AT THE PRIMARY POWER SERVICE DISCONNECT SWITCH.

I. NEMA CONTROLLER CABINETS: IF A POWER SERVICE DISCONNECT SWITCH IS LOCATED BEFORE THE CONTROLLER CABINET, THE NEUTRAL (AC-) AND THE GROUNDING BARS IN THE CONTROLLER CABINET SHALL NOT BE CONNECTED TOGETHER AS SHOWN IN NEMA TS-2, FIGURE 5-4.

II. IF SECONDARY DISCONNECT SWITCHES ARE CONNECTED AFTER THE PRIMARY DISCONNECT SWITCH, THE NEUTRAL (AC-) SHALL ONLY BE GROUNDED AT THE PRIMARY SWITCH. EQUIPMENT GROUNDING CONDUCTORS SHALL BE BROUGHT TO THE PRIMARY SWITCH, BUT SHALL BE GROUNDED AT BOTH SECONDARY AND PRIMARY SWITCHES.

7. PAYMENT - ALL MATERIALS AND WORK REQUIRED TO COMPLETE THE EFFECTIVE GROUND FAULT CURRENT PATH SYSTEM ARE INCIDENTAL TO THE CONDUCTORS INSTALLED BY CONTRACT.

THE CONTRACTOR SHALL PROVIDE THE PROJECT ENGINEER AND DISTRICT TRAFFIC ENGINEER WITH 72 HOUR NOTICE OF ANY WORK TO BE PERFORMED AT THE INTERSECTION SITE SO THAT INSPECTION SERVICES CAN BE SUPPLIED.

#### **MATERIALS**

ALL MATERIALS FURNISHED FOR THIS PROJECT SHALL BE IN ACCORDANCE WITH THE REQUIREMENTS OF THE OHIO DEPARTMENT OF TRANSPORTATION CONSTRUCTION AND MATERIAL SPECIFICATIONS (CM&S) DATED AS SHOWN ON SHEET 1. FURNISH NEW MATERIALS AND EQUIPMENT OF FIRST QUALITY, OF CURRENT DESIGN AND FREE FROM DEFECTS. NO USED MATERIAL WILL BE PERMITTED

CONTRACTOR SHALL SUPPLY A PAPER COPY AND AN ELECTRONIC COPY IN ADOBE ACROBAT FORMAT TO THE PROJECT AND DISTRICT TRAFFIC ENGINEER FOR APPROVAL

#### NOTIFICATION OF CONSTRUCTION INITIATION

AT LEAST FOURTEEN DAYS PRIOR TO ANY CONSTRUCTION ACTIVITIES, THE CONTRACTATOR SHALL ADVISE THE APPLICABLE DISTRICT OFFICE OF COMMUNICATIONS VIA EMAIL AT DO3.PIO@DOT.OHIO.GOV, THE APPLICABLE DISTRICT WORK ZONE TRAFFIC MANAGER VIA EMAIL AT DO3.MOT@DOT.OHIO.GOV, AND ODOT CENTRAL OFFICE OF TRAFFIC ENGINEERING AT CHARLES.FISHER@DOT.OHIO.GOV OF THE ANTICIPATED START DATE OF ANY CONSTRUCTION ACTIVITIES, INCLUDING BUT NOT LIMITED TO THE PLACING OF WORK ZONE SIGNS. THE NOTIFICATION SHALL ALSO INCLUDE THE PROJECT NUMBER, PID, NAME AND PHONE NUMBER OF THE CONTRACTOR, A POINT OF CONTACT AND THE ANTICIPATED IMPACT ON TRAFFIC. THE CONTRACTOR WILL IMMEDIATELY INFORM THE DISTRICT OFFICE OF COMMUNICATIONS AND THE DISTRICT WORK ZONE TRAFFIC MANAGER OF ANY AND ALL DELAYS AND/OR CHANGES REGARDING THE CONSTRUCTION INITIATION DATE.

#### NOTIFICATIONS OF TRAFFIC RESTRICTIONS

THROUGHOUT THE DURATION OF THE PROJECT, THE CONTRACTOR SHALL NOTIFY THE PROJECT ENGINEER IN WRITING OF ALL TRAFFIC RESTRICTIONS AND UPCOMING MAINTENANCE OF TRAFFIC CHANGES. THE CONTRACTOR SHALL ENSURE THE WRITTEN NOTIFICATION IS SUBMITTED IN A TIMELY MANNER TO ALLOW THE PROJECT ENGINEER TO MEET THE REQUIRED TIME FRAMES SET FORTH IN THE TABLE BELOW. NOTIFICATIONS SHALL BE RECEIVED BY THE PROJECT ENGINEER PRIOR TO THE PHYSICAL SETUP OF ANY APPLICABLE SIGNS OR MESSAGE BOARDS. UPON RECEIPT OF NOTIFICATION BY THE CONTRACTOR, THE PROJECT ENGINEER WILL ARRANGE NOTIFICATION OF THE FOLLOWING ORGANIZATIONS, IN WRITING, IN ACCORDANCE WITH THE BELOW TABLE:

COUNTY ENGINEER'S OFFICE
THE CITY OF VERMILION
TOWNSHIP TRUSTEES (TOWNSHIP ROADS ONLY)
LOCAL POLICE, FIRE, AND EMERGENCY MEDICAL SERVICES
LOCAL SCHOOL DISTRICTS
COUNTY SHERIFF'S OFFICE
ODOT DISTRICT THREE OFFICE OF ROADWAY SERVICES
ODOT DISTRICT THREE PUBLIC INFORMATION OFFICE
SPECIAL HAULING PERMITS SECTION (Hauling.Permits@dot.ohio.gov)

INFORMATION SHOULD INCLUDE, BUT IS NOT LIMITED TO, ALL CONSTRUCTION ACTIVITIES THAT IMPACT OR INTERFERE WITH TRAFFIC AND SHALL LIST THE SPECIFIC LOCATION, TYPE OF WORK, ROAD STATUS, DATE AND TIME OF RESTRICTION, DURATION OF RESTRICTION, NUMBER OF LANES MAINTAINED, NUMBER OF LANES CLOSED, MINIMUM VERTICAL CLEARANCE, MINIMUM WIDTH OF DRIVABLE PAVEMENT, DETOUR ROUTES, IF APPLICABLE, AND ANY OTHER INFORMATION REQUESTED BY THE PROJECT ENGINEER.

#### NOTIFICATION TIME TABLE

<u>ITEM</u>	<u>DURATION OF CLOSURE</u>	NOTICE LEAD TIME REQUIRED*			
DAME AND COD	TWO WEEKS OR GREATER	21 CALENDAR DAYS			
RAMP AND/OR  ROAD CLOSURES	12 HOURS TO TWO WEEKS	14 CALENDAR DAYS			
NOAD CEOSONES	12 HOURS OR LESS	4 BUSINESS DAYS			
LANE CLOSURES AND	TWO WEEKS OR GREATER	14 CALENDAR DAYS			
RESTRICTIONS	LESS THAN TWO WEEKS	5 BUSINESS DAYS			
START OF CONSTRUCTION AND TRAFFIC PATTERN CHANGES	N/A	14 CALENDAR DAYS PRIOR TO IMPLEMENTATION			

\* - PRIOR TO CLOSURE DATE, UNLESS NOTED OTHERWISE

ANY UNFORESEEN CONDITIONS NOT SPECIFIED IN THE PLANS REQUIRING TRAFFIC RESTRICTIONS SHALL ALSO BE REPORTED TO THE PROJECT ENGINEER USING THE NOTIFICATION TIME TABLE.

#### FINAL INSPECTION

THE PROJECT ENGINEER AND DISTRICT TRAFFIC ENGINEER SHALL BE NOTIFIED 72 HOURS PRIOR PRIOR TO THE FINISH OF THE PROJECT SO THAT A FINAL INSPECTION CAN BE SCHEDULED. THE CONTRACTOR WILL BE RESPONSIBLE TO SIGN OFF ON THE ODOT INSPECTION CHECKLIST, WHICH WILL BE PROVIDED AT THE PRE-CON MEETING, BEFORE ODOT WILL INSPECT THE WORK. ONCE THE FINAL INSPECTION IS PASSED, THE PROJECT WILL BE ACCEPTED.

#### 625- PULL BOX REMOVED

THE CONTRACTOR SHALL ONLY REMOVE EXISTING PULL BOXES THAT ARE ONLY CONNECTED TO THE LOOPS BEING REMOVED.

## 632- REMOVAL OF MISC. TRAFFIC CONTROL ITEM: LOOP LEAD-IN CABLE

THE REMOVAL OF LOOP LEAD-IN CABLE INCLUDES ANY CABLE RUN, WHICH INCLUDES IN THE SUPPORT POLES, CONDUITS, AND CABINETS, THE REMOVAL OF LOOP LEAD IN SHALL ONLY BE DONE WHERE RADAR DETECTION IS TO BE INSTALLED. LOOP LEAD IN SHALL BE REMOVED COMPLETELY FROM THE CABINET TO THE NEAREST PULL BOX WHEN THE LOOPS ARE ON THE CABINET CORNER, OR FROM THE CABINET TO ACROSS THE SPAN AND TO THE NEXT PULL BOX WHEN THE CABLES ARE OVERHEAD.

UNLASH/RELASHING OF MESSENGER WIRE TO REMOVE THE CABLE IS ACCOUNTED FOR IN AN ADDITIONAL ITEM.
PAYMENT FOR ITEM 632 REMOVAL OF MISC. TRAFFIC CONTROL ITEM: LOOP LEAD-IN CABLE SHALL BE MADE AT THE CONTRACT UNIT PRICE FOR EACH INTERSECTION, WHICH MAY INCLUDE ONE OR MORE CABLES.

### 632-VEHICULAR SIGNAL HEAD, LED, BLACK, (BY TYPE), WITH BACKPLATE, AS PER PLAN

IN ADDITION TO THE REQUIREMENTS OF C&MS 632 AND 732, THE FOLLOWING REQUIREMENTS SHALL APPLY:

- 1. SIGNAL HEADS AND VISORS SHALL BE CONSTRUCTED OF BLACK POLYCARBONATE PLASTIC WITH VISORS AS SPECIFIED AND MEET ITE SPECIFICATIONS.
- 2. PROPER EXTERIOR COLORS SHALL BE OBTAINED BY USE OF COLORED PLASTIC MATERIAL RATHER THAN PAINTING.
- 3. THE ENTRANCE FITTING SHALL BE OF THE TRI-STUD DESIGN WITH SERRATED RINGS IN ORDER TO ACHIEVE POSITIVE LOCKING.
- 4. ALL SIGNAL HEADS SHALL BE RIGIDLY MOUNTED TO THE MAST ARM WITH THE (COLOR) MODULE LOCATED IN FRONT OF THE MAST ARM.
- 5. ALUMINUM BACKPLATES SHALL BE IN ACCORDANCE WITH THE C&MS AND INCLUDE A FLUORESCENT YELLOW REFLECTIVE BORDER.
- 6. THE LIGHT EMITTING DIODE (LED) MODULES SHALL MEET THE REQUIREMENTS OF C&MS 732.04-C, AND SHALL BE LONG LIFE, MINIMUM WARRANTY OF 15 YEARS. THE CONTRACTOR SHALL PROVIDE ODOT, IN WRITING, WITH THE LED MANUFACTURER NAME, 400 TRAFFIC SIGNALS TRAFFIC ENGINEERING MANUAL (JANUARY 15, 2016) OCTOBER 23, 2002 4-77 SERIAL NUMBER, PART NUMBER, DESCRIPTION OF LAMP, AND DATE OF MANUFACTURE FOR ALL LED UNITS THAT ARE TO BE USED IN THE SIGNAL HEAD PRIOR TO INSTALLATION, FOR ACCEPTANCE AND WARRANTY PURPOSES.
- 7. EACH LENS CLIP THAT HOLDS THE LED SIGNAL LAMP IN PLACE SHALL BE FASTENED TO THE SIGNAL HEAD HOUSING DOOR BY USE OF A 3/4" LONG STAINLESS STEEL SOCKET SET SCREW AND STAINLESS STEEL NUT. THE VISOR SHALL BE ATTACHED BY USE OF 3/4" LONG STAINLESS STEEL SOCKET SECT SCREW AND STAINLESS STEEL NUT.
- 8. SIGNAL HEADS SHALL HAVE A MINIMUM WALL THICKNESS OF 0.117 INCHES.
- 9. SIGNAL HEADS SHALL INCLUDE CUTAWAY TYPE VISORS UNLESS OTHERWISE SPECIFIED IN THE PLANS.
- 10. APPLY A BEAD OF SILICONE TO THE SIGNAL HEAD, WASHER, AND ENTRANCE ADAPTER SERRATIONS TO PREVENT WATER INTRUSION. ALSO, FILL THE SPACE BETWEEN CONCENTRIC SERRATION RINGS ON THE TOP OF THE SIGNAL HEAD TO COMPLETELY EXCLUDE WATER FROM THE SPACE BETWEEN THE CONCENTRIC RINGS.
- 11. BALANCE ADJUSTERS SHALL NOT BE USED ON ONE-WAY HEADS OR TETHERED HEADS.

PAYMENT FOR ITEM 632 VEHICULAR SIGNAL HEAD, LED, BLACK, (BY TYPE), WITH BACKPLATE, AS PER PLAN SHALL BE MADE FOR COMPLETE SIGNAL HEAD FURNISHED AND INSTALLED, INCLUDING ALL LABOR, EQUIPMENT, MATERIALS, AND NEW ATTACHMENT HARDWARE.

### 632-SIGNALIZATION, MISC.: UNLASH AND RELASH MESSENGER WIRE

THE CONTRACTOR SHALL REMOVE EXISTING MESSENGER WIRE LASHING RODS AND REINSTALL THEM AS NECESSARY FOR THE INSTALLATION OF ANY NEW CABLE ON THE EXISTING INTERSECTION SIGNAL SPANS. REMOVE LOOP LEAD-IN CABLE AND/OR VIDEO DETECTION UNITS THAT ARE BEING REPLACED WITH RADAR. THE CABLES SHALL ENTER THE EXISTING STRAIN POLE THROUGH THE POLE CABLE ENTRANCE FITTING AND USE THE EXISTING CONDUIT SYSTEM TO GET TO THE CONTROLLER CABINET. THE NEW CABLES SHALL BE SUPPORTED BY A NEW CABLE SUPPORT ASSEMBLY AT THE TOP OF THE STRAIN POLE.

THE NEW SIGNAL CABLES SHALL BE BID BY SEPARATE BID ITEMS.

PAYMENT FOR ITEM 632 "SIGNALIZATION MISC.: UNLASH AND RELASH MESSENGER WIRE' SHALL BE MADE AT THE CONTRACT UNIT PRICE PER FOOT AND SHALL INCLUDE ALL LABOR, MATERIALS, CABLE SUPPORT ASSEMBLIES AND EQUIPMENT TO INSTALL NEW CABLES ON EXISTING SIGNAL SPAN WIRE INSTALLATIONS.

### 632- REMOVAL OF MISC. TRAFFIC CONTROL ITEM: VIDEO DETECTION

THE REMOVAL OF THIS ITEM SHALL INCLUDE ALL VIDEO DETECTION EQUIPMENT PER INTERSECTION INCLUDING BUT NOT LIMITED TO VIDEO DETECTION UNIT, SUPPORTS AND BRACKETS, CABLE DETECTOR CARDS, CABLES, AND SHELF MOUNTED EQUIPMENT.

PAYMENT FOR ITEM 632 REMOVAL OF MISC. TRAFFIC CONTROL ITEM: VIDEO DETECTION SHALL BE MADE AT THE CONTRACT UNIT PRICE FOR EACH INTERSECTION WHICH MAY INCLUDE ONE OR PIECES OF EQUIPMENT.

 $\bigcirc$ 

 $\bigcirc$ 

 $\bigcirc$ 

## ITEM 614- LAW ENFORCEMENT OFFICER (WITH PATROL CAR) FOR ASSISTANCE DURING CONSTRUCTION OPERATIONS

USE OF LAW ENFORCEMENT OFFICERS (LEOS) BY CONTRACTORS OTHER THAN THE USES SPECIFIED BELOW WILL NOT BE PERMITTED AT PROJECT COST. LEOS SHOULD NOT BE USED WHERE THE OMUTCD INTENDS THAT FLAGGERS BE USED. IN ADDITION TO THE REQUIREMENTS OF CMS 614 AND THE OMUTCD, A
UNIFORMED LEO WITH AN OFFICIAL PATROL CAR (CAR WITH TOP-MOUNTED
EMERGENCY FLASHING LIGHTS AND COMPLETE MARKINGS OF THE APPROPRIATE
LAW ENFORCEMENT AGENCY) SHALL BE PROVIDED FOR THE FOLLOWING TRAFFIC

-DURING THE ENTIRE ADVANCE PREPARATION AND CLOSURE SEQUENCE WHERE COMPLETE BLOCKAGE OF TRAFFIC IS REQUIRED.

-DURING A TRAFFIC SIGNAL INSTALLATION WHEN IMPACTING THE NORMAL FUNCTION OF THE SIGNAL OR THE FLOW OF TRAFFIC OR WHEN TRAFFIC NEEDS TO BE DIRECTED THROUGH AN ENERGIZED TRAFFIC SIGNAL CONTRARY TO THE SIGNAL DISPLAY (E.G., DIRECTING MOTORISTS THROUGH A RED LIGHT.) IN ADDITION TO THE REQUIREMENT OF CMS 614 AND THE OMUTCO, A UNIFORMED LEO WITH AN OFFICIAL PATROL CAR (CAR WITH TOP-MOUNTED EMERGENCY FLASHING LIGHTS AND COMPLETE MARKINGS OF THE APPROPRIATE LAW ENFORCEMENT AGENCY) SHOULD BE PROVIDED FOR THE FOLLOWING TRAFFIC

-FOR LANE CLOSURES: DURING INITIAL SET-UP PERIODS, TEAR DOWN PERIODS, SUBSTANTIAL SHIFTS OF A CLOSURE POINT OR WHEN NEW LANE CLOSURE ARRANGEMENTS ARE INITIATED FOR LONG-TERM LANE CLOSURES, SHIFTS (FOR THE FIRST AND LAST DAY OF MAJOR CHANGES IN TRAFFIC CONTROL SETUP). IN GENERAL, LEOS SHOULD BE POSITIONED AT THE POINT OF LANE RESTRICTION OR ROAD CLOSURE AND TO MANUALLY CONTROL TRAFFIC MOVEMENTS THROUGH INTERSECTIONS IN WORK ZONES.

-WHEN CONSTRUCTION VEHICLES ARE ENTERING/EXITING THE ZONE DIRECTLY FROM/INTO AN OPEN LANE OF TRAFFIC. IF A LANE HAS BEEN CLOSED TO PROVIDE AN ACCELERATION/DECELERATION LANE FOR THE VEHICLE, THE LEO WILL NOT BE REQUIRED.

LEOS SHOULD NOT FORGO THEIR TRAFFIC CONTROL RESPONSIBILITIES TO APPREHEND MOTORISTS FOR ROUTINE TRAFFIC VIOLATIONS. HOWEVER, IF APPREHEND MOTORISTS FOR ROUTINE TRAFFIC VIOLATIONS. HOWEVER, IF
A MOTORIST'S ACTIONS ARE CONSIDERED TO BE RECKLESS, THEN PURSUIT
OF THE MOTORIST IS APPROPRIATE. THE LEOS WORK AT THE DIRECTION OF
THE CONTRACTOR. THE CONTRACTOR IS RESPONSIBLE FOR SECURING THE
SERVICES OF THE LEOS WITH THE APPROPRIATE AGENCIES AND COMMUNICATION
THE INTENTIONS OF THE PLANS WITH RESPECT TO DUTIES OF THE LEOS. THE
ENGINEER SHALL HAVE FINAL CONTROL OVER THE LEOS'S DUTIES AND

AND WILL RESOLVE ANY ISSUES THAT MAY ARISE BETWEEN THE TWO PARTIES. THE LEO SHALL REPORT IN TO THE CONTRACTOR PRIOR TO THE START OF THE SHIFT, IN ORDER TO RECEIVE INSTRUCTIONS REGARDING SPECIFIC WORK

ASSIGNMENTS DURING HIS/HER SHIFT. THE LEO IS EXPECTED TO STAY AT THE PROJECT SITE FOR THE ENTIRE DURATION OF HIS/HER SHIFT. THE LEO IS EXPECTED TO STAY AT THE PROJECT SITE FOR THE ENTIRE DURATION OF HIS/HER SHIFT. THE LEO SHALL REPORT TO THE CONTRACTOR AT THE END OF HIS/HER SHIFT. ONCE THE LEO HAS COMPLETED THE DUTIES DESCRIBED ABOVE AND STILL HAS TIME REMAINING ON HIS/HER SHIFT, THE LEO MAY BE ASKED TO PATROL THROUGH THE WORK ZONE (WITH FLASHING LIGHTS OFF) OR BE PLACED AT ALLOW THE WORK ZONE (WITH FLASHING LIGHTS OFF) OR BE PLACED AT ALLOW THE WORK ZONE (WITH FLASHING LIGHTS OFF) OR BE PLACED AT ALLOW THE WORK ZONE (WITH FLASHING LIGHTS OFF) OR BE PLACED AT ALLOW THE WORK ZONE (WITH FLASHING LIGHTS OFF) OR BE PLACED AT ALLOW THE WORK ZONE (WITH FLASHING LIGHTS OFF) OR BE PLACED AT ALLOW THE WORK ZONE (WITH FLASHING LIGHTS OFF) OR BE PLACED AT ALLOW THE WORK ZONE (WITH FLASHING LIGHTS OFF) OR BE PLACED AT ALLOW THE WORK ZONE (WITH FLASHING LIGHTS OFF) OR BE PLACED AT ALLOW THE WORK ZONE (WITH FLASHING LIGHTS OFF) OR BE PLACED AT ALLOW THE WORK ZONE (WITH FLASHING LIGHTS OFF) OR BE PLACED AT ALLOW THE WORK ZONE (WITH FLASHING LIGHTS OFF) OR BE PLACED AT ALLOW THE WORK ZONE (WITH FLASHING LIGHTS OFF) OR BE PLACED AT ALLOW THE WORK ZONE (WITH FLASHING LIGHTS OFF) OR BE PLACED AT ALLOW THE WORK ZONE (WITH FLASHING LIGHTS OFF) OR BE PLACED AT ALLOW THE WORK ZONE (WITH FLASHING LIGHTS OFF). A LOCATION TO DETER MOTORISTS FROM SPEEDING. SHOULD IT BE NECESSARY TO LEAVE THE PROJECT SITE, THE LEO SHALL NOTIFY THE ENGINEER.

THE CONTRACTOR SHALL PROVIDE THE LEO WITH A TWO-WAY COMMUNICATION DEVICE SHALL BE RETURNED TO THE CONTRACTOR AT THE END OF HIS/HER SHIFT. LEOS (WITH PATROL CAR) REQUIRED BY THE TRAFFIC MAINTENANCE TASKS ABOVE SHALL BE PAID FOR ON A UNIT PRICE (HOURLY) BASIS UNDER ITEM 614, LAW ENFORCEMENT OFFICER (WITH PATROL CAR) FOR ASSISTANCE THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN CARRIED TO THE GENERAL SUMMARY. ITEM 614, LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE 120 HOURS.

THE HOURS PAID SHALL INCLUDE ANY MINIMUM SHOW-UP TIME REQUIRED BY THE LAW ENFORCEMENT AGENCY INVOLVED. ANY ADDITIONAL COSTS (ADMINISTRATIVE OR OTHERWISE) INCURRED BY THE CONTRACTOR TO OBTAIN THE SERVICES OF AN LEO ARE INCLUDED WITH THE BID UNIT PRICE FOR ITEM 614, LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE.

## <u>ITEM 614 - MAINTAINING TRAFFIC LANE CLOSURE/REDUCTION REQUIRED</u>

ALL WORK AND TRAFFIC CONTROL DEVICES SHALL BE IN ACCORDANCE WITH CMS 614 AND OTHER APPLICABLE PORTIONS OF THE SPECIFICATIONS, AS WELL AS THE OHIO MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES. PAYMENT FOR ALL LABOR, EQUIPMENT AND MATERIALS SHALL BE INCLUDED IN THE LUMP SUM CONTRACT PRICE FOR ITEM 614, MAINTAINING TRAFFIC, UNLESS SEPARATELY ITEMIZED ON THIS PLAN.

#### <u>ITEM 614 - MAINTENANCE OF TRAFFIC SIGNAL INSTALLATION</u>

THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING TRAFFIC SIGNAL/FLASHER INSTALLATIONS WITHIN THE PROJECT UNDER THE FOLLOWING

1. EXISTING SIGNAL/FLASHER INSTALLATIONS WHICH THE PLANS REQUIRE THE CONTRACTOR TO ADJUST, MODIFY, ADD ONTO OR REMOVE, OR WHICH THE CONTRACTOR ACTUALLY ADJUSTS, MODIFIES OR OTHERWISE DISTURBS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE ENTIRE INSTALLATION (AT AN INTERSECTION) FROM THE TIME HIS OPERATIONS FIRST DISTURB THE INSTALLATION UNTIL THE INSTALLATION HAS BEEN SUBSEQUENTLY REMOVED OR MODIFIED AND THE WORK ACCEPTED. MODIFIED AND THE WORK ACCEPTED.

2. NEW OR REUSED SIGNAL/FLASHER INSTALLATIONS OR DEVICES, INSTALLED BY THE CONTRACTOR. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTENANCE OF THESE FROM THE TIME OF INSTALLATION UNTIL THE WORK IS ACCEPTED. THE EXISTING SIGNAL INSTALLATION SHALL REMAIN IN OPERATION UNTIL THE NEW/PROPOSED SIGNAL INSTALLATION IS IN PLACE AND OPERATIONAL AS APPROVED BY THE ENGINEER.

THE CONTRACTOR SHALL CORRECT AS QUICKLY AS POSSIBLE ALL OUTAGES OR THE CONTRACTOR SHALL CURRECT AS QUICKLY AS POSSIBLE ALL OUTAGES OR MALFUNCTIONS. HE SHALL PROVIDE THE MAINTAINING AGENCY AND THE ENGINEER SUCH ADDRESSES AND PHONE NUMBERS WHERE HIS MAINTENANCE FORCES CAN BE CONTACTED. THE CONTRACTOR SHALL PROVIDE ONE OR MORE PERSONS TO RECEIVE ALL CALLS AND DISPATCH THE NECESSARY MAINTENANCE FORCES TO CORRECT OUTAGES. SUCH A PERSON OR PERSONS MAY BE USED TO PERFORM OTHER DUTIES AS LONG AS PROMPT ATTENTION IS GIVEN TO THESE CALLS AND A PERSON IS READILY AVAILABLE CONTINUOUSLY 24 HOURS A DAY, TOAKS A WEEK AND A PROVINCES CALLS AND EDITAGES. TOAYS A WEEK. ALL LAMP OUTAGES, CABLE OUTAGES, ELECTRICAL FAILURES, EQUIPMENT MALFUNCTIONS AND MISALIGNED SIGNAL HEADS SHALL BE CORRECTED TO THE SATISFACTION OF THE ENGINEER WITH THE SIGNAL BACK TO SERVICE WITHIN FOUR HOURS AFTER THE CONTRACTOR HAS BEEN NOTIFIED

IN THE EVENT NEW SIGNALS ARE DAMAGED PRIOR TO ACCEPTANCE, ALL DAMAGED EQUIPMENT EXCEPT POLES AND CONTROL EQUIPMENT SHALL BE REPLACED BY THE CONTRACTOR TO THE SATISFACTION OF THE ENGINEER WITH THE SIGNAL BACK IN SERVICE WITHIN 8 HOURS AFTER THE CONTRACTOR'S NOTIFICATION OF THE OUTAGE. THE CONTRACTOR SHALL ARRANGE FOR FULL TRAFFIC CONTROL UNTIL THE SIGNAL IS BACK IN OPERATION.

IF POLES AND/OR CONTROL EQUIPMENT ARE DAMAGED AND MUST BE REPLACED, THE CONTRACTOR SHALL MAKE TEMPORARY REPAIRS AS NECESSARY TO BRING THE SIGNAL BACK INTO FULL OPERATION WITHIN THE ALLOWED 8-HOUR PERIOD, AND SHALL MAKE PERMANENT REPAIRS OR REPLACEMENT AS SOON THERE AFTER AS POSSIBLE.

NONE OF THE ABOVE SHALL BE CONSTRUED AS COLLECTIVE OR CONSECUTIVE NONE OF THE ABOVE SHALL BE CONSTRUED AS COLLECTIVE OR CONSECUTIVE OUTAGE TIME PERIODS AT ANY ONE LOCATION. THAT IS WHERE MORE THAN ONE OUTAGE OCCURS AT ANY ONE LOCATION, THEN THE ALLOTTED TIME LIMIT SHALL BE FOR THE WORST SINGLE OUTAGE. WHERE OUTAGES ARE THE DIRECT RESULT OF A VEHICLE ACCIDENT, THE RESPONSE OF THE CONTRACTOR SHALL BE AS OUTLINED ABOVE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR COLLECTION OF ANY COMPENSATION FOR THIS WORK FROM THOSE PARTIES DESCRIPTIVE FOR THE DAMAGE. RESPONSIBLE FOR THE DAMAGE.

WHERE THE CONTRACTOR HAS FAILED TO, OR CANNOT RESPOND TO, AN OUTAGE OR SIGNAL EQUIPMENT MALFUNCTION AT THESE LOCATIONS WITHIN HIS RESPONSIBILITY, WITHIN PERIODS AS SPECIFIED ABOVE, THE ENGINEER MAY INVOKE THE PROVISIONS OF SECTION 105.15 AND ANY SUBSEQUENT BILLINGS TO STATE OR THE CITY OF ASHLAND FOR POLICE SERVICES AND MAINTENANCE SERVICES BY CITY FORCES SHALL BE DEDUCTED FROM MONIES DUE OR TO BECOME DUE THE CONTRACTOR IN ACCORDANCE WITH PROVISIONS OF SECTION

THE CONTRACTOR SHALL PROVIDE THE MAINTENANCE SERVICE ENTIRELY WITH HIS FORCES OR HE MAY CHOOSE TO ENTER INTO A COOPERATIVE UNDERSTANDING WITH THE LOCAL MAINTAINING AGENCY TO PROVIDE THE MAINTENANCE. THE CONTRACTOR SHALL INFORM THE ENGINEER, IN WRITING, OF THE MAINTENANCE METHOD SELECTED.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE TO ANY TRAFFIC SIGNAL COMPONENTS REQUIRED TO BE HANDLED DURING THE RELOCATION OF POLES AND REVISIONS TO THE SIGNAL SYSTEM.

WHEN A TRAFFIC SIGNAL MUST BE TAKEN OUT OF SERVICE BY THE WHEN A TRAFFIC SIGNAL MOST BE TAKEN OUT OF SERVICE BY THE
CONTRACTOR, DUE TO CONSTRUCTION PROCEDURES THIS OUTAGE SHALL NOT
EXCEED 12 HOURS AND SHALL NOT INCLUDE THE HOURS OF 6:00 AM TO 6:00
PM. ANY SIGNALIZED INTERSECTION, WHERE THE SIGNAL IS OUT OF SERVICE
DUE TO CONSTRUCTION PROCEDURES, OR DUE TO AN OUTAGE OR MALFUNCTION
OF EQUIPMENT AS DESCRIBED ABOVE, SHALL BE PROTECTED, BY THE
CONTRACTOR, BY THE INSTALLATION OF TEMPORARY "STOP" SIGNS. ANY
VENTOUS ARE TRAFFIC SIGNAL MEAD. ETHER NEW OF EXISTING WHICH BE VEHICULAR TRAFFIC SIGNAL HEAD, EITHER NEW OR EXISTING WHICH WILL BE OUT OF OPERATION SHALL BE CÓVERED IN THE MANNER DESCRIBED IN 632.25.

### <u>ITEM 614 - MAINTENANCE OF TRAFFIC SIGNAL INSTALLATION</u> (CONTINUED)

THE CONTRACTOR SHALL MAINTAIN COMPLETE RECORDS OF MALFUNCTIONS INCLUDING:

1. TIME OF NOTIFICATION OF MALFUNCTION; 2. TIME OF WORK CREWS ARRIVAL TO CORRECT THE MALFUNCTION; 3. ACTIONS TAKEN TO CORRECT THE MALFUNCTION, INCLUDING A LIST OF PARTS REPAIRED OR REPLACED;

4. A DIAGNOSIS OF REASON FOR THE MALFUNCTION AND PROBABILITY OF REOCCURRENCE;

5. TIME OF COMPLETION OF THE REPAIR AND SYSTEM RESTORED TO FULL

A COPY OF THESE RECORDS SHALL BE PROVIDED TO THE ENGINEER WITHIN THREE (3) WORKING DAYS FOLLOWING COMPLETION OF EACH REPAIR. ALL COSTS RESULTING FROM THE ABOVE REQUIREMENTS SHALL BE CONSIDERED TO BE INCLUDED IN THE LUMP SUM PRICE BID FOR ITEM 614, MAINTAINING

#### <u> ITEM 809 - STOP BAR DETECTION (WAVETRONIX)</u>

THIS ITEM OF WORK SHALL CONSIST OF FURNISHING AND INSTALLING A WAVETRONIX SMARTSENSOR MATRIX DETECTION UNIT. THE DETECTION UNIT SHALL INCLUDE THE FOLLOWING:

- 1. POWER SHALL BE PROVIDED FROM THE TRAFFIC CABINET.
- 2. ALL REQUIRED INPUTS CARDS SHALL BE INCLUDED IN THE TRAFFIC CABINET AND SHALL BE COMPATIBLE WITH CALTRANS, NEMA TSI AND NEMA TS2
  DETECTOR RACKS. THE CARDS SHALL PROVIDE TRUE PRESENCE DETECTOR CALLS
  OR CONTACT CLOSURE TO THE TRAFFIC CONTROLLER.
- 3. THE UNIT SHALL BE MOUNTED DIRECTLY TO A POLE OR MAST ARM, AS RECOMMENDED BY THE MANUFACTURER. CABLE(S) SHALL BE PROVIDED AS REQUIRED AND RECOMMENDED BY THE MANUFACTURER.
- 4. SURGE PROTECTION DEVICES, AS RECOMMENDED BY THE MANUFACTURER SHALL BE INCLUDED BOTH AT THE POLE WHERE THE UNIT IS LOCATED TO PROTECT THE UNIT AND IN THE TRAFFIC CABINET TO PROTECT THE CABINET ELECTRONICS.
- 5. THE MANUFACTURER'S REPRESENTATIVE SHALL BE ON SITE DURING INSTALLATION AND TESTING AND SHALL PROVIDE ONSITE TRAINING ON THE SETUP, OPERATION AND MAINTENANCE OF THE UNIT.
- 6. A SERIAL TO ETHERNET COMMUNICATIONS MODULE AND ETHERNET CABLE (MINIMUM 7 FEET).
- 7. THE POWER SUPPLY AND COMMUNICATION MODULES SHALL BE SECURED TO A SINGLE PANEL THAT CAN BE MOUNTED INTERIOR TO THE TRAFFIC CABINET.
  THE PANEL SHALL INCLUDE MODULAR-PLUG STYLE CONNECTIONS FOR UP TO
  FOUR (4) SENSOR CABLES. ADDITIONAL SENSORS MAY BE HARD-WIRED TO THE COMMUNICATION MODULES, AS NECESSARY.

PAYMENT FOR ITEM 809 STOP-BAR RADAR DETECTION SHALL BE MADE AT THE CONTRACT UNIT PRICE FOR EACH UNIT, COMPLETE AND IN PLACE INCLUDING ALL REQUIRED CABINET HARDWARE, MOUNTING BRACKETS, CABLES, CONDUIT AND CONNECTIONS TESTED AND ACCEPTED.

G

#### ITEM 809 - ADVANCE DETECTION (WAVETRONIX)

THIS ITEM OF WORK SHALL CONSIST OF FURNISHING AND INSTALLING A WAVETRONIX SMARTSENSOR ADVANCE DETECTION UNIT (MODEL SS-200E). THE DETECTION UNIT SHALL INCLUDE THE FOLLOWING:

- 1. POWER SHALL BE PROVIDED FROM THE TRAFFIC CABINET.
- 2. ALL REQUIRED INPUTS CARDS SHALL BE INCLUDED IN THE TRAFFIC CABINET AND SHALL BE COMPATIBLE WITH CALTRANS, NEMA TSI AND NEMA TS2 DETECTOR RACKS. THE CARDS SHALL PROVIDE TRUE PRESENCE DETECTOR CALLS OR CONTACT CLOSURE TO THE TRAFFIC CONTROLLER.
- 3. THE UNIT SHALL BE MOUNTED DIRECTLY TO A POLE OR MAST ARM, AS RECOMMENDED BY THE MANUFACTURER. CABLE(S) SHALL BE PROVIDED AS REQUIRED AND RECOMMENDED BY THE MANUFACTURER.
- 4. SURGE PROTECTION DEVICES, AS RECOMMENDED BY THE MANUFACTURER SHALL BE INCLUDED BOTH AT THE POLE WHERE THE UNIT IS LOCATED TO PROTECT THE UNIT AND IN THE TRAFFIC CABINET TO PROTECT THE CABINET
- 5. THE MANUFACTURER'S REPRESENTATIVE SHALL BE ON SITE DURING INSTALLATION AND TESTING AND SHALL PROVIDE ONSITE TRAINING ON THE SETUP, OPERATION AND MAINTENANCE OF THE UNIT.
- 6. A SERIAL TO ETHERNET COMMUNICATIONS MODULE AND ETHERNET CABLE (MINIMUM 7 FEET).
- 7. THE POWER SUPPLY AND COMMUNICATION MODULES SHALL BE SECURED TO A SINGLE PANEL THAT CAN BE MOUNTED INTERIOR TO THE TRAFFIC CABINET. THE PANEL SHALL INCLUDE MODULAR-PLUG STYLE CONNECTIONS FOR UP TO FOUR (4) SENSOR CABLES. ADDITIONAL SENSORS MAY BE HARD-WIRED TO THE COMMUNICATION MODULES, AS NECESSARY.

PAYMENT FOR ITEM 809 ADVANCE RADAR DETECTION SHALL BE MADE AT THE CONTRACT UNIT PRICE FOR EACH UNIT, COMPLETE AND IN PLACE INCLUDING ALL REQUIRED CABINET HARDWARE, MOUNTING BRACKETS, CABLES, CONDUIT, CONNECTIONS TESTED AND ACCEPTED, AND ANY OTHER NECESSARY HARDWARE TO ESTABLISH A FULLY FUNCTIONAL DETECTION SYSTEM.

		SHEET NUM.			PART.	ITEM	ITEM	GRAND	UNIT	DESCRIPTION	SEE SHEET NO.	ALCULATED STO CHECKED CAD		
	6	9				01/SAF/OT	02/SAF/O T	11200	EXT	TOTAL	0/11/	DESCRIPTION	NO.	CALC
								205	7,510		51011	TRAFFIC SIGNALS		
		41 16				41 16		625 632	31510 05007	41 16	EACH EACH	PULL BOX REMOVED  VEHICULAR SIGNAL HEAD, (LED), 3-SECTION, 12" LENS, 1-WAY, POLYCARBONATE, AS PER PLAN BLACK	5	-
		3,145				3,145		632	40500	3,145	FT	SIGNAL CABLE, 5 CONDUCTOR, NO. 14 AWG		1
		3,630				3,374	256	632	90500	3,630	FT	SIGNALIZATION, MISC.:UNLASH AND RELASH MESSENGER WIRE	5	
		1					1	632	90020	1	EACH	REMOVAL OF MISCELLANEOUS TRAFFIC SIGNAL ITEM VIDEO DETECTION	5	4
$\circ$		39 4				35	4 4	809 809	69000 69100	39 4	EACH EACH	ADVANCE RADAR DETECTION STOP-BAR RADAR DETECTION	7 6	
												MAINTENANCE OF TRAFFIC		
	120					120		614	11110	120	HOUR	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE	6	-
												INCIDENTALS		
						LS		103 614	05000 11000	LS LS		PREMIUM FOR CONTRACT PERFORMANCE BOND AND FOR PAYMENT BOND MAINTAINING TRAFFIC		4
						LS LS		623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	+	┪ 、
$\bigcirc$						LS		624	10000	LS		MOBILIZATION	+	<b>→</b>
														UMMAR
														<b>∮</b> ≦
														SU
														AL
														<u> </u>
														GENER
														_
													+	1
														_
								_						-
														4
														1
														-
														1
Qqu	<u></u>													-
0 000														1
37 G				<u> </u>	1									<del></del>
0759														1
\\\ \\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\	ó													018
Hee														20   10   10   10   10   10   10   10   1
) }														<b>↓≻</b>
														┨╙
) og/														დ ყ
Sign	<u></u>												_	⊣ູທ ັ
7\De														<b>                                     </b>
10759														03
9+9														
3c+D														
.07													<u> </u>	$\frac{1}{8}$
<u></u>	<u>.</u>													$1 \overset{\smile}{\smile}$

809-Advance and Stop Bar Radar General Layout

Stop Bar

1

\*\*Drawing not to Scale\*\*

A) Number of lanes may vary, detection is required in each approach lane.

B) Each Stop Bar detector zone shall have seperate controller inputs.

D Dilemma Zone Radar Detection Unit

7

Dilemma and Stop Bar Radar Unit placements vary by location. Typical locations shown in drawing. Follow manufacturer's recommendations for

Dilemma Zone unit placement on existing bracket arm on far side of intersection not shown but recommended where available.

DOS

Stop Bar Radar Detection Unit

Advanced Detection Zone

placement location.

SUMMARY

Advanced Detection Zone

<b>&gt;</b>	
L	
· F	S
5	$\overline{}$
S	
_	
3	
$\mathbf{c}$	

(	9	1
$\Box$	a	7

					625	632	632	632	632	809	80
COUNTY	ROUTE	SLM	CROSSROAD/ LOCATION		PULL BOX REMOVED	VEHICULAR SIGNAL HEAD, (LED), 3-SECTION, 12" LENS, 1-WAY, POLYCARBONATE, AS PER PLAN	SIGNAL CABLE, 5 CONDUCTOR, NO. 14 AWG	SIGNALIZATION, MISC.: UNLASH AND RELASH MESSENGER WIRE	REMOVAL OF MISC. TRAFFIC CONTROL ITEM: VIDEO DETECTION	ADVANCE RADAR DETECTION	STOP-RAR DETECTION
					EA	EA	FT	FT	EA	EA	EA
ASD	US 250	1.61	US 224					129		4	
ASD	US 250	16.25	SUGARBUSH DR					273		2	
ASD	US 250	16.45	GEORGE RD			2	400	230		2	
ASD	US 250	17.08	TR 743		6	2	394	228		2	
ASD	US 250	17.31	CR 1575		5	2	245	167		2	
ERI	US 250	8.75	HURON AVERY RD		2	2	541			2	
ERI	US 250	8.90	MASON RD		4					2	
ERI	US 250	10.63	MUDBROOK RD		4	1	289	165		2	
ERI	US 250	11.75	SHAW MILL RD		7			153		2	
HUR	US 250	5.78	OLD STATE/ TOWNLINE RD					357		2	
LOR	US 20	6.59	SR 58	+				256	1	4	4
LOR	SR 2	3.32	BAUMHART RD EB		5			138		2	
LOR	SR 2	3.35	BAUMHART RD WB	+	4			181		2	
MED	US 224	15.46	LAKE RD	+				392		1	
WAY	US 30	20.15	SR 57			2	290	173		2	
WAY	US 250	24.37	KIDRON RD		1	1	163			2	
WAY	US 21	3.89	EDWARDS RD		3	2	260	414		2	
WAY	US 21	5.86	EASTERN RD			2	563	374		2	
		ENERAL S									

				625	632	632	632	632	809	809
COUNTY	ROUTE	SLM	CROSSROAD/ LOCATION	PULL BOX REMOVED	VEHICULAR SIGNAL HEAD, (LED), 3-SECTION, 12" LENS, 1-WAY, POLYCARBONATE, AS PER PLAN	SIGNAL CABLE, 5 CONDUCTOR, NO. 14 AWG	SIGNALIZATION, MISC.: UNLASH AND RELASH MESSENGER WIRE	REMOVAL OF MISC. TRAFFIC CONTROL ITEM: VIDEO DETECTION	ADVANCE RADAR DETECTION	STOP-BAR DETECTION
				EA	EA	FT	FT	EA	EA	EA
ASD	US 250	1.61	US 224				129		4	
ASD	US 250	16.25	SUGARBUSH DR				273		2	
ASD	US 250	16.45	GEORGE RD		2	400	230		2	
ASD	US 250	17.08	TR 743	6	2	394	228		2	
ASD	US 250	17.31	CR 1575	5	2	245	167		2	
ERI	US 250	8.75	HURON AVERY RD	2	2	541			2	
ERI	US 250	8.90	MASON RD	4					2	
ERI	US 250	10.63	MUDBROOK RD	4	1	289	165		2	
ERI	US 250	11.75	SHAW MILL RD	7			153		2	
HUR	US 250	5.78	OLD STATE/ TOWNLINE RD				357		2	
LOR	US 20	6.59	SR 58				256	1	4	4
LOR	SR 2	3.32	BAUMHART RD EB	5			138	,	2	,
LOR	SR 2	3.35	BAUMHART RD WB	4			181		2	
MED	US 224	15.46	LAKE RD				392		1	
WAY	US 30	20.15	SR 57		2	290	173		2	
WAY	US 250	24.37	KIDRON RD	1	1	163			2	
WAY	US 21	3.89	EDWARDS RD	3	2	260	414		2	
WAY	US 21	5.86	EASTERN RD		2	563	374		2	
OTALS CAR	RIED TO GE	ENERAL S	SUMMARY	41	16	3145	3630	1	39	4

 $\bigcirc$ 

 $\bigcirc$ 

 $\bigcirc$