


GENERAL SUMMARY	
DESIGN AGENCY	
	
DESIGNER	
GCB	
REVIEWER	
DTC	10/03/25
PROJECT ID	
116205	
SHEET	TOTAL
P.19	52

STATION RANGE			TYPICAL SECTION	SIDE	DISTANCE (D)	AVERAGE WIDTH (W)	SURFACE AREA (A) A=DxW/9	CADD GENERATED AREA	SPLIT	202	204	209	254	301	304	407	442	442	617	618	875						
					PAVEMENT REMOVED	SUBGRADE COMPACTION	LINEAR GRADING	PAVEMENT PLANING, ASPHALT CONCRETE, 3 1/4"		ASPHALT CONCRETE BASE, PG64-22, (449)	AGGREGATE BASE	TACK COAT	ASPHALT CONCRETE SURFACE COURSE, 12.5 MM, TYPE A (446)	ASPHALT CONCRETE INTERMEDIATE COURSE, 12.5 MM, TYPE A (446)	COMPACTED AGGREGATE	RUMBLE STRIPS, SHOULDER (ASPHALT CONCRETE)	LONGITUDINAL JOINT ADHESIVE										
																		FT	FT	SY	SF	SY	SY	MILE	SY	CY	CY
S.R. 795																											
93+10.75	TO	100+90.69	A		779.94	50.25	4354.39	39189.52	03/S>2				4354.39			609.61	181.43	211.67			584.96						
101+23.43	TO	106+10.00	A		486.57	52.39	2832.30	25490.70	03/S>2				2832.30			396.52	118.01	137.68			364.93						
106+10.00	TO	109+72.86	B		362.86	78.26	3155.45	28399.05	03/S>2			0.18	3155.45			441.76	131.48	153.39	8.96	726	272.15						
109+72.86	TO	111+38.57	C		165.71	76.56	1409.65	12686.83	03/S>2			0.14	1409.65			197.35	58.74	68.52	4.09	331	82.85						
111+38.57	TO	112+46.04	D		107.47	86.15	1028.74	9258.68	03/S>2			0.06	1028.74			144.02	42.86	50.01	2.65	215	80.60						
112+46.04	TO	118+55.00	D		608.96	85.08	5756.62	51809.60	02/NHS			0.04	5756.62			805.93	239.86	279.84	15.04	1218	456.72						
118+55.00	TO	119+19.00	E		64.00	81.76	581.43	5232.83	01/BRO	575.52	594.66	0.02		142.88	99.11	96.16	24.23	28.26	1.36	120	32.00						
119+19.00	TO	119+53.18	F		34.18	47.30	179.64	1616.72	01/BRO	181.96	192.26	0.01		45.95	32.04	30.10	7.48	8.73	0.60	45	5.05						
119+53.18	TO	119+77.51			24.33	87.19	235.70	2121.34	01/BRO						39.28												
124+04.12	TO	124+28.45			24.33	87.19	235.70	2121.34	01/BRO						39.28												
124+28.45	TO	124+95.00	G		66.55	88.73	656.14	5905.23	01/BRO	647.86	784.96	0.03		188.36	174.43	114.62	27.34	31.90	1.96	163	41.04						
TOTALS CARRIED TO GENERAL SUMMARY										1406	2044	0.48	18538	378	385	2837	832	970	35	2818	1921						
ROUTE	INTERSECTING STREET	STATION	SIDE	LENGTH	MOUTH	THROAT	SURFACE AREA (A) A=DxW/9	CADD GENERATED AREA	SPLIT	254		407		442	442												
										PAVEMENT PLANING, ASPHALT CONCRETE, 3 1/4"		TACK COAT		ASPHALT CONCRETE SURFACE COURSE, 12.5 MM, TYPE A (449)	ASPHALT CONCRETE INTERMEDIATE COURSE, 12.5 MM, TYPE A (449)												
S.R. 795	MCCARTHY DR.	97+28.67	LT	22.00	92.81	26.09	108.18	973.58	03/S>2	108.18		15.14		4.51	5.26												
S.R. 795	SIMMONS RD.	105+91.00	LT	18.78	121.82	55.14	163.71	1473.40	03/S>2	163.71		22.92		6.82	7.96												
S.R. 795	SIMMONS RD.	105+91.00	RT	21.06	83.12	37.07	115.53	1039.77	03/S>2	115.53		16.17		4.81	5.62												
S.R. 795	WYANDOT PL	112+46.04	LT	33.43	20.74	8.13	41.32	371.90	03/S>2	41.32		5.79		1.72	2.01												
S.R. 795	WYANDOT PL	112+46.04	LT	33.43	27.06	9.91	44.57	401.10	02/NHS	44.57		6.24		1.86	2.17												
S.R. 795	SB I-75 RAMP	112+46.04	RT	73.51	99.00	39.25	431.73	3885.59	03/S>2	431.73		60.44		17.99	20.99												
S.R. 795	SB I-75 RAMP	112+46.04	RT	73.51	146.42	47.35	534.72	4812.44	02/NHS	534.72		74.86		22.28	25.99												
TOTALS CARRIED TO GENERAL SUMMARY										1440		202		60	70												

PAVEMENT SUBSUMMARY

DESIGN AGENCY



DESIGNER

GCB

REVIEWER

DTC 10/03/25

PROJECT ID

116205

SHEET

P.22

TOTAL

52