



- NOTES:
1. THE MEDIAN JUNCTION BOX, AS PER PLAN SHALL MEET THE SPECIFICATIONS AS DESCRIBED ON SHEET 21.
 2. THE REMOVAL OF THE EXISTING EQUIPMENT SHALL COORDINATED AS DESCRIBED ON SHEET 21.
 3. PROPOSED RACEPIPES SHALL BE INSTALLED IN ASPHALT & AND PLACED 4" ±1/2" BELOW FINAL SURFACE COURSE.
 4. PROPOSED RACEPIPE LOCATIONS SHALL BE MARKED ON PROPOSED MEDIAN BARRIER.
 5. THE PROPOSED 3" CONDUIT SHALL CONNECT THE TWO PROPOSED MEDIAN JUNCTION BOXES, AS PER PLAN.
 6. RACEPIPE ENDS SHALL BE SECURED WITH PLUMBERS DUCT SEAL (ONE POUND BLOCK PER RACEPIPE).
 7. PAYMENT SHALL BE IN ACCORDANCE TO NOTES ON SHEET 21.

P:\89130\Design\Roadway\Sheets\89130_GM001.dgn Sheet 3/11/2020 2:23:46 PM mcornett