


Belmont 40 Arch Bridge Superstructure Reconstruction

Calculated: ETB 2/7/25
Checked: DBW 2/20/25


- APPLY CONSTRUCTION DEAD LOAD (CDL) OF 15 psf x 50' WIDE = 750PLF TO ACCOUNT FOR PROTECTIVE DECKING / DEBRIS CONTAINMENT.
- APPLY CONSTRUCTION DEAD LOAD (CDL) OF 50psf x 19' WIDE TO ACCOUNT FOR CRANE MATS ON CENTER 5 SLAB BEAMS + 375 PLF FOR H-PILES ON SLAB BEAMS. TOTAL CONSTRUCTION DEAD LOAD IN CRANE MAT REGION = 70PSF
- APPLY CONSTRUCTION LIVE LOAD (CLL) OF 25 psf x 50' WIDE = 1,250 PLF TO ACCOUNT FOR PERSONNEL AND MISC. EQUIPMENT.
- APPLY CONSTRUCTION LIVE LOAD (CR) OF CAT 336 EXCAVATOR: 81,000 lb (ON 2 TRACKS APPROX. 13' LONG) AND SU4 TRUCK (54,000lb)



ETB: I will apply the construction dead load to the cap beams as element beam loads and the construction live load as pressure loads to the deck elements. There are 5 different cap beam load magnitudes for each construction live load and dead load based upon tributary spacing of cap beams. Grouped in the model using the groups shown below. They are:

- Group A Caps, 15.125' say 11.34k/42.5' = 0.267klf for construction dead load
- Group B Caps, 14' say 10.5k/42.5' = 0.247klf for construction dead load
- Group C Caps, 14.125' say 10.59k/42.5' = 0.249klf for construction dead load
- Group D Caps, 15.75' say 11.81k/42.5' = 0.278klf for construction dead load
- Group E Caps, 15.625' say 11.72k/42.5' = 0.275klf for construction dead load

- Models created for various stages of construction, with both columns and arches investigated.
- Assume excavator weight is 81k + slab beam pick (20'x4'x1' = 12k) and has an axle spacing of 13.25'. Total axle load is 46.5k. SU4 truck is 54k (including slab beam loads) and follows the traditional AASHTO axle weights and spacings. Keep a minimum distance of 10' between excavator and wheel loader.
- Assume the excavator/truck is primarily confined to the CL of the bridge. The truck will transport each slab beam to the excavator, which will pick the slab beam and move it into place. No other heavy construction vehicle will be on the bridge with the excavator and wheel loader.
- Braking force, BR, will be 10% of the weight of the excavator + truck: $0.1 \cdot (46.5k \cdot 2 + 54k) / 42.5' = 0.35klf$ applied to the cap elements. Assume this load is distributed to only one cap for conservatism. All stages of construction were analyzed for column loads without braking force, and then the two cases with the highest D/C ratios were re-run with the braking force included.
- Previous demo iterations have shown that the arch is sensitive to unbalanced load conditions. The first attempt to rebuild the deck will consist of starting at the west end of Arch A and building out each slab beam span in full width before moving east into the next slab beam span. If this approach does not work, I will try building Arch Span A in full width slab beam spans evenly from both the east and west simultaneously.
- For Arches A and B, the demolition steps have been furthest discretized. Since Arches C and D bridge decks will be deconstructed most similarly to Arch B, only a couple Arch C and D stages will be modeled to save time. These stages will be chosen based upon those governing Arch B stages.





TRANSVERSE DECK SECTION THRU ARCH SPANS
Transverse Section Showing Bridge Demolition Initial Sequence and Excavator Placement

CONSTRUCTION STAGE LOAD COMBINATIONS:

- STR-I: $1.25x(DC) + 1.5x(CDL + CLL) + 1.5x(CR + IM + BR) + 0.50x(TU)$
 - ~~STR-II: $1.25x(DC) + 1.25x(CR + CLL) + 0.50x(TU) + 1.0x(WS)$~~
 - STR-VA: $1.25x(DC) + 1.25x(CDL) + 1.35x(CLL) + 1.35x(CR) \times (1.1) + 1.0x(TU) + 1.0x(CW)$
 - STR-X: $1.4x(DC) + 1.4x(CDL + CLL) + 1.4x(CR) \times (1.1) + 1.0x(TU)$
 - SVC-1: $1.0x(DC) + 1.0x(CDL + CLL) + 1.0x(CR + IM + BR) + 1.0x(CW) + 1.0(TU)$
- NOTE:
- DC = PERMANENT DEAD LOAD
 - CDL = CONSTRUCTION DEAD LOAD
 - CLL = CONSTRUCTION LIVE LOAD
 - CR = CRANE & EQUIVALENT MLBO LOAD
 - IM = DYNAMIC ALLOWANCE (10%)
 - TU = UNIFORM TEMPERATURE FORCE EFFECT
 - WS = WIND LOAD ON STRUCTURE DURING CONSTRUCTION ("INACTIVE" WIND)
 - CW = CONSTRUCTION WIND LOAD ("ACTIVE" WIND OF 20 MPH)
 - BR = 10% OF CR IN THE LONGITUDINAL DIRECTION

IGNORE FOR INITIAL PROOF OF CONCEPT CHECKS


IGNORE THERMAL AND WIND FOR INITIAL PROOF OF CONCEPT CHECKS



336 Hydraulic Excavator Specifications

Dimensions

All dimensions are approximate and may vary depending on bucket selection.



Undercarriage Option	Long Wide Undercarriage			
	Reach Boom 6.5 m (21'4")		Mass Boom 6.18 m (20'3")	
Boom Options	Reach Stick		Mass Stick	
Stick Options	R3.9DB (12'10")	R3.2DB (10'6")	M2.55TB (8'4")	
1 Machine Height:				
Cab height	3180 mm 10'5"	3180 mm 10'5"	3180 mm 10'5"	
OPG height	3330 mm 10'11"	3330 mm 10'11"	3330 mm 10'11"	
Guardrails/Handrails Height	3180 mm 10'5"	3180 mm 10'5"	3180 mm 10'5"	
With Boom/Stick/Bucket Installed	3660 mm 12'0"	3480 mm 11'5"	3610 mm 11'10"	
With Boom/Stick Installed	3560 mm 11'8"	3330 mm 10'11"	3410 mm 11'2"	
With Boom Installed	2880 mm 9'5"	2880 mm 9'5"	2830 mm 9'3"	
With Boom/Stick/Bucket Installed (with auxiliary lines)	3670 mm 12'0"	3530 mm 11'7"	3620 mm 11'11"	
With Boom/Stick Installed (with auxiliary lines)	3620 mm 11'11"	3410 mm 11'2"	3420 mm 11'3"	
With Boom Installed (with auxiliary lines)	2970 mm 9'9"	2970 mm 9'9"	2900 mm 9'6"	
2 Machine Length:				
With Boom/Stick/Bucket Installed	11 180 mm 36'8"	11 160 mm 36'7"	10 870 mm 35'8"	
With Boom/Stick Installed	11 170 mm 36'8"	11 120 mm 36'6"	10 830 mm 35'6"	
With Boom Installed	9960 mm 32'8"	9960 mm 32'8"	9640 mm 31'8"	
With Boom/Stick/Bucket Installed (with auxiliary lines)	11 180 mm 36'8"	11 160 mm 36'7"	10 870 mm 35'8"	
With Boom/Stick Installed (with auxiliary lines)	11 170 mm 36'8"	11 120 mm 36'6"	10 830 mm 35'6"	
With Boom Installed (with auxiliary lines)	10 010 mm 32'10"	10 010 mm 32'10"	9640 mm 31'8"	
With Boom Installed (with auxiliary lines)	2970 mm 9'9"	2970 mm 9'9"	2970 mm 9'9"	
3 Upperframe Width without Walkways				
2970 mm 9'9"	2970 mm 9'9"	2970 mm 9'9"	2970 mm 9'9"	
4 Tail Swing Radius				
3530 mm 11'7"	3530 mm 11'7"	3530 mm 11'7"	3530 mm 11'7"	
5 Counterweight Clearance				
1260 mm 4'2"	1260 mm 4'2"	1260 mm 4'2"	1260 mm 4'2"	
6 Ground Clearance				
510 mm 1'8"	510 mm 1'8"	510 mm 1'8"	510 mm 1'8"	
7 Track Length – Length to Center of Rollers				
4040 mm 13'3"	4040 mm 13'3"	4040 mm 13'3"	4040 mm 13'3"	
8 Track Length				
5030 mm 16'6"	5030 mm 16'6"	5030 mm 16'6"	5030 mm 16'6"	
9 Track Gauge – Extended				
2740 mm 9'0"	2740 mm 9'0"	2740 mm 9'0"	2740 mm 9'0"	
10 Track Width/Undercarriage Width (with steps):				
700 mm (28") Shoes	3440 mm 11'3"	3440 mm 11'3"	3440 mm 11'3"	
800 mm (31") Shoes	3540 mm 11'7"	3540 mm 11'7"	3540 mm 11'7"	
850 mm (33") Shoes	3590 mm 11'9"	3590 mm 11'9"	3590 mm 11'9"	
Bucket Type	HD	HD	SDV	
Bucket Capacity	2.00 m³ 2.61 yd³	2.00 m³ 2.61 yd³	2.41 m³ 3.15 yd³	
Bucket Tip Radius	1790 mm 5'9"	1790 mm 5'9"	1910 mm 6'3"	

336 Hydraulic Excavator Specifications

Engine

Engine Model	Cat® C7.1 TTA	
Net Power	223.5 kW	300 hp
ISO 9249	223.5 kW	300 hp
ISO 9249 (DIN)	304 hp (metric)	

Engine Power	225 kW	302 hp
ISO 14396	225 kW	302 hp
ISO 14396 (DIN)	306 hp (metric)	

Bore	105 mm	4 in
Stroke	135 mm	5 in
Displacement	7.01 L	428 in³

• Meets U.S. EPA Tier 4 Final, EU Stage V, and Japan 2014 emission standards.

• Recommended for use up to 4500 m (14,760 ft) altitude with engine power derate above 3000 m (9,840 ft).

• Advertised power is tested per the specified standard in effect at the time of manufacture.

• Net power is the power available at the flywheel when the engine is equipped with fan, air intake system, exhaust system, and alternator with engine speed at 2,000 rpm.

• All Cat nonroad U.S. EPA Tier 4 Final, EU Stage V, Japan 2014, Korea Stage V, India CEV Stage V, and China Nonroad Stage IV diesel engines are required to use ULSD (ultra-low sulfur diesel with 15 ppm of sulfur or less) or ULSD blended with the following lower-carbon intensity fuels** up to:

✓ 20% biodiesel FAME (fatty acid methyl ester)*

✓ 100% renewable diesel, HVO (hydro-treated vegetable oil) and GTL (gas-to-liquid) fuels

Refer to guidelines for successful application. Please consult your Cat dealer or "Caterpillar Machine Fluids Recommendations"

(SEBU6250) for details.

*Engines with no aftertreatment devices can use higher blends, up to 100% biodiesel.

**Tailpipe greenhouse gas emissions from lower-carbon intensity fuels are essentially the same as traditional fuels.

Swing Mechanism

Swing Speed	8.84 rpm	
Maximum Swing Torque	143 kN-m	105,250 lbf-ft

Weights

Operating Weight	36 800 kg	81,100 lb
------------------	-----------	-----------

• Long Wide Undercarriage, Reach Boom, R3.9DB (12'10") Stick, HD 2.12 m³ (2.77 yd³) Bucket, 850 mm (33") Triple Grouser Shoes, 6.8 mt (15,000 lb) Counterweight.

Track

Optional Track Shoes Width	850 mm	33 in
Optional Track Shoes Width	800 mm	31 in
Optional Track Shoes Width	700 mm	28 in

Number of Shoes (each side) 49

Number of Track Rollers (each side) 8

Number of Carrier Rollers (each side) 2

Drive

Maximum Gradeability	35%/70%	
Maximum Travel Speed	4.7 km/h	2.9 mph
Maximum Drawbar Pull	302.5 kN	68,005 lbf

Hydraulic System

Main System – Maximum Flow (Implement)	560 L/min (280 x 2 pumps)	148 gal/min (74 x 2 pumps)
--	---------------------------	----------------------------

Maximum Pressure – Equipment – Implement	35 000 kPa	5,076 psi
--	------------	-----------

Maximum Pressure – Equipment – Lift Mode	38 000 kPa	5,511 psi
--	------------	-----------

Maximum Pressure – Travel	35 000 kPa	5,076 psi
---------------------------	------------	-----------

Maximum Pressure – Swing	29 400 kPa	4,264 psi
--------------------------	------------	-----------

Boom Cylinder – Bore	150 mm	6 in
----------------------	--------	------

Boom Cylinder – Stroke	1440 mm	57 in
------------------------	---------	-------

Stick Cylinder – Bore	170 mm	7 in
-----------------------	--------	------

Stick Cylinder – Stroke	1738 mm	68 in
-------------------------	---------	-------

DB Bucket Cylinder – Bore	150 mm	6 in
---------------------------	--------	------

DB Bucket Cylinder – Stroke	1151 mm	45 in
-----------------------------	---------	-------

TB Bucket Cylinder – Bore	160 mm	6 in
---------------------------	--------	------

TB Bucket Cylinder – Stroke	1356 mm	53 in
-----------------------------	---------	-------

Service Refill Capacities

Fuel Tank Capacity	600 L	158.5 gal
Cooling System	39 L	10.2 gal
Engine Oil (with filter)	25 L	6.6 gal
Swing Drive	18 L	4.8 gal
Final Drive (each)	8 L	2.1 gal
Hydraulic System (including tank)	373 L	98.5 gal
Hydraulic Tank (including suction pipe)	161 L	42.5 gal
Diesel Exhaust Fluid (DEF) Tank	50 L	13.2 gal

Standards

Brakes	ISO 10265:2008
Cab/Operator Protective Guards (OPG) (optional)	ISO 10262:1998 Level II
Cab/Rollover Protective Structure (ROPS)	ISO 12117-2:2008

Sound Performance

ISO 6395:2008 (external)	105 dB(A)
ISO 6396:2008 (inside cab)	72 dB(A)


• Hearing protection may be needed when operating with an open operator station and cab (when not properly maintained or doors/windows open) for extended periods or in a noisy environment.

Air Conditioning System

The air conditioning system on this machine contains the fluorinated greenhouse gas refrigerant R134a (Global Warming Potential = 1430). The system contains 1.00 kg of refrigerant, which has a CO₂ equivalent of 1,430 metric tonnes.

27 T; 18'

SU4




ASSUME EXCAVATOR IS CENTERED IN 14' SPAN AND REACHES TO ADJACENT 14' SPAN
PICK RADIUS = 7' + 7' = 14' (SAY 15')

ASSUME EXCAVATOR IS CENTERED IN 14' SPAN AND REACHES TO ADJACENT 20'-3" SPAN
PICK RADIUS = 7' + 10'-1.5" = 17'-1.5" (SAY 20')

LIFT CAPACITY IS GREATER THAN 20,000 lb.


REPRESENTATIVE TRUCK DEFINED IN MIDAS FOR EXCAVATOR PLUS SU4 TRUCK




Comparison of Floorbeam Maximum Positive Moments in Final Condition vs. During Construction

Compare the original/final condition dead and live load to the construction conditions. Up to three lanes of SU7 can load the floorbeam during the original/final condition. During construction, one lane of loader/excavator can be on the bridge, in addition to crane mats and protective decking.


Final Condition, Unfactored DL+LL+IM (SU7) BEL 40 Iteration 3 Rehabilitation Model.mcb




Demo Condition, Unfactored DL+LL+IM (Excavator + Loader) BEL 40 Iteration 3 Demo Analysis Arch Model Construction Loading.mcb




Conclusion: The demo condition, which adds the dead loads of crane mats and protective decking to the bridge, has lower unfactored floorbeam moments than the original/final condition bridge. The change in dead load is smaller than the change in live loading (SU7's versus a single excavator).




BEL 40 Iteration 3 Deck Reconstruction Analysis Stage 1.mcb




BEL 40 Iteration 3 Deck Reconstruction Analysis Stage 2.mcb




BEL 40 Iteration 3 Deck Reconstruction Analysis Stage 3.mcb




BEL 40 Iteration 3 Deck Reconstruction Analysis Stage 4.mcb
 *No construction Live load included in this case




BEL 40 Iteration 3 Deck Reconstruction Analysis Stage 5.mcb




BEL 40 Iteration 3 Deck Reconstruction Analysis Stage 6.mcb




BEL 40 Iteration 3 Deck Reconstruction Analysis Stage 7.mcb




BEL 40 Iteration 3 Deck Reconstruction Analysis Stage 8.mcb




BEL 40 Iteration 3 Deck Reconstruction Analysis Stage 9.mcb




BEL 40 Iteration 3 Deck Reconstruction Analysis Stage 10.mcb




BEL 40 Iteration 3 Deck Reconstruction Analysis Stage 11.mcb




BEL 40 Iteration 3 Deck Reconstruction Analysis Stage 12.mcb




BEL 40 Iteration 3 Deck Reconstruction Analysis Stage 13.mcb




BEL 40 Iteration 3 Deck Reconstruction Analysis Stage 14.mcb




BEL 40 Iteration 3 Deck Reconstruction Analysis Stage 15.mcb




BEL 40 Iteration 3 Deck Reconstruction Analysis Stage 16.mcb




BEL 40 Iteration 3 Deck Reconstruction Analysis Stage 17.mcb




BEL 40 Iteration 3 Deck Reconstruction Analysis Stage 18.mcb




BEL 40 Iteration 3 Deck Reconstruction Analysis Stage 19.mcb




BEL 40 Iteration 3 Deck Reconstruction Analysis Stage 20.mcb




BEL 40 Iteration 3 Deck Reconstruction Analysis Stage 21.mcb




BEL 40 Iteration 3 Deck Reconstruction Analysis Stage 22.mcb




BEL 40 Iteration 3 Deck Reconstruction Analysis Stage 23.mcb




BEL 40 Iteration 3 Deck Reconstruction Analysis Stage 24.mcb




BEL 40 Iteration 3 Deck Reconstruction Analysis Stage 25.mcb




BEL 40 Iteration 3 Deck Reconstruction Analysis Stage 26.mcb




BEL 40 Iteration 3 Deck Reconstruction Analysis Stage 27.mcb




BEL 40 Iteration 3 Deck Reconstruction Analysis Stage 28.mcb




BEL 40 Iteration 3 Deck Reconstruction Analysis Stage 29.mcb




BEL 40 Iteration 3 Deck Reconstruction Analysis Stage 30.mcb




BEL 40 Iteration 3 Deck Reconstruction Analysis Stage 31.mcb



BEL 40 Iteration 3 Deck Reconstruction Analysis Stage 32.mcb



BEL 40 Iteration 3 Deck Reconstruction Analysis Stage 33.mcb



BEL 40 Iteration 3 Deck Reconstruction Analysis Stage 34.mcb

Works

- Analysis Control Data
- Moving Load Analysis Data [Method=Exact]
- Construction Stage Analysis [Stage=Last]

Structures

- Nodes : 6908
- Elements : 5940

Properties

- Material : 4
- Section : 367
- Section Stiffness Scale Factor
- Thickness : 1

Boundaries

- Supports : 32
- Elastic Link : 1536
- Plate End Release : 1701

Static Loads

- Static Load Case 1 [Self Weight ;]
- Static Load Case 2 [Deflector Type Parapet ; Deflector Type Parapet]
- Static Load Case 3 [Sidewalk Type Parapet ; Sidewalk Type Parapet]
- Static Load Case 4 [Sidewalk ; Sidewalk]
- Static Load Case 5 [Deck ; Deck]
- Static Load Case 6 [Overlay ; Overlay]
- Static Load Case 7 [Construction Dead Load ; Construction Dead Load]
- Static Load Case 8 [Construction Live Load ; Construction Live Load]
- Static Load Case 9 [Braking Force ; Braking Force]
- Static Load Case 10 [Crane Mats ; Crane Mats]

updated the load combinations to reflect the loads present on the bridge during these construction stages.

LIST OF LOAD COMBINATIONS					
NUM	NAME	ACTIVE	LOADCASE (FACTOR) +	TYPE	LOADCASE (FACTOR)
1	DC_C	Active	Self Weight(1.000) +	Add	Deck(1.000)
2	DW_C	Active	Construction Dead Lo(1.000) +	Add	Construction Live Lo(1.000) + Crane Mats(1.000)
3	FactoredDLDeflection	Active	Self Weight(1.250) +	Add	Deck(1.250) + Construction Dead Lo(1.500) + Construction Live Lo(1.500) + Crane Mats(1.500)

this load used to be the slab beam plus deck load. Now it is just the slab beam load (slab beams are 12" thick)

increased this load to account for weight of the HP sections

Moving Load Analysis

- Moving Load Code [AASHTO LRFD]
- Traffic Surface Lanes : 2
 - Traffic Surface Lane 1 [Const From Left]
 - Traffic Surface Lane 2 [Const From Right]

- Vehicles : 7
 - Vehicles 1 [Cat 336 ; User Defined]
 - Vehicles 2 [HL-93TDM ; Standard]
 - Vehicles 3 [HL-93TRK ; Standard]
 - Vehicles 4 [SU4 ; User Defined]
 - Vehicles 5 [SU5 ; User Defined]
 - Vehicles 6 [SU6 ; User Defined]
 - Vehicles 7 [SU7 ; User Defined]

Modified to include SU4 truck and slightly lighter excavator tread loads as defined earlier in this pdf.

- Vehicle Classes : 1
 - Vehicle Class 1 [HL-93 VC]

- Moving Load Cases : 2
 - Moving Load Case 1 [Arch A&B]
 - Moving Load Case 2 [Arch C&D]

Added these moving load cases for the construction equipment moving from the left and right and meeting at the middle of the bridge

MICROFILMED
JAN 22 1986

BEGIN WORK
Sta. 106+14
BRM-25 00 (1)

FHWA REGION	STATE	PROJECT	
5	OHIO		


BEL-40-2338

2
74


*Add a 6" x 8" wood or W6 x 15.5 steel post set in 4" min. concrete encasement 2'-3" from the end of the concrete parapet. Use a back-up plate and spacer block.

For details see Standard Construction Drawings GR-3B (Type J)* and GR-4A (Type T); 1 Tem 606 Type 5, 12'6" L.F.


For details see Standard Construction Drawings GR-3 and GR-4 (Type A); 1 Tem 606 Type 5, 12'6" L.F.



BLAINE HILL VIADUCT LOCATION
USGS Map: Ohio-Belmont Co.
Lansing 7.5 Quadrangle
Latitude N 40° 04' 01"
Longitude W 80° 49' 16"



TRAFFIC DATA (Highway)
Current ADT (1980) = 7,800
? = 12,480



NOTE:
Elevations shown opposite stationing are for \mathcal{E} Bridge.



STATE OF OHIO DEPARTMENT OF TRANSPORTATION BUREAU OF BRIDGES AND STRUCTURAL DESIGN					
GENERAL PLAN AND ELEVATION BRIDGE NO. BEL-40-2338 OVER THE B. & O. RAILROAD AND WHEELING CREEK					
DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE
AJM	AJM		R.L.D.	WJJ	12-1-80

Rev. 5-5-81

PROFILES MICROFILMED
 JAN 22 1986

FHWA REGION	STATE	PROJECT
5	OHIO	

15
74



PRECAST TRANSVERSE BEAM PLAN

LEGEND:

Existing Pier Columns not used for load carrying. Beams C and C₁ are used for architectural purposes.

Scupper location = ■

NOTES:

For beam details see sheet: 15/72 - Beam A
 16/72 - Beam B
 17/72 - Beams C and C₁

For Scupper details see sheets 48/72 and 49/72.

For Transverse Beam elevations see sheets 28/72 to 35/72 incl.

NOTES: (Con't)

All plan lengths shown are horizontal (typ., unless noted)


STATE OF OHIO
 DEPARTMENT OF TRANSPORTATION
 BUREAU OF BRIDGES AND STRUCTURAL DESIGN

14/72

TRANSVERSE BEAM LAYOUT

BRIDGE NO. BEL-40-2338
 OVER THE B. & O. RAILROAD
 AND WHEELING CREEK

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
J.A.M.	J.A.M.		R.L.D.	WJU	12-1-80	




MICROFILMED
JAN 22 1986

MICROFILMED
JAN 22 1986


FHWA REGION	STATE	PROJECT	
5	OHIO		

BEL-40-23.38

16
74




PLAN-BEAM A




SECTION C-C

SECTION B-B




SECTION A-A
(Along Beam C)



VIEW F-F

PARTIAL VIEW E-E
(Showing Existing Column)



SECTION D-D

NOTES(cont.)
SUPPORT locations during storage and transportation shall be under the lifting inserts. Ship, store upright

NOTES(cont.)
FOR beam layout plan see sheet 14/72
FOR scupper details see sheets 48/72 and 49/72
BEAMS shall be precast CONCRETE, Class S

NOTES
LIFTING inserts shall be of the contractor's design approved by the Director. Cut it off close to the beam after erection. Payment included in transverse beams.


STATE OF OHIO DEPARTMENT OF TRANSPORTATION BUREAU OF BRIDGES AND STRUCTURAL DESIGN						15/72
TRANSVERSE BEAM A DETAILS						
BRIDGE NO. BEL-40-2338 OVER THE B. & O. RAILROAD AND WHEELING CREEK						
DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISION
J.A.M.	J.A.M.		R.L.D.	W.J.J.	12-1-80	

MICROFILMED
JAN 22 1986


FHWA REGION	STATE	PROJECT	
5	OHIO		

17
74


BEL-40-2338




PLAN-BEAM B




SECTION C-C




SECTION B-B




SECTION A-A
(Along Beam CL)



VIEW F-F




PARTIAL VIEW E-E
(Showing Existing Column)




SECTION D-D

NOTES
BEAMS shall be precast
CONCRETE, Class S
FOR beam layout plan see sheet
14/72

STATE OF OHIO DEPARTMENT OF TRANSPORTATION BUREAU OF BRIDGES AND STRUCTURAL DESIGN					
TRANSVERSE BEAM B DETAILS					
BRIDGE NO. BEL-40-2338 OVER THE B. & O. RAILROAD AND WHEELING CREEK					
DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE
J.A.M.	J.A.M.		R.L.D.	W.J.J.	12-1-80




MICROFILMED
JAN 22 1986




Payment for concrete to fill voids shall be included in superstructure precast transverse beams.


PLAN-BEAM C
(BEAM C, -OPP. HAND)




SECTION A-A
(Along Beam C)




SECTION B-B



VIEW E-E



PARTIAL VIEW C-C
(Showing Exist. Column)



SECTION D-D



NOTES
FOR beam layout plan see sheet 14/72
BEAMS shall be precast CONCRETE, Class S

STATE OF OHIO DEPARTMENT OF TRANSPORTATION BUREAU OF BRIDGES AND STRUCTURAL DESIGN						17/72
TRANSVERSE BEAMS C&C, DETAILS BRIDGE NO. BEL-40-2338 OVER THE B. & O. RAILROAD AND WHEELING CREEK						
DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
J.A.M.	J.A.M.		R.L.D.	WJ	12-1-80	

FHWA REGION	STATE	PROJECT
5	OHIO	

MICROFILMED
JAN 22 1986

Sta 106 +85.00



NOTES:

For Box Beam details see sheet 21/72

For Superstructure details see sheets 22/72 thru 30/72 and 46/72 thru 50/72

For Transverse Beam plan see sheet 14/72

Match line B; see sheet 19/72

NOTES: (cont)

Box beams shall have the same identification marks on the shop drawings as on the project plans.

PRESTRESSED CONCRETE BEAM PLAN

STATE OF OHIO DEPARTMENT OF TRANSPORTATION BUREAU OF BRIDGES AND STRUCTURAL DESIGN						18/72
BOX BEAM LAYOUT						
BRIDGE NO. BEL-40-2338 OVER THE B. & O. RAILROAD AND WHEELING CREEK						
DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
J.A.M.	J.A.M.		R.L.D.	WJW	12-1-80	

MICROFILMED
JAN 22 1986

Match line
B; see sheet
18/72

Bridge
16'-16"

Match
line C

Bridge

ARCH SPAN "B" = 132'-6"



ARCH SPAN "C" = 118'-6"

ARCH SPAN "D" = 103'-6"

FHWA REGION	STATE	PROJECT
5	OHIO	

20
74

BEL-40-23.38



PRESTRESSED CONCRETE BEAM PLAN


FOR notes see sheet 18/72

STATE OF OHIO DEPARTMENT OF TRANSPORTATION BUREAU OF BRIDGES AND STRUCTURAL DESIGN						19/72
BOX BEAM LAYOUT						
BRIDGE NO. BEL-40-2338 OVER THE B. & O. RAILROAD AND WHEELER CREEK						
DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
J.A.M.	J.A.M.		R.L.D.	W.J.J.	12-1-80	

FHWA REGION	STATE	PROJECT
5	OHIO	

BEL-40-23.38

21



For notes see sheet 18/72


STATE OF OHIO
DEPARTMENT OF TRANSPORTATION
BUREAU OF BRIDGES AND STRUCTURAL DESIGN

20/72


BOX BEAM LAYOUT
BRIDGE NO. BEL-40-23.38
OVER THE B. & O. RAILROAD
AND WHEELING CREEK

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED
J.A.M.	J.A.M.		R.L.D.	W.J.J. 12-1


PRESTRESSED CONCRETE BEAM PLAN



CB 12-4B
(8 Strands)
All beams in Arch Spans A, B, C, D except B122 to B132 Incl.; B221 to B231 Incl.; B309 to B319 Incl.; and B17, B28, B39, B50, B61, B72, B83, B94, B105, B116, B138, B149, B160, B171, B182, B193, B204, B215, B227, B248, B259, B270, B281, B292, B303, B325, B336, B347, B358, B369, B380




CB 12-4B
(10 Strands)
Beams B122 to B126 Incl.; B128 to B132 Incl.; B221 to B225 Incl.; B227 to B231 Incl.; B309 to B313 Incl.; B315 to B319




B 12-36
(6 Strands)
Beams B17, B28, B39, B50, B61, B72, B83, B94, B105, B116, B138, B149, B160, B171, B182, B193, B204, B215, B237, B248, B259, B270, B281, B292, B303, B325, B336, B347, B358, B369, B380
(modified for composite construction)

Dimensions and reinforcing not shown is the same as for B12-36 (8 Strands, this sheet)




B 12-36
(8 Strands)
Beams B127, B226, B314
(modified for composite construction)


Debond 2 strands; Length=2'6"



CB 21-4B
(16 Strands)
Beams B1 to B5 Incl.; B7 to B11 Incl.; B419 to B423 Incl.; B425 to B429 Incl.; B430 to B434 Incl.; B436 to B440 Incl.




CB 21-4B
(10 Strands)
Beams B386 to B390 Incl.; B392 to B396 Incl.; B397 to B401 Incl.; B403 to B407 Incl.; B408 to B412 Incl.; B414 to B418 Incl.






B 21-36
(12 Strands)
(modified for composite construction)
Beams B6, B424, B435

Debond 2 strands; Length=1'6"



B 21-36
(8 Strands)
(modified for composite construction)
Beams B391, B402, B413

Dimensions and reinforcement not shown is the same as for B21-36 (12 Strands)



Bending Diagrams
(Bars X401, X402, W, Y shall be epoxy coated. Payment included in Item 515)

Additional Top Bars
Each End

Beam	Bar Size	No. Reqd	Length
CB 21-4B (16 Strands)	#4	7	9'-6"
CB 21-4B (10 Strands)	#4	3	6'-0"
B 21-36 (12 Strands)	#5	3	8'-6"
B 21-36 (8 Strands)	#5	1	6'-6"

NOTES

For beam notches and dowel hole locations see sheets 261/72, 491/72, 264/72

For additional beam details see Std. Drwg. PSBD-1-71, Sheets 1, 2, 3

Top surface finish for composite members as per Item 515.06.

Sloping sides of beams at θ of bridge is not required.

Box beams are composite members

STATE OF OHIO DEPARTMENT OF TRANSPORTATION BUREAU OF BRIDGES AND STRUCTURAL DESIGN		21/72
BOX BEAM DETAILS		
BRIDGE NO. BEL-40-2338 OVER THE B. & O. RAILROAD AND WHEELING CREEK		
DESIGNED J.A.M.	DRAWN J.A.M.	TRACED R.L.D.
CHECKED R.L.D.	REVIEWED W.J.J.	DATE 12-1-80