707.41 Non-Perforated ASTM D3034, SDR 35, 707.42 or 707.33

DRAINAGE														
					603		604	605					670	604
REF. NO.	STATION		SIDE		6" Conduit, Type F ##		Catch Basin, No. 4 with E-Grate, As Per Plan	6" Shallow Pipe U.D. w/Fabric Wrap (18" Deep)	6" Shallow Pipe U.D. (30" Deep)	6" Shallow Pipe U.D. w/Fabric Wrap (30" Deep)	6" Unclassified Underdrain w/Fabric Wrap	6" Unclassified Underdrain	Ditch Erosion Protection	Precast Reinforced Concrete Outlet
	FROM	TO			Lin.Ft.		Each	Lin.Ft.	Lin.Ft.	Lin.Ft.	Lin.Ft.	Lin.Ft.	Sq.Yd.	Each
U-1	473+00	485+00	Lt.						1200			36		
U-2	473+00	485+00	Lt.		45			1200						
U-3	473+00	485+00	Rt.		45			1200						
U-4	473+00	485+00	Rt.						1200			36		
D-1	473+50	475+00	℄				1						125	
D-2	478+50	480+00	℄				1						125	
D-3	483+50	485+00	℄				1						125	
	TOTALS				90		3	2400	2400			72	375	

PLAN & PROFILE QUANTITIES STA. 470+00 TO STA. 485+00

PLOTTED BY: fkonopka
PLOTTED: Rowers Beforsberg pid08459Bdgn 307qu01b.dgn 307QU01B.DGN
PLOT SUBMITTED:31-JUL-1998 07:55