



CALC. BY MSP  
DATE 2/93  
CHKD. BY JJB  
DATE 7/93

CUY-271-7.61

OHIO REGION 5  
231 568

SOUTHBOUND

NORTHBOUND

SEEDING  
END WIDTH SQ. YDS.  
36  
197  
35  
120  
38  
87  
38  
139  
12

470+00

469+50

469+20.50

469+00

MH, NO. 5  
STA. 469+75.8, 167' RT.  
RIM ELEV. 1181.80  
48" INV 1168.81

REMOVE MH  
STA 469+23, 151.0' RT.  
RIM ELEV. 1183.17  
15" INV 1174.60 \*  
48" INV N 1169.25 \*  
48" INV S 1169.22 \*

MH, NO. 3  
STA. 469+24, 167' RT.  
RIM ELEV. 1182.10  
15" INV 1174.20  
48" INV 1169.46  
6" INV 1175.5

EX. 15" RCP

REMOVE 4'-15" S

20'-15" CONDUIT,  
TYPE B, @ 2.5%

\* ESTIMATED ELEV.

MAINLINE WIDENING CROSS SECTIONS STA. 469+00 TO STA. 470+00

N:\PROJECTS\PR13810\CADD\XML3\_18.DWG 07-22-83