

OFFICE CALCS	SHEET NUMBER														ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	SP 1307-3(a)	SEE SHEET NO.
	11	82	83	84	85	86	87	88	89	91	105	157	255	259						DATE: JULY 2022	
	LS														201	11000	LS		CLEARING AND GRUBBING		
32738															202	23000	32738	SY	PAVEMENT REMOVED		
1503															202	23500	1503	SY	WEARING COURSE REMOVED		
															202	32000	1953	FT	CURB REMOVED		
															202	32001	927	FT	CURB REMOVED, AS PER PLAN	105	
															202	38000	12687.5	FT	GUARDRAIL REMOVED		
															202	38700	34	EACH	GUARDRAIL POST REMOVED		
					3										202	58500	3	EACH	CATCH BASIN ABANDONED		
	185	8423	20657	6224	169					188	479	153	331		203	10000	39679	CY	EXCAVATION		
		1067	2189	7148	1069					225	1144	50	62		203	20000	12954	CY	EMBANKMENT		
71464															204	10000	71464	SY	SUBGRADE COMPACTION		
															606	15050	11650	FT	GUARDRAIL, TYPE MGS		
															606	15150	175	FT	GUARDRAIL, TYPE MGS HALF POST SPACING		
															606	25550	12	EACH	ANCHOR ASSEMBLY, MGS TYPE A		
															606	26150	12	EACH	ANCHOR ASSEMBLY, MGS TYPE E (MASH 2016)		
															606	26550	23	EACH	ANCHOR ASSEMBLY, MGS TYPE T		
															606	35002	36	EACH	MGS BRIDGE TERMINAL ASSEMBLY, TYPE 1		
															606	35102	4	EACH	MGS BRIDGE TERMINAL ASSEMBLY, TYPE 2		
	10														623	38500	10	EACH	MONUMENT ASSEMBLY, TYPE C		

GENERAL SUMMARY

TRU-99-13.48

79
267