

SHEET NUMBER										PARTICIPATION		ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	SP 1307-3(d)		SEE SHEET NO.	CALCULATED	JKP CHECKED	FGW
10	18	25															DATE: JULY 2022					
<i>ADDITIVE ALTERNATE 1: SIDEWALK</i>																						
5985										5985	608	10000	5985	SF	4" CONCRETE WALK							
126										126	608	52000	126	SF	CURB RAMP							
	5									5	616	10000	5	MGAL	WATER							
	105									105	659	00300	105	CY	TOPSOIL							
	940									940	659	10000	940	SY	SEEDING AND MULCHING							
<i>ADDITIVE ALTERNATE 2: PEDESTRIAN CROSSWALK</i>																						
			52.0							52.0	630	02100	52.0	FT	GROUND MOUNTED SUPPORT, NO. 2 POST							
			1							1	630	08600	1	EACH	SIGN POST REFLECTOR							
			27.8							27.8	630	80100	27.8	SF	SIGN, FLAT SHEET							
			2							2	630	84900	2	EACH	REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL							
			2							2	630	86002	2	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL							
			2							2	631	92001	2	EACH	SIGN FLASHER ASSEMBLY, AS PER PLAN							5
			13							13	644	00500	13	FT	STOP LINE							
			200							200	644	00620	200	FT	CROSSWALK LINE, 12"							
<i>INCIDENTALS</i>																						
										LS	614	11000	LS		MAINTAINING TRAFFIC							
										6	619	16010	6	MNTH	FIELD OFFICE, TYPE B							
										LS	623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING							
										LS	624	10000	LS		MOBILIZATION							

GENERAL SUMMARY

LIC-C.R. 79-0.89