

SAMPLE PLAN SHEETS

PURPOSE AND APPLICATION

THE SAMPLE PLAN SHEETS ARE CONSIDERED TO BE AN INTEGRAL PART OF THE LOCATION AND DESIGN MANUAL'S VOLUME 3. IT IS FOR INFORMATIONAL PURPOSES ONLY AND IS INTENDED TO BE USED AS A STANDARDIZED GUIDELINE FOR THE PREPARATION OF HIGHWAY CONSTRUCTION PLANS IN THE STATE OF OHIO. EXAMPLES CONTAINED HEREIN ILLUSTRATE PREFERRED TECHNIQUES TO ENSURE THE UNIFORMITY, QUALITY, AND CONTINUITY OF THE PLANS, BUT DO NOT NECESSARILY REPRESENT A PREFERRED DESIGN. EXAMPLES HAVE BEEN PROVIDED BASED UPON THE MOST COMMONLY OCCURRING SITUATIONS. HOWEVER, IT IS RECOGNIZED THAT SOME PROJECTS MAY HAVE UNUSUAL CIRCUMSTANCES THAT MAY REQUIRE VARIATIONS FROM THE STANDARDS CONTAINED HEREIN. PLEASE CONTACT THE APPROPRIATE ODOT TECHNICAL OFFICE WITH QUESTIONS.

THIS SET OF SAMPLE PLAN SHEETS IS A COLLECTION OF INDIVIDUAL SHEET TYPES. IT SHOULD NOT BE CONSIDERED, OR USED, AS A SINGLE, COORDINATED PLAN. ACTUAL PLAN SHEETS HAVE BEEN USED TO DEVELOP THE SHEETS CONTAINED HEREIN. IT IS IMPORTANT TO NOTE THAT MODIFICATIONS HAVE BEEN MADE TO THESE SHEETS IN ORDER TO DEVELOP AN APPROPRIATE SAMPLE SHEET, THEREFORE, THEY ARE NO LONGER TO BE CONSIDERED AN OFFICIAL RECORD OF THE PLANS FROM WHICH THEY WERE TAKEN.

IN CASES WHERE THE INFORMATION SHOWN ON A SAMPLE PLAN SHEET IS IN CONFLICT WITH, OR CONTRADICTORY TO, THE DESIGN POLICIES OR PRACTICES CONTAINED IN THE CONSTRUCTION AND MATERIAL SPECIFICATIONS, DESIGN MANUALS, OR STANDARD CONSTRUCTION DRAWINGS, THE POLICIES OR PRACTICES WILL SUPERSEDE THE CONFLICTING SAMPLE PLAN SHEET INFORMATION.

STATE OF OHIO
DEPARTMENT OF TRANSPORTATION
JEF-FERNWOOD RD.
VILLAGE OF WINTERSVILLE
CROSS CREEK TOWNSHIP
JEFFERSON COUNTY

PROJECT DESCRIPTION


UPGRADING 0.44 MILE OF FERNWOOD ROAD BY WIDENING AND RESURFACING, INCLUDING NEW STORM SEWER SYSTEM, CURB AND GUTTER, SIDEWALK. TRAFFIC CONTROL SIGNS AND PAVEMENT MARKINGS.

EARTH DISTURBED AREAS

PROJECT EARTH DISTURBED AREA: 3.1 ACRES
ESTIMATED CONTRACTOR EARTH DISTURBED AREA: 0.5 ACRES
NOTICE OF INTENT EARTH DISTURBED AREA: 4.9 ACRES


2013 SPECIFICATIONS

THE STANDARD SPECIFICATIONS OF THE STATE OF OHIO, DEPARTMENT OF TRANSPORTATION, INCLUDING SUPPLEMENTAL SPECIFICATIONS LISTED IN THE PLANS AND CHANGES LISTED IN THE PROPOSAL SHALL GOVERN THIS IMPROVEMENT.



LOCATION MAP

LATITUDE: 40°22'20" LONGITUDE: 80°42'05"



PORTION TO BE IMPROVED

| | |
|----------------------------------|-----|
| INTERSTATE & DIVIDED HIGHWAY | --- |
| UNDIVIDED STATE & FEDERAL ROUTES | --- |
| OTHER ROADS | --- |

DESIGN DESIGNATION

| | |
|-----------------------------------|------------|
| CURRENT ADT (2013) | 2940 |
| DESIGN YEAR ADT (2025) | 4494 |
| DESIGN HOURLY VOLUME (2025) | 449 |
| DIRECTIONAL DISTRIBUTION | 50% |
| TRUCKS (24 HOUR B&C) | 3% |
| DESIGN SPEED | 3R PROJECT |
| LEGAL SPEED | 35 MPH |
| DESIGN FUNCTIONAL CLASSIFICATION: | |
| 06 MINOR COLLECTOR (URBAN) | |
| NHS PROJECT | NO |

DESIGN EXCEPTIONS

| DESIGN FEATURE | APPROVAL DATES | SHEET NUMBER |
|-------------------------|----------------|--------------|
| HORIZONTAL ALIGNMENT: | | |
| SUPERELEVATION | 6-27-14 | 2 |
| VERTICAL ALIGNMENT: | | |
| STOPPING SIGHT DISTANCE | 6-27-14 | 10, 12 |

INDEX OF SHEETS:

| | |
|------------------------|-------|
| TITLE SHEET | 1 |
| SCHEMATIC PLAN | 2 |
| TYPICAL SECTIONS | 3-4 |
| GENERAL NOTES | 5 |
| MAINTENANCE OF TRAFFIC | 6-7 |
| GENERAL SUMMARY | 8 |
| PROJECT SITE PLAN | 9 |
| PLAN AND PROFILE | 10 |
| CROSS SECTIONS | 11-17 |
| SIDE APPROACHES | 18-25 |
| SUPERELEVATION TABLE | 26-30 |
| DRIVE DETAILS | 31 |
| DRAINAGE DETAILS | 32-37 |
| TRAFFIC CONTROL | 38-39 |
| RIGHT OF WAY | 40-50 |
| SOIL PROFILES | |

UNDERGROUND UTILITIES

CONTACT BOTH SERVICES TWO WORKING DAYS BEFORE YOU DIG.

PLAN PREPARED BY:
JOHN J. DOE & ASSOC., INC.
CONSULTING ENGINEERS
9999 ENGLISH DRIVE
COMPUTERLAND, OHIO 00000

ENGINEERS SEAL:

SIGNED: *John J. Doe*
DATE: 11/11/14

| STANDARD CONSTRUCTION DRAWINGS | | | | | | SUPPLEMENTAL SPECIFICATIONS | |
|--------------------------------|---------|---------|----------|-----------|----------|-----------------------------|---------|
| BP-1.1 | 7/28/00 | MGS-1.1 | 7/19/13 | MT-105.10 | 7/19/13 | 800-2013 | 1/21/15 |
| BP-2.1 | 7/19/13 | MGS-2.1 | 7/19/13 | | | 832 | 1/17/14 |
| BP-2.2 | 7/18/08 | MGS-4.2 | 7/19/13 | TC-41.20 | 10/18/13 | | |
| BP-3.1 | 7/18/14 | MGS-5.3 | 7/19/13 | TC-41.40 | 10/18/13 | | |
| BP-4.1 | 7/19/13 | | | TC-42.20 | 10/18/13 | | |
| BP-5.1 | 7/19/13 | HW-2.1 | 1/18/13 | TC-52.10 | 10/18/13 | | |
| BP-7.1 | 7/18/14 | HW-2.2 | 1/18/13 | TC-52.20 | 7/18/14 | | |
| | | | | TC-71.10 | 1/17/14 | | |
| CB-2.1 | 1/18/13 | LA-1.1 | 10/15/10 | | | | |
| CB-2.2 | 1/17/14 | LA-1.2 | 10/15/10 | | | | |
| CB-2.3 | 1/18/13 | | | | | | |
| | | MH-1.1 | 1/18/13 | | | | |
| DM-1.1 | 1/18/13 | MH-1.2 | 1/18/13 | | | REINFORCED EARTH | 5/27/14 |
| DM-4.4 | 7/20/12 | MH-1.3 | 1/18/13 | | | WATERWAY PERMIT | 1/23/15 |

I HEREBY APPROVE THESE PLANS AND DECLARE THAT THE MAKING OF THIS IMPROVEMENT WILL NOT REQUIRE THE CLOSING TO TRAFFIC OF THE HIGHWAY AND THAT PROVISIONS FOR THE MAINTENANCE AND SAFETY OF TRAFFIC WILL BE AS SET FORTH ON THE PLANS AND ESTIMATES.

APPROVED _____
DATE _____ MAYOR, VILLAGE OF WINTERSVILLE

APPROVED _____
DATE _____ DISTRICT DEPUTY DIRECTOR

APPROVED _____
DATE _____ DIRECTOR, DEPARTMENT OF TRANSPORTATION

FEDERAL PROJECT NO. **E025 (762)**
CONSTRUCTION PROJECT NO. **15549**
RAILROAD INVOLVEMENT **NONE**
JEF-FERNWOOD RD.
1/50

PROJECT DESCRIPTION

REHABILITATION OF THE EXISTING STRUCTURE OVER THE OHIO CENTRAL RAILROAD BY REPLACEMENT OF THE BRIDGE DECK AND APPROACH SLABS.

EARTH DISTURBED AREAS

PROJECT EARTH DISTURBED AREA: 1.5 ACRES
 ESTIMATED CONTRACTOR EARTH DISTURBED AREA: 0.7 ACRES
 NOTICE OF INTENT EARTH DISTURBED AREA: 4.9 ACRES

2013 SPECIFICATIONS

THE STANDARD SPECIFICATIONS OF THE STATE OF OHIO, DEPARTMENT OF TRANSPORTATION, INCLUDING SUPPLEMENTAL SPECIFICATIONS LISTED IN THE PLANS AND CHANGES LISTED IN THE PROPOSAL SHALL GOVERN THIS IMPROVEMENT.


FEDERAL PROJECT NO. E073 (345)
 PID NO. 22512
 CONSTRUCTION PROJECT NO.
 RAILROAD INVOLVEMENT OHIO CENTRAL R.R.
 TUS-93-8.02
 1/28

STATE OF OHIO
 DEPARTMENT OF TRANSPORTATION

TUS-93-8.02

RECONSTRUCTION OF EXISTING SEPARATED CROSSING WITH THE OHIO CENTRAL RAILROAD


**WAYNE TOWNSHIP
 TUSCARAWAS COUNTY**



LOCATION MAP

LATITUDE: 40°34'20" LONGITUDE: 81°37'00"

SCALE IN MILES



| | | |
|----------------------------------|-------|-------|
| PORTION TO BE IMPROVED | ----- | ===== |
| INTERSTATE & DIVIDED HIGHWAY | ----- | ===== |
| UNDIVIDED STATE & FEDERAL ROUTES | ----- | ===== |
| OTHER ROADS | ----- | ===== |

DESIGN DESIGNATION

| | | |
|-----------------------------------|-------|----------------------------|
| CURRENT ADT (2013) | ----- | 1270 |
| DESIGN YEAR ADT (2033) | ----- | 2240 |
| DESIGN HOURLY VOLUME (2033) | ----- | 224 |
| DIRECTIONAL DISTRIBUTION | ----- | 60% |
| TRUCKS (24 HOUR B&C) | ----- | 5% |
| DESIGN SPEED | ----- | 55 MPH |
| LEGAL SPEED | ----- | 55 MPH |
| DESIGN FUNCTIONAL CLASSIFICATION: | ----- | 06 MINOR COLLECTOR (RURAL) |
| NHS PROJECT | ----- | NO |

DESIGN EXCEPTIONS


NONE REQUIRED

INDEX OF SHEETS:

| | |
|------------------------------|-------|
| TITLE SHEET | 1 |
| SCHEMATIC PLAN | 2 |
| TYPICAL SECTIONS | 3 |
| GENERAL NOTES | 4 |
| MAINTENANCE OF TRAFFIC | 5-7 |
| GENERAL SUMMARY | 8 |
| PROJECT SITE PLAN | 9 |
| PLAN AND PROFILE | 10-11 |
| CROSS SECTIONS | 12-13 |
| TRAFFIC CONTROL | 14 |
| STRUCTURES OVER 20 FOOT SPAN | 15-21 |
| RIGHT OF WAY | 22-28 |
| SOIL PROFILES | |

ENGINEERS SEAL


FOR STRUCTURES OVER 20 FOOT SPAN



SIGNED: *John J. Doe*
 DATE: 11/11/14

ENGINEERS SEAL

FOR ENTIRE PLAN EXCEPT STRUCTURES OVER 20 FOOT SPAN



SIGNED: *Jane C. Smith*
 DATE: 11/11/14

STANDARD CONSTRUCTION DRAWINGS

| STANDARD CONSTRUCTION DRAWINGS | | | | SUPPLEMENTAL SPECIFICATIONS | |
|--------------------------------|---------|----------|---------|-----------------------------|---------|
| BP-3.1 | 7/18/14 | AS-1-81 | 1/18/13 | 800-2013 | 1/21/15 |
| BP-4.1 | 7/19/13 | CPA-1-08 | 7/18/08 | 832 | 1/17/14 |
| BP-5.1 | 7/19/13 | CS-1-08 | 7/18/08 | | |
| | | SBR-1-99 | 7/19/02 | | |
| DM-1.1 | 1/18/13 | | | | |
| DM-1.4 | 1/18/13 | MT-96.11 | 7/18/14 | | |
| DM-4.4 | 7/20/12 | MT-96.20 | 7/19/13 | | |
| | | MT-96.26 | 7/19/13 | | |
| MGS-1.1 | 1/20/12 | | | | |
| MGS-2.1 | 7/19/13 | | | | |
| MGS-3.1 | 7/18/14 | | | | |
| MGS-4.2 | 7/19/13 | | | | |
| MGS-5.3 | 7/19/13 | | | | |
| RM-4.2 | 7/19/13 | | | | |

SPECIAL PROVISIONS

WATERWAY PERMIT
 1/23/15

I HEREBY APPROVE THESE PLANS AND DECLARE THAT THE MAKING OF THIS IMPROVEMENT WILL NOT REQUIRE THE CLOSING TO TRAFFIC OF THE HIGHWAY AND THAT PROVISIONS FOR THE MAINTENANCE AND SAFETY OF TRAFFIC WILL BE AS SET FORTH ON THE PLANS AND ESTIMATES.

APPROVED _____
 DATE _____ DISTRICT DEPUTY DIRECTOR

APPROVED _____
 DATE _____ DIRECTOR, DEPARTMENT OF TRANSPORTATION

UNDERGROUND UTILITIES
 CONTACT BOTH SERVICES TWO WORKING DAYS BEFORE YOU DIG.

Call Before You Dig
1-800-362-2764

(Non-members must be called directly)
 OIL & GAS PRODUCERS UNDERGROUND PROTECTION SERVICE
1-800-925-0988

PLAN PREPARED BY:
 JOHN J. DOE & ASSOC., INC.
 CONSULTING ENGINEERS
 9999 ENGLISH DRIVE
 COMPUTERLAND, OHIO 00000

STATE OF OHIO
DEPARTMENT OF TRANSPORTATION

WYA-30-9.11
SALEM TOWNSHIP
WYANDOT COUNTY

PROJECT DESCRIPTION

CONSTRUCTION OF A 2.24 MILE CONNECTION FROM U.S. 30 TO U.S. 23, WITH A CONNECTING ROAD AT U.S. 30 AND A LIGHTED INTERCHANGE AT U.S. 23. INCLUDING CONSTRUCTION OF STRUCTURES U.S. 30 UNDER T.R. 49, U.S. 30 WB OVER U.S.23 SB, RAMP B, AND U.S. 23 UNDER C.R. 47; REPLACEMENT OF STRUCTURES U.S. 23 NB AND SB OVER LITTLE TYMOCHTEE CREEK; RECONSTRUCTION OF VARIOUS LOCAL ROADS; AND INSTALLATION OF NECESSARY TRAFFIC CONTROL DEVICES.

EARTH DISTURBED AREAS

PROJECT EARTH DISTURBED AREA: 20.6 ACRES
ESTIMATED CONTRACTOR EARTH DISTURBED AREA: 5.4 ACRES
NOTICE OF INTENT EARTH DISTURBED AREA: 26.0 ACRES

LIMITED ACCESS

THIS IMPROVEMENT IS ESPECIALLY DESIGNED FOR THROUGH TRAFFIC AND HAS BEEN DECLARED A LIMITED ACCESS HIGHWAY OR FREEWAY BY ACTION OF THE DIRECTOR IN ACCORDANCE WITH THE PROVISIONS OF SECTION 5511.02 OF THE OHIO REVISED CODE.


2013 SPECIFICATIONS

THE STANDARD SPECIFICATIONS OF THE STATE OF OHIO, DEPARTMENT OF TRANSPORTATION, INCLUDING SUPPLEMENTAL SPECIFICATIONS LISTED IN THE PLANS AND CHANGES LISTED IN THE PROPOSAL SHALL GOVERN THIS IMPROVEMENT.

I HEREBY APPROVE THESE PLANS AND DECLARE THAT THE MAKING OF THIS IMPROVEMENT WILL NOT REQUIRE THE CLOSING TO TRAFFIC OF THE HIGHWAY EXCEPT AS NOTED ON SHEET 25, AND THAT PROVISIONS FOR THE MAINTENANCE AND SAFETY OF TRAFFIC WILL BE AS SET FORTH ON THE PLANS AND ESTIMATES.

APPROVED _____
DATE _____ DISTRICT DEPUTY DIRECTOR

APPROVED _____
DATE _____ DIRECTOR, DEPARTMENT OF TRANSPORTATION



LOCATION MAP

LATITUDE: 40°50'50" LONGITUDE: 83°19'35"



PORTION TO BE IMPROVED

INTERSTATE & DIVIDED HIGHWAY

UNDIVIDED STATE & FEDERAL ROUTES

OTHER ROADS

DESIGN DESIGNATION

| | |
|-----------------------------------|--------------------|
| CURRENT ADT (2013) | 3510 |
| DESIGN YEAR ADT (2033) | 4880 |
| DESIGN HOURLY VOLUME (2033) | 488 |
| DIRECTIONAL DISTRIBUTION | 55% |
| TRUCKS (24 HOUR B&C) | 20% |
| DESIGN SPEED | 70 MPH |
| T _d | 20% |
| LEGAL SPEED | 55 MPH |
| DESIGN FUNCTIONAL CLASSIFICATION: | 06 FREEWAY (RURAL) |
| NHS PROJECT | NO |

DESIGN EXCEPTIONS

NONE REQUIRED

UNDERGROUND UTILITIES
CONTACT BOTH SERVICES TWO WORKING DAYS BEFORE YOU DIG.

Call Before You Dig
1-800-362-2764

(Non-members must be called directly)

OIL & GAS PRODUCERS
UNDERGROUND PROTECTION SERVICE
1-800-925-0988


PLAN PREPARED BY:
JOHN J. DOE & ASSOC., INC.
CONSULTING ENGINEERS
9999 ENGLISH DRIVE
COMPUTERLAND, OHIO 00000

| | |
|--|---|
| ENGINEERS SEAL FOR STRUCTURES OVER 20 FOOT | ENGINEERS SEAL FOR ENTIRE PLAN EXCEPT STRUCTURES OVER 20 FOOT |
| | |
| SIGNED: <i>John J. Doe</i> DATE: 11/11/14 | SIGNED: <i>Jane C. Smith</i> DATE: 11/11/14 |

| | | | |
|--------------------------------------|---------------|-------------------------------------|----------|
| TITLE SHEET | 1 | SUPERELEVATION TABLES | 270-273 |
| SCHEMATIC PLAN | 2-3 | INTERSECTION DETAILS | 274-276 |
| TYPICAL SECTIONS | 4-20 | GRADING DETAILS | 277-278 |
| GENERAL NOTES | 21-23,23A | CHANNEL CROSS SECTIONS | 279-280 |
| MAINTENANCE OF TRAFFIC | 24-29 | TERMINAL DETAILS | 281-283 |
| GENERAL SUMMARY | 50-52 | IMPACT ATTENUATOR DETAILS | 284-285 |
| MISCELLANEOUS CALCULATIONS | 72,72A-C | SETTLEMENT PLATFORM DETAILS & NOTES | 286 |
| PROJECT SITE PLAN | 73 | UNDERDRAIN DETAILS | 287-288 |
| PLAN AND PROFILE - U.S.R. 30 | 74-83 | PREFABRICATED STRUCTURES | 289-322 |
| PLAN AND PROFILE - INTERCHANGE RAMP | 84-112 | TRAFFIC CONTROL | 323-393 |
| PLAN AND PROFILE - MAINTENANCE DRIVE | 113-115 | LIGHTING | 394-409 |
| PLAN AND PROFILE - SERVICE ROAD | 116-117 | STRUCTURES OVER 20' SPAN: | |
| PLAN AND PROFILE - CONNECTOR ROAD | 118-119 | WYA-30-1051 | 410-422 |
| PLAN AND PROFILE - C.R.108 | 120-130 | WYA-30-1129 WB | 423-446 |
| PLAN AND PROFILE - T.R.49 | 131-134 | WYA-30-1129 RAMP B | 447-467 |
| PLAN AND PROFILE - T.R.47 | 135-138 | WYA-23-2589 L | 468-480 |
| CROSS SECTIONS - U.S.R. 30 | 139-161 | WYA-23-1589 R | 481-492 |
| CROSS SECTIONS - INTERCHANGE RAMP | 162-208 | WYA-30-1603 | 493-507 |
| CROSS SECTIONS - MAINTENANCE DRIVE | 209-210 | RIGHT OF WAY | 508-521 |
| CROSS SECTIONS - SERVICE ROAD | 211-215 | SOIL PROFILE | |
| CROSS SECTIONS - CONNECTOR ROAD | 216-218 | SHEETS NOT USED | 248, 279 |
| CROSS SECTIONS - C.R.108 | 219-238, 222A | | |
| CROSS SECTIONS - T.R.49 | 239-253 | | |
| CROSS SECTIONS - T.R.47 | 254-269 | | |

| STANDARD CONSTRUCTION DRAWINGS | | | | | | | | SUPPLEMENTAL SPECIFICATIONS | | | |
|--------------------------------|---------|---------|----------|-----------|---------|----------|---------|-----------------------------|----------|----------|---------|
| BP-1.1 | 7/28/00 | MGS-1.1 | 7/19/13 | MH-1.1 | 1/18/13 | HL-10.31 | 1/16/15 | TC-07.65 | 10/18/13 | 800-2013 | 1/21/15 |
| | | MGS-2.1 | 7/19/13 | MH-1.2 | 1/18/13 | HL-20.11 | 1/16/15 | TC-12.30 | 10/18/13 | 832 | 1/17/14 |
| CB-2.2 | 1/17/14 | MGS-3.1 | 7/18/14 | MH-3.1 | 1/18/13 | HL-20.14 | 1/16/15 | TC-21.10 | 10/18/13 | | |
| CB-3.1 | 1/18/13 | MGS-4.2 | 7/19/13 | | | HL-20.21 | 1/17/14 | TC-21.20 | 1/16/15 | | |
| CB-3.2 | 1/18/13 | MGS-5.3 | 7/19/13 | RM-1.1 | 7/18/14 | HL-30.11 | 1/16/15 | TC-22.20 | 1/17/14 | | |
| CB-3.4 | 1/18/13 | MGS-6.1 | 7/19/13 | RM-4.2 | 6/4/14 | HL-30.21 | 1/17/14 | TC-41.10 | 7/19/13 | | |
| | | | | RM-4.3 | 7/18/14 | HL-30.22 | 1/17/14 | TC-41.20 | 10/18/13 | | |
| DM-1.1 | 1/18/13 | HW-1.1 | 1/18/13 | | | HL-30.31 | 1/17/14 | TC-41.40 | 10/18/13 | | |
| DM-4.4 | 7/20/12 | HW-2.1 | 1/18/13 | MT-95.30 | 7/18/14 | HL-40.10 | 1/17/14 | TC-41.50 | 10/18/13 | | |
| | | HW-2.2 | 1/18/13 | MT-102.10 | 7/18/14 | HL-50.11 | 1/16/15 | TC-42.10 | 10/18/13 | | |
| F-2.1 | 7/19/13 | | | | | HL-60.21 | 1/16/15 | TC-42.20 | 10/18/13 | | |
| F-3.1 | 7/19/13 | LA-1.1 | 10/15/10 | AS-1-81 | 1/18/13 | HL-60.31 | 1/16/15 | TC-51.11 | 1/17/14 | | |
| F-3.3 | 7/19/13 | LA-1.2 | 10/15/10 | ICD-1-82 | 7/19/02 | | | TC-52.10 | 10/18/13 | | |
| F-3.4 | 7/19/13 | | | | | | | TC-52.20 | 7/18/14 | | |
| | | WO-1.1 | 1/18/13 | | | | | | | | |
| | | WO-1.2 | 1/18/13 | | | | | | | | |

| |
|--------------------------------|
| SPECIAL PROVISIONS |
| WATERWAY PERMIT 1/23/15 |
| GEOTECHNICAL REPORT 6/02/14 |



LOCATION MAP

LATITUDE: 41°24'10" LONGITUDE: 82°18'40"



PORTION TO BE IMPROVED - - - - -
 INTERSTATE & DIVIDED HIGHWAY - - - - -
 UNDIVIDED STATE & FEDERAL ROUTES - - - - -
 OTHER ROADS - - - - -

**FOR DESIGN DESIGNATION AND DESIGN
 EXCEPTIONS SEE SHEETS 2 AND 3**

STATE OF OHIO
 DEPARTMENT OF TRANSPORTATION

ERI-2-30.51 AND VARIOUS LOR-2-0.00 AND VARIOUS

**CITY OF VERMILION
 BROWNHELM TOWNSHIP
 VERMILION TOWNSHIP
 ERIE AND LORAIN COUNTIES**

PROJECT DESCRIPTION

REHABILITATION OF 1.72 MILES OF EXISTING PAVEMENT AND SHOULDERS FOR ONGOING RESEARCH PROJECTS INCLUDING THE INSTALLATION OF WEIGH-IN-MOTION INSTRUMENTATION AND THE REHABILITATION OF BRIDGES UNDER WEST REIVER ROAD, VERMILION ROAD, VERMILION INTERCHANGE ROAD, SUNNYSIDE ROAD AND CLAUD ROAD AND OVER THE VERMILION RIVER AND BAUMHART ROAD.

EARTH DISTURBED AREAS

PROJECT EARTH DISTURBED AREA: 9.5 ACRES
 ESTIMATED CONTRACTOR EARTH DISTURBED AREA: 2.6 ACRES
 NOTICE OF INTENT EARTH DISTURBED AREA: 12.1 ACRES

LIMITED ACCESS

THIS IMPROVEMENT IS ESPECIALLY DESIGNED FOR THROUGH TRAFFIC AND HAS BEEN DECLARED A LIMITED ACCESS HIGHWAY OR FREEWAY BY ACTION OF THE DIRECTOR IN ACCORDANCE WITH THE PROVISIONS OF SECTION 5511.02 OF THE OHIO REVISED CODE.

2013 SPECIFICATIONS

THE STANDARD SPECIFICATIONS OF THE STATE OF OHIO, DEPARTMENT OF TRANSPORTATION, INCLUDING SUPPLEMENTAL SPECIFICATIONS LISTED IN THE PLANS AND CHANGES LISTED IN THE PROPOSAL SHALL GOVERN THIS IMPROVEMENT.

I HEREBY APPROVE THESE PLANS AND DECLARE THAT THE MAKING OF THIS IMPROVEMENT WILL NOT REQUIRE THE CLOSING TO TRAFFIC OF THE HIGHWAY EXCEPT FOR THE RAMPS AND SIDE ROADS AS DESCRIBED ON SHEETS 16 & 17 AND AS SHOWN ON SHEETS 19-22, AND THAT PROVISIONS FOR THE MAINTENANCE AND SAFETY OF TRAFFIC WILL BE AS SET FORTH ON THE PLANS AND ESTIMATES.

APPROVED _____
 DATE _____ DISTRICT DEPUTY DIRECTOR

APPROVED _____
 DATE _____ DIRECTOR, DEPARTMENT OF TRANSPORTATION

INDEX OF SHEETS:

| | | | |
|-------------------------------|------------|-------------------------------------|---------------|
| TITLE SHEET | 1 | VERMILION INTERCHANGE ROAD | 139 |
| SCHEMATIC PLAN | 2-3 | SUNNYSIDE ROAD | 140-141 |
| TYPICAL SECTIONS | 4-9 | CLAUD ROAD | 142-143 |
| GENERAL NOTES | 10-15 | DETAILS: | |
| MAINTENANCE OF TRAFFIC | 16-59, 59A | PAVEMENT JOINT REPAIR | 144-146 |
| GENERAL SUMMARY | 60-62 | SHRP PAVEMENT REPAIR | 147-154, 154A |
| SUBSUMMARIES: | | PIER PROTECTION | 155-156 |
| GUARDRAIL | 63 | APPROACH SLABS | 157-158 |
| SEEDING | 64 | CURB REMOVAL & SHOULDER REPLACEMENT | 159-166 |
| DRAINAGE | 65-66 | CONCRETE SHOULDER | 167 |
| CALCULATIONS: | | MEDIAN CROSSOVER | 168 |
| JOINT REPAIR | 74-80 | DRAINAGE | 169, 169A |
| PAVEMENT GRINDING | 81 | SUPERELEVATION TABLES | 170-171 |
| JOINT SEALING | 82-83 | PREFABRICATED STRUCTURES | 172-179 |
| SEEDING | 84-85 | WEIGH-IN-MOTION DETAILS | 180-185 |
| PROJECT SITE PLAN | 89-90 | TRAFFIC CONTROL | 186-205 |
| PLAN AND PROFILE - S.R.2 | 91-108 | STRUCTURES OVER 20 FOOT SPAN | |
| CROSS SECTIONS - S.R.2 | 109-122 | LOR-2-3001 | 206-214 |
| SIDE APPROACHES: | | LOR-2-9806 | 215-223 |
| RAMPS - REST AREA | 123-128 | LOR-2-1070 | 224-233 |
| RAMPS - VERMILION INTERCHANGE | 129-132 | LOR-2-1511 | 234-242 |
| RAMPS - BAUMHART INTERCHANGE | 133-134 | LOR-2-2231 | 243-251 |
| WEST RIVER ROAD | 135-136 | LOR-2-2621 | 252-261 |
| VERMILION ROAD | 137-138 | LOR-2-3331 | 262-267 |
| | | SOIL PROFILES | |
| | | TRAFFIC CONTROL | 186-205 |
| | | SHEETS NOT USED | 67-73, 86-88 |

UNDERGROUND UTILITIES


CONTACT BOTH SERVICES TWO WORKING DAYS BEFORE YOU DIG.

Call Before You Dig
1-800-362-2764

(Non-members must be called directly)
 OIL & GAS PRODUCERS
 UNDERGROUND PROTECTION SERVICE
1-800-925-0988


PLAN PREPARED BY:
 JOHN J. DOE & ASSOC., INC.
 CONSULTING ENGINEERS
 9999 ENGLISH DRIVE
 COMPUTERLAND, OHIO 00000

ENGINEERS SEAL
 FOR STRUCTURES
 20' & UNDER



SIGNED: *John J. Doe*
 DATE: 11-11-14

ENGINEERS SEAL
 FOR ENTIRE PLAN
 EXCEPT STRUCTURES
 OVER 20'



SIGNED: *Jane C. Smith*
 DATE: 11-11-14

| STANDARD CONSTRUCTION DRAWINGS | | | | | | | | SUPPLEMENTAL SPECIFICATIONS | |
|--------------------------------|---------|----------|---------|----------|---------|----------|----------|-----------------------------|---------|
| BP-1.1 | 7/28/00 | MGS-1.1 | 7/19/13 | HL-10.13 | 1/16/15 | TC-18.24 | 1/17/14 | 800-2013 | 1/21/15 |
| BP-2.1 | 7/19/13 | MGS-2.1 | 7/19/13 | HL-20.14 | 1/16/15 | TC-22.20 | 1/17/14 | 832 | 1/17/14 |
| BP-2.2 | 7/18/08 | MGS-3.1 | 7/18/14 | HL-30.11 | 1/16/15 | TC-41.10 | 7/19/13 | | |
| BP-2.3 | 7/18/14 | MGS-3.2 | 1/18/13 | HL-30.21 | 1/17/14 | TC-41.20 | 10/18/13 | | |
| BP-2.5 | 7/19/13 | MGS-4.2 | 7/19/13 | HL-30.31 | 1/17/14 | TC-41.40 | 10/18/13 | | |
| BP-3.1 | 7/18/14 | MGS-5.3 | 7/19/13 | HL-30.32 | 1/17/14 | TC-41.50 | 10/18/13 | | |
| BP-6.1 | 7/19/13 | MGS-6.1 | 7/19/13 | HL-40.10 | 1/17/14 | TC-42.10 | 10/18/13 | | |
| CB-1.1 | 1/18/13 | RM-4.2 | 6/4/14 | MT-95.30 | 7/18/14 | TC-51.11 | 1/17/14 | | |
| CB-2.2 | 1/17/14 | RM-4.3 | 7/18/14 | MT-95.31 | 7/18/14 | TC-52.10 | 10/18/13 | | |
| CB-3.1 | 1/18/13 | RM-4.4 | 7/18/14 | MT-96.11 | 7/18/14 | TC-52.20 | 7/18/14 | | |
| CB-3.2 | 1/18/13 | | | MT-96.20 | 7/19/13 | TC-65.10 | 1/17/14 | | |
| DM-1.1 | 1/18/13 | AS-1-81 | 1/18/13 | MT-96.26 | 7/19/13 | TC-65.11 | 7/18/14 | | |
| DM-4.4 | 7/20/12 | EXJ-4-87 | 7/19/02 | MT-99.20 | 7/19/13 | TC-72.20 | 7/18/14 | | |
| | | RB-1-55 | 7/19/13 | | | TC-82.10 | 10/18/13 | | |

SPECIAL PROVISIONS

WATERWAY PERMIT
 1/23/14

FEDERAL PROJECT NO. E115 (218)
 CONSTRUCTION PROJECT NO. 20283
 RAILROAD INVOLVEMENT NONE
 ERI-2-30.51 AND VARIOUS LOR-2-0.00 AND VARIOUS
 1/267

STATE OF OHIO
DEPARTMENT OF TRANSPORTATION

CRA - C.R. 6 - 1.61
(BOUNDARY RD.) PART 1
CRANBERRY TOWNSHIP
CRAWFORD COUNTY
FOR PART 2, SEE CAR-C.R. 31 (SCOTT RD.)

PROJECT DESCRIPTION

IMPROVEMENT OF 0.04 MILE OF C.R. 6 (BOUNDARY ROAD) BY REPLACEMENT OF AN EXISTING STEEL TRUSS STRUCTURE OVER BROKEN KNIFE CREEK WITH A PRECAST PRESTRESSED BOX BEAM TYPE STRUCTURE INCLUDING APPROACH RECONSTRUCTION.

EARTH DISTURBED AREAS

PROJECT EARTH DISTURBED AREA: 1.7 ACRES
ESTIMATED CONTRACTOR EARTH DISTURBED AREA: 0.6 ACRES
NOTICE OF INTENT EARTH DISTURBED AREA: 4.9 ACRES

2013 SPECIFICATIONS

THE STANDARD SPECIFICATIONS OF THE STATE OF OHIO, DEPARTMENT OF TRANSPORTATION, INCLUDING SUPPLEMENTAL SPECIFICATIONS LISTED IN THE PLANS AND CHANGES LISTED IN THE PROPOSAL SHALL GOVERN THIS IMPROVEMENT.

I HEREBY APPROVE THESE PLANS AND DECLARE THAT THE MAKING OF THIS IMPROVEMENT WILL REQUIRE THE CLOSING TO TRAFFIC OF THE HIGHWAY AND THAT DETOURS WILL BE PROVIDED AS INDICATED ON SHEET 7.

APPROVED _____
DATE _____ CRAWFORD COUNTY COMMISSIONER


APPROVED _____
DATE _____ CRAWFORD COUNTY COMMISSIONER

APPROVED _____
DATE _____ CRAWFORD COUNTY COMMISSIONER

APPROVED _____
DATE _____ ENGINEER, CRAWFORD COUNTY

APPROVED _____
DATE _____ DISTRICT DEPUTY DIRECTOR

APPROVED _____
DATE _____ DIRECTOR, DEPARTMENT OF TRANSPORTATION



LOCATION MAP

LATITUDE: 40°59'10" LONGITUDE: 82°51'10"



PORTION TO BE IMPROVED - - - - -
INTERSTATE & DIVIDED HIGHWAY - - - - -
UNDIVIDED STATE & FEDERAL ROUTES - - - - -
OTHER ROADS - - - - -

DESIGN DESIGNATION

CURRENT ADT (2013) - - - - - 1500
DESIGN YEAR ADT (2033) - - - - - 2020
DESIGN HOURLY VOLUME (2033) - - - - - 166
DIRECTIONAL DISTRIBUTION - - - - - 50%
TRUCKS (24 HOUR B&C) - - - - - 5%
DESIGN SPEED - - - - - 55 MPH
LEGAL SPEED - - - - - 55 MPH
DESIGN FUNCTIONAL CLASSIFICATION: - - 05 MAJOR COLLECTOR (RURAL)
NHS PROJECT - - - - - NO

DESIGN EXCEPTIONS

NONE REQUIRED

UNDERGROUND UTILITIES
CONTACT BOTH SERVICES TWO WORKING DAYS BEFORE YOU DIG.

OHIO Utilities Protection SERVICE
Call Before You Dig
1-800-362-2764
(Non-members must be called directly)

OIL & GAS PRODUCERS UNDERGROUND PROTECTION SERVICE
1-800-925-0988

PLAN PREPARED BY:

JOHN J. DOE & ASSOC., INC.
CONSULTING ENGINEERS
9999 ENGLISH DRIVE
COMPUTERLAND, OHIO 00000

INDEX OF SHEETS:

| | |
|----------------------------------|-------|
| TITLE SHEET | 1 |
| SCHEMATIC PLAN | 2 |
| TYPICAL SECTIONS | 3-4 |
| GENERAL NOTES | 5 |
| MAINTENANCE OF TRAFFIC | 6 |
| DETOUR PLAN | 7 |
| MAINTENANCE OF TRAFFIC | 8-9 |
| GENERAL SUMMARY AND CALCULATIONS | 10 |
| PROJECT SITE PLAN | 11 |
| PLAN AND PROFILE | 12-13 |
| CROSS SECTIONS | 14-17 |
| PREFABRICATED STRUCTURES | 18-21 |
| RIGHT OF WAY | 22-27 |
| SOIL PROFILES | |

ENGINEERS SEAL:
FOR DESIGN CHANGES NOTED ON SHEET 4

SIGNED: *John J. Doe*
DATE: 11/11/14

ENGINEERS SEAL:
FOR ENTIRE PLAN EXCEPT STRUCTURES 20' & OVER

SIGNED: *Jane C. Smith*
DATE: 11/11/14

| PARTS 1 AND 2 | | | | | | SUPPLEMENTAL SPECIFICATIONS | |
|--------------------------------|---------|-----------|----------|--|--|-----------------------------|---------|
| STANDARD CONSTRUCTION DRAWINGS | | | | | | | |
| BP-3.1 | 7/18/14 | RM-1.1 | 7/18/14 | | | 800-2013 | 1/21/15 |
| CB-1.1 | 1/18/13 | AS-1-81 | 1/18/13 | | | 832 | 1/17/14 |
| CB-1.2 | 1/18/13 | TST-1-99 | 1/17/14 | | | | |
| DM-1.1 | 1/18/13 | MT-105.10 | 7/19/13 | | | | |
| DM-4.4 | 7/20/12 | MT-110.10 | 7/19/13 | | | | |
| MGS-1.1 | 7/19/13 | TC-41.20 | 10/18/13 | | | | |
| MGS-2.1 | 7/19/13 | TC-41.40 | 10/18/13 | | | | |
| MGS-4.2 | 7/19/13 | TC-52.10 | 10/18/13 | | | | |
| MGS-5.3 | 7/19/13 | TC-52.20 | 7/18/14 | | | | |
| HW-2.1 | 1/18/13 | | | | | | |
| HW-2.2 | 1/18/13 | | | | | | |
| | | | | | | SPECIAL PROVISIONS | |
| | | | | | | WATERWAY PERMIT | |
| | | | | | | 1/23/15 | |

FEDERAL PROJECT NO. E017 (212)
CONSTRUCTION PROJECT NO. 24988
RAILROAD INVOLVEMENT NONE
CRA-C.R. 6-1.61 (BOUNDARY RD.) PART 1
1/27

STATE OF OHIO
DEPARTMENT OF TRANSPORTATION

DEL-257-8.37
MAR-257-0.00

VILLAGE OF PROSPECT
CONCORD AND SCIOTO TOWNSHIPS
THOMPSON AND PROSPECT TOWNSHIPS
DELAWARE AND MARION COUNTIES

PROJECT DESCRIPTION


SPOT PAVEMENT REPAIRS ON SR-257 IN DELAWARE COUNTY BETWEEN SLM 8.37 (US-42/SR-745) AND SLM 14.26 (SR-37).

6' WIDE CONTINUOUS SLOT PAVING ON OUTSIDE EDGE OF SR-257 BEGINNING AT SLM 14.26 (SR-37) IN DELAWARE COUNTY AND ENDING AT SR-47 IN MARION COUNTY (SLM 0.66).

EARTH DISTURBED AREA:

PROJECT EARTH DISTURBED AREA N/A*
EST. CONTRACTOR EARTH DISTURBED AREA N/A*
NOTICE OF INTENT EARTH DISTURBED AREA N/A*


* MAINTENANCE PROJECT



LOCATION MAP

LATITUDE: 40° 20' 20" LONGITUDE: 83° 10' 47"

SCALE IN MILES



| | | |
|-------------------------|-------|-------|
| PORTION TO BE IMPROVED | ----- | ===== |
| INTERSTATE HIGHWAY | ----- | ===== |
| FEDERAL ROUTES | ----- | ===== |
| STATE ROUTES | ----- | ===== |
| COUNTY & TOWNSHIP ROADS | ----- | ===== |
| OTHER ROADS | ----- | ===== |

| DESIGN DESIGNATION | DEL-257-8.37 | MAR-257-0.00 |
|-----------------------------|--------------|--------------|
| CURRENT ADT (2012) | 1,762 | 813 |
| DESIGN YEAR ADT (2024) | 1,869 | 862 |
| DESIGN HOURLY VOLUME (2024) | 78 | 36 |
| DIRECTIONAL DISTRIBUTION | 50% | 50% |
| TRUCKS (24 HOUR B&C) | 4% | 9% |
| DESIGN SPEED | 60 | 60 |
| LEGAL SPEED | 55 | 35/55 |

DESIGN FUNCTIONAL CLASSIFICATION:
DEL-257-8.37: 05 MAJOR COLLECTOR (RURAL)
MAR-257-0.00: 06 MINOR COLLECTOR (RURAL)

DESIGN EXCEPTIONS
NONE REQUIRED

UNDERGROUND UTILITIES
CONTACT BOTH SERVICES TWO WORKING DAYS BEFORE YOU DIG.


Call Before You Dig
1-800-362-2764

(Non-members must be called directly)

OIL & GAS PRODUCERS
UNDERGROUND PROTECTION SERVICE
1-800-925-0988

PLAN PREPARED BY:
JOHN J. DOE & ASSOC., INC.
CONSULTING ENGINEERS
9999 ENGLISH DRIVE
COMPUTERLAND, OHIO 00000

ENGINEERS SEAL



SIGNED: John J. Doe
DATE: 01/21/11

INDEX OF SHEETS:

| | |
|------------------------------|-------|
| TITLE | 1 |
| TYPICAL DETAILS | 2 - 3 |
| GENERAL NOTES | 4 - 5 |
| MAINTENANCE OF TRAFFIC NOTES | 6 - 7 |
| GENERAL SUMMARY | 8 |
| PLAN SUBSUMMARY | 9 |
| PAVEMENT MARKING SUBSUMMARY | 10 |
| RPM SUBSUMMARY | 11 |

| STANDARD CONSTRUCTION DRAWINGS | | SUPPLEMENTAL SPECIFICATIONS | |
|--------------------------------|----------|-----------------------------|----------|
| BP-3.1 | 7/18/14 | 800-2013 | 1/21/15 |
| | | 821 | 04/20/12 |
| | | 832 | 1/17/14 |
| MT-97.11 | 7/18/14 | | |
| MT-97.12 | 7/18/14 | | |
| MT-99.20 | 7/19/13 | | |
| MT-105.10 | 7/19/13 | | |
| TC-41.20 | 10/18/13 | | |
| TC-42.20 | 10/18/13 | | |
| TC-52.10 | 10/18/13 | | |
| TC-52.20 | 7/18/14 | | |
| TC-65.10 | 1/17/14 | | |
| TC-65.11 | 7/18/14 | | |
| TC-71.10 | 1/17/14 | | |
| TC-82.10 | 10/18/13 | | |

SPECIAL PROVISIONS

2013 SPECIFICATIONS

THE STANDARD SPECIFICATIONS OF THE STATE OF OHIO, DEPARTMENT OF TRANSPORTATION, INCLUDING SUPPLEMENTAL SPECIFICATIONS LISTED IN THE PLANS AND CHANGES LISTED IN THE PROPOSAL SHALL GOVERN THIS IMPROVEMENT.

I HEREBY APPROVE THESE PLANS AND DECLARE THAT THE MAKING OF THIS IMPROVEMENT WILL NOT REQUIRE THE CLOSING TO TRAFFIC OF THE HIGHWAY AND THAT PROVISIONS FOR THE MAINTENANCE AND SAFETY OF TRAFFIC WILL BE AS SET FORTH ON THE PLANS AND ESTIMATES.

APPROVED _____
DATE _____ DISTRICT DEPUTY DIRECTOR

APPROVED _____
DATE _____ DIRECTOR, DEPARTMENT OF TRANSPORTATION

FEDERAL PROJECT NO.
NONE


PID NO.
93708

CONSTRUCTION PROJECT NO.

DEL-257-8.37
MAR-257-0.00



STATE OF OHIO, DEPARTMENT OF TRANSPORTATION



D04-PMF-FY13

FAST DRY PAVEMENT MARKINGS

CONSTRUCTION PROJECT NUMBER: 13-_____
 PID NO: _____
 FEDERAL PROJECT NUMBER: 100% STATE

PROJECT DESCRIPTION
 PLACEMENT OF PAVEMENT MARKING USING FAST DRY AT EXISTING LOCATIONS.

2013 SPECIFICATIONS
 THE STANDARD SPECIFICATIONS OF THE STATE OF OHIO, DEPARTMENT OF TRANSPORTATION, INCLUDING SUPPLEMENTAL SPECIFICATIONS LISTED IN THE PLANS AND CHANGES LISTED IN THE PROPOSAL SHALL GOVERN THIS IMPROVEMENT.

LIMITED ACCESS:
 THIS IMPROVEMENT IS ESPECIALLY DESIGNED FOR THROUGH TRAFFIC AND HAS BEEN DECLARED A LIMITED ACCESS HIGHWAY OR FREEWAY BY THE ACTION OF THE DIRECTOR IN ACCORDANCE WITH THE PROVISIONS OF SECTION 5511.02 OF THE OHIO REVISED CODE.

LATITUDE: 40° 17' 52" LONGITUDE: 83° 02' 58"

Project Earth Disturbed Area: N/A (Maintenance Project)
 Est. Contractor Earth Disturbed Area: N/A (Maintenance Project)
 Notice of Intent Earth Disturbed Area: N/A (Maintenance Project)
 Railroad Involvement: None
 DESIGN DESIGNATION: See Sheet _____
 DESIGN EXCEPTIONS: None

I HEREBY APPROVE THESE PLANS AND DECLARE THAT THE MAKING OF THIS IMPROVEMENT WILL NOT REQUIRE THE CLOSING TO TRAFFIC OF THE HIGHWAY AND THAT PROVISIONS FOR THE MAINTENANCE AND SAFETY OF TRAFFIC WILL BE AS SET FORTH ON THE PLANS AND ESTIMATES.

UNDERGROUND UTILITIES
 CONTACT BOTH SERVICES TWO WORKING DAYS BEFORE YOU DIG.

Call Before You Dig
1-800-362-2764

OIL & GAS PRODUCERS
 UNDERGROUND PROTECTION SERVICE
 1-800-925-0988

APPROVED: _____
 DISTRICT DEPUTY DIRECTOR

DATE: _____

APPROVED: _____
 DIRECTOR, DEPARTMENT OF TRANSPORTATION

DATE: _____

PLANS PREPARED BY:
 JOHN J. DOE & ASSOCIATES
 CONSULTING ENGINEERS
 999 ENGLISH DRIVE
 COMPUTERLAND, OHIO 00000

ENGINEERS SEAL:

SIGNED: John Doe
 DATE: 11-11-14



| STANDARD CONSTRUCTION DRAWINGS | | | | | | SUPPLEMENTAL SPECIFICATIONS | |
|--------------------------------|----------|-----------|----------|----------|----------|-----------------------------|-----------|
| MT-95.30 | 07/18/14 | MT-105.10 | 07/19/13 | TC-41.20 | 10/18/13 | 800-2013 | 1/15/2015 |
| MT-95.31 | 07/18/14 | | | TC-72.20 | 07/18/14 | 832 | 1/17/2014 |
| MT-95.32 | 07/18/14 | | | | | | |
| MT-95.50 | 07/19/13 | | | | | | |
| MT-98.10 | 07/18/14 | | | | | | |
| MT-98.11 | 07/18/14 | | | | | | |
| MT-98.20 | 07/18/14 | | | | | | |
| MT-98.22 | 07/18/14 | | | | | | |
| MT-98.28 | 07/18/14 | | | | | | |
| MT-99.20 | 07/19/13 | | | | | | |
| | | | | | | SPECIAL PROVISIONS | |
| | | | | | | NONE | |



CURVE DATA

P.I. Sta. = 367+51.56 @ Constr. S.R. 144
 $\Delta = 30^{\circ}00'00''$ (LT)
 $D_c = 8^{\circ}00'00''$
 $R = 716.20'$
 $L_s = 350.00'$
 $\theta_s = 14^{\circ}00'00''$
 $LT = 234.07'$
 $ST = 117.33'$
 $x = 347.92'$
 $y = 28.39'$
 $k = 174.65'$
 $p = 7.11'$
 $\Delta_c = 2^{\circ}00'00''$ (LT)
 $L_c = 25.00'$
 $T_s = 368.46'$
 $E_s = 32.63'$
 $e_{max} = 0.08$

NOTE: REFER TO THE SURVEYING PARAMETERS NOTE IN THE GENERAL NOTES FOR PROJECT CONTROL INFORMATION.




NOTE: There are no existing landscaped areas within the work limits.


CURVE DATA

P.I. Sta. = 7+34.52 @ Constr. S.R. 146
 $\Delta = 2^{\circ}23'53''$ (RT)
 $D_c = 1^{\circ}30'00''$
 $R = 3819.72'$
 $T = 79.95'$
 $L = 159.87'$
 $E = 0.84'$
 $e_{max} = NC$ (INDC 0.025)

CENTERLINE REFERENCES (Not to Scale)



CENTERLINE REFERENCE (Not to Scale)



I:\pr\35\tds\SamplePlans\2011\July\1303\1303_1.dgn 13-JUL-2011 12:17PM mwawski



SCHEMATIC PLAN & DESIGN DESIGNATIONS

MIA-43-26.15

The coordinate values expressed herein are assumed and tied to project specific control monuments with no scale factor applied. They are ground values in English units.

CURVE DATA
 P.I. STA.= 707+01.08 @ CONSTR. S.R. 43
 $\Delta = 3^\circ 33' 00''$ (LT.)
 $D_c = 1^\circ 00' 00''$
 $R = 5,729.58'$
 $T = 177.56'$
 $L = 355.00'$
 $E = 2.75'$
 $e_{max} = NC$

CURVE DATA
 P.I. STA. = 702+00.00 @ CONSTR. S.R. 43
 $\Delta = 0^\circ 35' 20''$ (LT.)
 NO CURVE


CURVE DATA
 P.I. STA.= 46+17.51 @ Constr. Trump Rd.
 $\Delta = 89^\circ 23' 07''$ (LT.)
 $D_c = 24^\circ 54' 40''$
 $R = 230.00'$
 $T = 227.55'$
 $L = 358.82'$
 $E = 93.54'$
 $e_{max} = 0.025$

CURVE DATA
 P.I. STA.= 744+49.29, @ CONSTR. S.R. 43
 $\Delta = 25^\circ 35' 20''$ (LT.)
 $D_c = 4^\circ 00' 22''$
 $R = 1,430.25'$
 $T = 324.80'$
 $L = 638.76'$
 $E = 36.42'$
 $e_{max} = NC$ (NDC 0.040)

CURVE DATA
 P.I. STA. 727+61.39 @ CONSTR. S.R. 43
 $\Delta = 1^\circ 05' 00''$ (LT.)
 $D_c = 0^\circ 29' 33''$
 $R = 11,635.10'$
 $T = 110.00'$
 $L = 219.99'$
 $E = 0.52'$
 $e_{max} = NC$

CURVE DATA
 PI STA. 41+61.02, @ Constr. Trump Rd.
 $\Delta = 50^\circ 48' 16''$ RT.
 $D_c = 24^\circ 54' 40''$
 $R = 230.00'$
 $T = 109.22'$
 $L = 203.94'$
 $E = 24.62'$
 $e_{max} = 0.078$

| DESIGN DESIGNATIONS | |
|--|--|
| S.R. 43 | RELOCATED TRUMP RD. |
| CURRENT ADT (2005) _____ 11,120 | CURRENT ADT (2005) _____ 1,420 |
| DESIGN YEAR ADT (2025) _____ 18,525 | DESIGN YEAR ADT (2025) _____ 1,990 |
| DESIGN HOURLY VOLUME (2025) _____ 2,574 | DESIGN HOURLY VOLUME (2025) _____ 199 |
| DIRECTIONAL DISTRIBUTION _____ 55% | DIRECTIONAL DISTRIBUTION _____ 55% |
| TRUCKS (24 HOUR B&C) _____ 4% | TRUCKS (24 HOUR B&C) _____ 4% |
| T_d _____ 5% | DESIGN SPEED _____ 25 MPH |
| DESIGN SPEED _____ 35 MPH | LEGAL SPEED _____ 25 MPH |
| LEGAL SPEED _____ 35 MPH | DESIGN FUNCTIONAL CLASSIFICATION: URBAN LOCAL |
| DESIGN FUNCTIONAL CLASSIFICATION - URBAN ARTERIAL | NHS Project _____ No |
| NHS Project _____ No | DESIGN EXCEPTIONS - NONE REQUIRED |
| DESIGN EXCEPTIONS - NONE REQUIRED | |



NOTE: There are no existing landscaped areas within the work limit.

I:\pr\1303\1303_V8\1303_2s.dgn 22-JUN-2006 12:43PM eblockso




SCHEMATIC PLAN

HAS - 36 - 8.21

CURVE DATA (Existing & Proposed)
P.I. STA.= 30+00.00 @ Constr. Meeker Rd.
 $\Delta = 0^\circ 55' 03''$ (RT.)
No Curve

CURVE DATA (EXISTING)
P.I. STA.= 653+16.78 @ Existing U.S. 36
 $\Delta = 84^\circ 32' 23''$ (RT.)
 $D_C = 28^\circ 55' 58''$
 $R = 198.03'$
 $T = 180.00'$
 $L = 292.19'$
 $E = 69.58'$
 $e_{max} = 0.08$

CURVE DATA (Proposed)
P.I. STA.= 653+16.78 @ Constr. U.S. 36
 $\Delta = 84^\circ 32' 23''$ (RT.)
 $D_C = 6^\circ 00' 00''$ (NDC $4^\circ 45'$ max.)
 $R = 954.93'$
 $L_S = 250.00'$
 $\theta_S = 7^\circ 30' 00''$
 $LT = 166.82'$
 $ST = 83.47'$
 $x = 249.57'$
 $y = 10.89'$
 $k = 124.93'$
 $p = 2.73'$
 $D_C = 69^\circ 32' 23''$ (RT.)
 $L_C = 1,159.00'$
 $T_S = 995.41'$
 $E_S = 339.22'$
 $e_{max} = 0.08$



Note: There are no existing landscaped areas within the work limit.

The coordinate values shown herein are converted from the Ohio State Plane Coordinate System, South Zone. The values were established using CORS Station LEBA with an applied scale factor of 1.000012754. These values are ground values and were further converted to English units.

I:\pr\1303\SamplePlans\Future Revision\1303_V8\1303_3s.dgn 22-JUN-2006 12:43PM eblockso

For Roads For Maintaining Traffic Details See Sheets 20-24.



SCHEMATIC PLAN & DESIGN DESIGNATION

SUM/POR-21-30.51/0.00 AND VARIOUS

CITY OF VICTORY

CURVE DATA
P.I. Sta. 26+02.47, @ Constr. Victory Road
 $\Delta = 39^\circ 03' 54''$ RT
 $D_c = 4^\circ 04' 06''$
 $R = 1408.30'$
 $T = 499.61'$
 $L = 960.20'$
 $E = 85.99'$
 $\theta_{max} = NC$ (NDC 0.057)

CURVE DATA
P.I. Sta. 1792+05.70, @ Constr. S.R. 21
 $\Delta = 35^\circ 19' 21''$ (LT)
 $D_c = 1^\circ 28' 00''$
 $R = 3,906.53'$
 $T = 1,234.82'$
 $L = 2,408.35'$
 $E = 193.23'$
 $\theta_{max} = 0.037$

CURVE DATA
P.I. Sta. 1814+54.72, @ Constr. S.R. 21
 $\Delta = 29^\circ 22' 21''$ (RT)
 $D_c = 2^\circ 00' 00''$
 $L_s = 300.00'$
 $L_c = 300.00'$
 $\theta_s = 3^\circ 00' 00''$
 $LT = 200.03'$
 $ST = 100.03'$
 $x = 299.22'$
 $y = 5.23'$
 $k = 149.99'$
 $p = 1.31'$
 $D_c = 23^\circ 22' 21''$ (RT)
 $L_c = 1,168.62'$
 $T_s = 901.15'$
 $E_s = 98.11'$
 $\theta_{max} = 0.045$


DESIGN DESIGNATION (S.R. 21) (S.R. 59 TO INTERCHANGE RD.)

| | |
|-----------------------------------|--------|
| CURRENT ADT (2005) | 14,410 |
| DESIGN YEAR ADT (2025) | 21,620 |
| DESIGN HOURLY VOLUME (2025) | 2,162 |
| DIRECTIONAL DISTRIBUTION | 50% |
| TRUCKS (24 HOUR B&C) | 22% |
| T_d | 20% |
| DESIGN SPEED | 60 MPH |
| LEGAL SPEED | 55 MPH |
| DESIGN FUNCTIONAL CLASSIFICATION: | |
| URBAN FREEWAY/EXPRESSWAY | |
| NHS Project | No |

The coordinate values shown herein are converted from the Ohio State Plane Coordinate System, South Zone. The values were established using CORS Station LEBA with an applied scale factor of 1.000012754. These values are ground values and were further converted to English units.

DESIGN EXCEPTIONS

| DESIGN FEATURE | APPROVAL DATE | SHEET NOS. |
|-----------------------|---------------|------------|
| HORIZONTAL CLEARANCE | 1-03-05 | 231 & 237 |
| GRADED SHOULDER WIDTH | 5-09-05 | 5 |



I:\pr\V3Std\SamplePlans\Future Revision\1303_V8\1303_4.as.dgn 22-JUN-2006 12:43PM eblockso



SCHEMATIC PLAN & DESIGN DESIGNATION

**SUM/POR-21-30.51-0.00
AND VARIOUS**

CITY
OF
VICTORY

CITY
OF
LINNEN

BROWNHELM TWP.

CITY
OF
VICTORY

The coordinate values shown herein are converted from the Ohio State Plane Coordinate System, South Zone. The values were established using CORS Station LEBA with an applied scale factor of 1.000012754. These values are ground values and were further converted to English units.

CURVE DATA
P.I. Sta. 150+59.03, @ Constr. S.R. 21
 $\Delta = 2^\circ 01' 10''$ LT
 $D_c = 0^\circ 15' 00''$
 $R = 22,918.31'$
 $T = 403.93'$
 $L = 807.78'$
 $E = 3.56'$
 $e_{max} = NC$


CURVE DATA
P.I. Sta. 66+35.86, @ Constr. S.R. 21
 $\Delta = 6^\circ 30' 00''$ RT
 $D_c = 0^\circ 28' 00''$
 $R = 12,277.67'$
 $T = 697.18'$
 $L = 1392.86'$
 $E = 19.78'$
 $e_{max} = NC$ (NDC 0.08)

**DESIGN DESIGNATION (S.R. 21)
(INTERCHANGE RD. TO BAUMHART RD.):**


| | |
|--|--------|
| CURRENT ADT (2005) | 16,520 |
| DESIGN YEAR ADT (2025) | 24,815 |
| DESIGN HOURLY VOLUME (2025) | 2,482 |
| DIRECTIONAL DISTRIBUTION | 50% |
| TRUCKS (24 HOUR B&C) | 22% |
| T_d | 20% |
| DESIGN SPEED | 60 MPH |
| LEGAL SPEED | 55 MPH |
| DESIGN FUNCTIONAL CLASSIFICATION - URBAN FREEWAY/EXPRESSWAY | |
| NHS Project | No |

DESIGN EXCEPTIONS:


| DESIGN FEATURE | APPROVAL DATE | SHEET NOS. |
|-----------------------|---------------|------------|
| HORIZONTAL CLEARANCE | 1-03-05 | 231 & 237 |
| GRADED SHOULDER WIDTH | 5-09-05 | 5 |



I:\pr\35\35\SamplePlans\Future Revision\1303_V8\1303_4bs.dgn 22-JUN-2006 12:43PM eblockso



NORMAL SECTION - U.S. 46
Sta. 634+00.00 to Sta. 635+75.00




BASE AND SUBBASE STEP DETAIL


- A** Unless otherwise shown on Cross Sections
- B** No rounding is required when foreslope is 6:1 or flatter. 4' Rounding when guardrail is required.
- C** Foreslope may vary in pavement transition areas at extreme ends of pavement work and adjacent to Structure PIC-46-1209; see cross sections.
- D** 0.04 Min., 0.08 Desirable

LEGEND


- ① ITEM 442 - 1½" ASPHALT CONCRETE SURFACE COURSE, 12.5mm, TYPE A (448)
 - ② ITEM 442 - 1¾" ASPHALT CONCRETE INTERMEDIATE COURSE, 19mm, Type A (448)
 - ③ ITEM 301 - 5" ASPHALT CONCRETE BASE, PG64-22
 - ④ ITEM 304 - 6" AGGREGATE BASE
 - ⑤ ITEM 304 - 8" AGGREGATE BASE
 - ⑥ ITEM 407 - TACK COAT
 - ⑦ ITEM 408 - PRIME COAT (APPLIED AT A RATE OF 0.40 GAL./SQ. YD.)
 - ⑧ ITEM 206 - LIME STABILIZED SUBGRADE, 18 INCHES DEEP
 - ⑨ ITEM 605 - AGGREGATE DRAINS
 - ⑩ ITEM 606 - GUARDRAIL, MGS
 - ⑪ ITEM 615 - PAVEMENT FOR MAINTAINING TRAFFIC, CLASS A, AS PER PLAN (SEE RESPECTIVE MAINTENANCE OF TRAFFIC DETAILS)
 - ⑫ ITEM 204 - SUBGRADE COMPACTION
 - ⑬ ITEM 659 - SEEDING AND MULCHING
 - ⑭ ITEM 526 - REINFORCED CONCRETE APPROACH SLABS (T=15")
 - ⑮ NOT USED
 - ⑯ ITEM 605 - 6" SHALLOW PIPE UNDERDRAINS
- (A) 3" ± ASPHALT CONCRETE
(B) 8" ± CONCRETE PAVEMENT




NORMAL SECTION - U.S. 46
Sta. 635+75.00 to Sta. 642+81.37
Sta. 638+22.44 to Sta. 640+48.86



SHOULDER DETAIL
For pavement slopes of 0.010 or less




SHOULDER DETAIL
For pavement slopes greater than 0.010



SUPERELEVATED SECTION - U.S. 46


Sta. 642+81.37 to Sta. 649+00.00



SUPERELEVATED SECTION - U.S. 46


- A Same slope as pavement
- B Or pavement slope whichever is greater
- C For high side shoulder slopes on superelevated sections see shoulder details, this sheet.
- D 0.04 Min., 0.08 Desirable
- E Sta. 649+00.00 to Sta. 651+45.03
- F Sta. 651+45.03 to Sta. 654+75.03
- G Sta. 654+75.03 to Sta. 658+77.85

STA. 656+57.63 TO STA. 658+77.85, SEE INTERSECTION DETAIL ON SHEET 39.
SEE INTERSECTION DETAIL, SHEET 39.
FOR PAVEMENT LEGEND, SEE SHEET 3.
FOR BASE AND SUBBASE STEP DETAIL, SEE SHEET 3.




SUPERELEVATED SECTION - U.S. 46

- E** STA. 658+77.85 TO STA. 659+27.03
- F** STA. 659+27.03 TO STA. 660+20.37




SHOULDER DETAIL
For pavement slopes of 0.010 or less



NORMAL SECTION - U.S. 46


- G** STA. 660+20.37 TO STA. 660+51.59
- H** STA. 660+51.59 TO STA. 663+81.59
- I** STA. 663+81.59 TO STA. 664+31.59
- J** STA. 664+31.59 TO STA. 664+81.59



SHOULDER DETAIL
For pavement slopes of more than 0.010


- A** SAME SLOPE AS PAVEMENT
- B** 0.06 OR SAME SLOPE AS PAVEMENT WHICHEVER IS GREATER
- C** FOR HIGH SIDE SHOULDER SLOPES ON SUPERELEVATED SECTIONS SEE SHOULDER DETAILS, THIS SHEET.
- D** 0.04 MIN., 0.08 DESIRABLE

FOR PAVEMENT LEGEND SEE SHEET 3.
FOR BASE AND SUBBASE STEP DETAIL SEE SHEET 3.



NORMAL SECTION - ARLINGTON ROAD

- A** Sta. 21+00.00 to Sta. 21+37.83
- B** Sta. 21+37.83 to Sta. 24+37.83
- C** Sta. 24+37.83 to Sta. 29+05.61
Sta. 31+26.68 to Sta. 31+44.41
- D** Sta. 31+44.41 to Sta. 34+25.00



APPROACH SLAB TYPICAL SECTION - U.S. 46




STRUCTURE PIC-46-1209 = Sta. 638+22.44 to Sta. 640+48.86
Sta. 638+47.44 to Sta. 640+23.86


- E** Unless otherwise shown on Cross Sections
- F** Foreslope may vary in pavement transition areas at extreme ends of pavement work; See Cross Sections.
- G** No rounding is required when foreslope is 6:1 or flatter.

FOR PAVEMENT LEGEND SEE SHEET 3.
FOR BASE AND SUBBASE STEP DETAIL, SEE SHEET 3.


LEGEND

- (1) ITEM 441 - 1 1/4" Asphalt Concrete Surface Course, Type 1, (448) PG64-22
 - (2) ITEM 441 - 1 3/4" Asphalt Concrete Intermediate Course, Type 2, (448)
 - (3) ITEM 305 - 9" Concrete Base, As Per Plan
 - (4) ITEM 304 - 6" Aggregate Base
 - (5) ITEM 254 - Pavement Planing, Asphalt Concrete (Max. Depth=3")
 - (6) ITEM 301 - 9" Asphalt Concrete Base, PG64-22
 - (7) ITEM 304 - 9" Aggregate Base
 - (8) ITEM 301 - 4" Asphalt Concrete Base, PG64-22
 - (9) ITEM 304 - Aggregate Base, Depth as shown
 - (10) ITEM 408 - Prime Coat (Applied At The Rate Of 0.4 Gal/Sq. Yd.)
 - (11) ITEM 407 - Tack Coat
 - (12) ITEM 609 - Curb, Type 6
 - (13) ITEM 660 - Sodding Unstaked
 - (14) ITEM 605 - 6" Shallow Pipe Underdrains
 - (15) ITEM 204 - Subgrade Compaction
 - (16) ITEM 609 - Curb, Type 2-B
- (A) 12" ± Asphalt
 - (B) 8" ± Subbase
 - (C) Curb & Gutter
 - (D) 4" Concrete Sidewalk
 - (E) 3" ± Asphalt
 - (F) 9" ± Reinforced Concrete
 - (G) 6" ± Subbase
 - (H) 10" ± Asphalt
 - (J) 4" ± Subbase
- A 25'-0" From Sta. 0+84 to Sta. 3+50
Varies: 25'-0" @ Sta. 3+50 to 12' @ Sta. 4+00
 - B 12'-0" From Sta. 0+84 to Sta. 3+50
Varies: 12'-0" @ Sta. 3+50 to 11'-0" @ Sta. 4+00
 - C Varies: 4' @ Sta. 3+50 to 2' @ Sta. 4+00






NORMAL SECTION - S.R. 307
STA. 88+75.00 TO STA. 90+15.00



GUARDRAIL SECTION
STA. 93+75 TO STA. 95+25 (L.T.)



NORMAL SECTION - S.R. 307
STA. 90+15.00 TO STA. 96+45.00

LEGEND




- | | |
|--|---|
| ① ITEM 441 - 1/2" ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448) PG64-22 | ⑧ ITEM 606 - GUARDRAIL, TYPE MGS |
| ② ITEM 254 - PAVEMENT PLANING, ASPHALT CONCRETE [A] | ⑨ ITEM 659 - SEEDING AND MULCHING (SEE GENERAL NOTE) |
| ③ ITEM 301 - 9" ASPHALT CONCRETE BASE, PG64-22 | ⑩ SEE PAVEMENT BUILDUP NOTE, THIS SHEET [B] |
| ④ ITEM 304 - AGGREGATE BASE, DEPTH AS SHOWN | ⑪ ITEM 204 - SUBGRADE COMPACTION |
| ⑤ ITEM 609 - CURB, TYPE 6 | ⑫ ITEM 605 - 6" BASE PIPE UNDERDRAINS |
| ⑥ ITEM 407 - TACK COAT | ⑬ ITEM 660 - SODDING UNSTAKED |
| ⑦ ITEM 408 - PRIME COAT (APPLIED AT THE RATE OF 0.4 GAL./SQ.YD.) | ⑭ ITEM 441 - 1 3/4" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (448) |
| (A) 6" ASPHALT SURFACE | (D) CURB & GUTTER (TO BE REMOVED) |
| (B) 9" REINFORCED CONCRETE BASE | (E) ROADWAY DRAINAGE, 12" (TO BE REMOVED) |
| (C) 6" MIN. CLASSIFIED EMBANKMENT BLANKET COURSE | (F) CURB (TO BE REMOVED) |

S.R. 307 PAVEMENT PLANING TABLES

| STATION | PROPOSED PROFILE ELEVATION | PLANING DEPTH (FEET) @ E | STATION | PROPOSED PROFILE ELEVATION | PLANING DEPTH (FEET) @ E |
|---------|----------------------------|--------------------------|---------|----------------------------|--------------------------|
| 88+50 | 1094.08 | 0.17 | 92+75 | 1095.26 | 0.27 |
| 88+75 | 1094.17 | 0.15 | 93+00 | 1095.28 | 0.19 |
| 89+00 | 1094.26 | 0.16 | 93+25 | 1095.32 | 0.20 |
| 89+25 | 1094.34 | 0.19 | 93+50 | 1095.36 | 0.21 |
| 89+50 | 1094.43 | 0.20 | 93+75 | 1095.41 | 0.22 |
| 89+75 | 1094.52 | 0.19 | 94+00 | 1095.46 | 0.24 |
| 90+00 | 1094.61 | 0.21 | 94+25 | 1095.51 | 0.28 |
| 90+25 | 1094.69 | 0.20 | 94+50 | 1095.56 | 0.38 |
| 90+50 | 1094.78 | 0.18 | 94+75 | 1095.61 | 0.34 |
| 90+75 | 1094.87 | 0.18 | 95+00 | 1095.66 | 0.26 |
| 91+00 | 1094.96 | 0.18 | 95+25 | 1095.71 | 0.17 |
| 91+25 | 1095.04 | 0.17 | 95+50 | 1095.69 | 0.16 |
| 91+50 | 1095.13 | 0.17 | 95+75 | 1095.67 | 0.15 |
| 91+75 | 1095.16 | 0.18 | 96+00 | 1095.65 | 0.14 |
| 92+00 | 1095.18 | 0.20 | 96+25 | 1095.63 | 0.15 |
| 92+25 | 1095.21 | 0.23 | 96+50 | 1095.61 | 0.16 |
| 92+50 | 1095.23 | 0.28 | | | |

NOTES


- S.R. 307 - THE CROWN SHALL BE WORKED OUT OF THE PAVEMENT BETWEEN STA. 92+57.25 AND STA. 92+97.25.
- THE PAVEMENT BETWEEN STA. 92+97.25 AND STA. 94+02.25 SHALL BE BUILT WITHOUT CROWN.
- THE CROWN SHALL BE WORKED INTO THE PAVEMENT BETWEEN STA. 94+02.25 AND STA. 94+42.25.
- [A] IN AN EFFORT TO REMOVE EXISTING PARABOLIC CROWN AND ESTABLISH A SMOOTH AND CONSISTENT PROFILE THROUGHOUT THE PROJECT, THE PAVEMENT SHALL BE PLANED TO A DEPTH INDICATED IN THE PAVEMENT PLANING TABLE ON THIS SHEET. A 0.016 NORMAL CROSS SLOPE SHALL BE ESTABLISHED FROM THE CENTERLINE TO THE EXISTING EDGE OF PAVEMENT.
- [B] THE PAVEMENT BUILD-UP WHEN ADJOINING AN EXISTING ASPHALT PAVEMENT SHALL BE AS FOLLOWS:
 ITEM 441 - 1/4" ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448) PG64-22
 ITEM 441 - 1 3/4" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (448)
 ITEM 304 - 8" AGGREGATE BASE
 THE PAVEMENT BUILD-UP WHEN ADJOINING AN EXISTING GRAVEL OR SLAG PARKING AREA SHALL BE AS FOLLOWS:
 ITEM 304 - 11" AGGREGATE BASE
- [C] UNCLASSIFIED UNDERDRAIN LIMITS:
 STA. 88+75 TO STA. 91+25 AND
 STA. 95+25 TO STA. 96+27.25



LEGEND

- ① ITEM 441 - 1/4" ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (446) PG64-22
- ② ITEM 441 - 1 3/4" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (446)
- ③ ITEM 301 - 10" ASPHALT CONCRETE BASE, PG64-22
- ④ ITEM 304 - 6" AGGREGATE BASE
- ⑤ ITEM 204 - SUBGRADE COMPACTION
- ⑥ ITEM 605 - 6" SHALLOW PIPE UNDERDRAINS [D]
- ⑦ ITEM 609 - COMBINATION CURB AND GUTTER, TYPE 2, AS PER PLAN (SEE SHEET 9)
- ⑧ ITEM 606 - GUARDRAIL, TYPE 5
- ⑨ ITEM 659 - SEEDING AND MULCHING
- ⑩ ITEM 608 - 4" CONCRETE WALK
- ⑪ ITEM 441 - ASPHALT CONCRETE SURFACE COURSE, TYPE 1 (446) PG64-22 (VARIABLE THICKNESS)
- ⑫ ITEM 407 - TACK COAT
- ⑬ ITEM 408 - PRIME COAT (APPLIED AT THE RATE OF 0.4 GAL./SQ. YD.)
- ⑭ NOT USED
- ⑮ ITEM 660 - SODDING UNSTAKED
- (A) 3" ± ASPHALT PAVEMENT OVER 10" ± AGGREGATE SUBBASE
- (B) 8" ± DENSE ASPHALT





TRANSITION PAVEMENT CROWN TO MEET EXISTING CROWN BETWEEN STA. 130+00 AND STA. 133+00. SEE SHEET 15 FOR DETAILS.




NOTES:

FOR VARIABLE PAVEMENT WIDTHS AND SIDEWALK LIMITS, SEE PAVEMENT DETAILS, SHEETS 15 - 18.

- [A] WIDTH VARIES FROM 34'-0" @ STA. 129+50 TO 22'-0" @ STA. 130+00 DUE TO RIGHT TURN LANE TAPER FROM 12' TO 0'
- [B] WIDTH VARIES FROM 34'-0" @ STA. 124+60 TO 22'-0" @ STA. 130+00 DUE TO RIGHT THRU LANE TAPER FROM 12' TO 0'
- [C] PAVEMENT WIDTH VARIES FROM 18'-0", LT. & RT. @ STA. 130+00 TO 16'-0" LT. AND 8'-0", RT. @ STA. 133+00 DUE TO LEFT TURN LANE TRANSITION
- [D] EXCEPT IN AREAS OF GUARDRAIL SECTIONS, PIPE UNDERDRAINS SHALL BE LOCATED IMMEDIATELY BEHIND THE CURB.
- [E] OR PAVEMENT SLOPE, IF GREATER
- [F] ITEM 441, ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (446) PG64-22, IS TO BE 1/4" ABOVE GUTTER PLATE.




- LEGEND**
- ① ITEM 452 - 12" Non-Reinforced Concrete Pavement
 - ② ITEM 304 - 6" Aggregate Base
 - ③ ITEM 605 - 6" Deep Pipe Underdrains
 - ④ ITEM 606 - Guardrail, Type MGS
 - ⑤ ITEM 659 - Seeding and Mulching
 - ⑥ ITEM 204 - Subgrade Compaction
 - ⑦ ITEM 605 - 6" Base Pipe Underdrains
 - A 0.04 Max. to 0.034 Min.
 - B Slope conditions shown for high side shoulder adjacent to speed change lane pavement; For low side of shoulders adjacent to speed change lane pavement, shoulder slope shall be 0.04.
 - C Longitudinal Joint Per BP-2.1



Slopes as Shown on Grading Plan. See Sheets 280-282

NORMAL SECTION - RAMPS C & D

Sta. 465+49.13 to Sta. 477+25.00 Ramp C
Sta. 557+00.00 to Sta. 566+96.94 Ramp D




Slopes as Shown on Cross Sections.

NORMAL SECTION - RAMPS A & B

Sta. 160+75.00 to Sta. 166+65.18 Ramp A
Sta. 266+17.10 to Sta. 271+50.00 Ramp B


- A** WHEN FORESLOPE IS 6:1 OR FLATTER
- B** FOR GUARDRAIL SECTIONS AND NON-GUARDRAIL SECTIONS WITH FORESLOPE STEEPER THAN 6:1
- C** SEE DETAILS "A" AND "B"
- D** 4' ROUNDING ON GUARDRAIL SECTIONS; NO ROUNDING REQUIRED WHEN FORESLOPE IS 6:1 OR FLATTER.
- E** GUARDRAIL DETAIL DOES NOT APPLY



Slopes as Shown on Grading Plan. See Sheets 280-282

SUPERELEVATED SECTION (RIGHT) - RAMPS C & D


Sta. 477+25.00 to Sta. 481+60.26 Ramp C
Sta. 554+58.38 to Sta. 557+00.00 Ramp D




Slopes as Shown on Grading Plan. See Sheets 280-282

SUPERELEVATED SECTION (LEFT) - RAMPS E & F

Sta. 354+62.19 to Sta. 360+75.00 Ramp E
Sta. 571+50.00 to Sta. 577+03.57 Ramp F



DETAIL A




DETAIL B


FOR LEGEND, SEE SHEET 9

LEGEND

- | | | | |
|---|---|---|-------------------------------------|
| ① | ITEM 880 - 10" ASPHALT CONCRETE (7 YEAR WARRANTY) | ⑥ | ITEM 606 - GUARDRAIL, MGS |
| ② | ITEM 408 - PRIME COAT (0.4 GAL/YD ²) | ⑦ | ITEM 659 - SEEDING AND MULCHING |
| ③ | ITEM 304 - 6" AGGREGATE BASE | ⑧ | ITEM 204 - SUBGRADE COMPACTION |
| ④ | ITEM 304 - 10" AGGREGATE BASE | ⑨ | ITEM 605 - 6" BASE PIPE UNDERDRAINS |
| ⑤ | ITEM 605 - 4" SHALLOW PIPE UNDERDRAINS, AS PER PLAN | ⑩ | ITEM 605 - 4" BASE PIPE UNDERDRAINS |




TYPICAL SECTION #1
60' MEDIAN - NORMAL SECTION - U.S. 35
STA. 595+00 TO STA. 607+50



RAMP B ACCEL. LANE DETAIL

* SLOPE MATCHES MAINLANE RATE (0.016) UNTIL SUPER TRANSITION FOR RAMP. TRANSITION FROM NORMAL CROSS SLOPE TO SUPERELEVATED SECTION BETWEEN STATIONS 598+75 AND 600+90.

** 0.042 OR RATE OF SUPER, IF GREATER.



RAMP A DECEL. LANE DETAIL

* SLOPE MATCHES MAINLANE RATE (0.016) UNTIL SUPER TRANSITION FOR RAMP. TRANSITION FROM NORMAL CROSS SLOPE TO SUPERELEVATED SECTION BETWEEN STATIONS 595+50 AND 596+25.

** 0.042 OR RATE OF SUPER, IF GREATER.

ROUNDING

THE ROUNDING AT SLOPE BREAKPOINTS SHOWN ON THE TYPICAL SECTIONS APPLY TO ALL CROSS-SECTIONS EVEN THOUGH OTHERWISE SHOWN.

UTILITIES

LISTED BELOW ARE ALL UTILITIES LOCATED WITHIN THE PROJECT CONSTRUCTION LIMITS TOGETHER WITH THEIR RESPECTIVE OWNERS:

ELECTRIC:
 AMERICAN ELECTRIC POWER
 215 NORTH FRONT STREET
 COLUMBUS, OHIO 43215
 (614) 464-7911

GAS:
 COLUMBIA GAS OF OHIO
 939 WEST GOODALE BOULEVARD
 COLUMBUS, OHIO 43212
 (614) 460-2240

TELEPHONE:
 SBC AMERITECH
 150 EAST GAY STREET
 ROOM 6F
 COLUMBUS, OHIO 43215
 (614) 223-8535

CABLE:
 TIME WARNER COMMUNICATIONS
 1266 DUBLIN ROAD
 COLUMBUS, OHIO 43212
 (614) 481-5261

SANITARY, STORM:
 CITY OF COLUMBUS
 DIVISION OF SEWERAGE & DRAINAGE
 910 DUBLIN ROAD
 COLUMBUS, OHIO 43215
 (614) 645-7175

WATER:
 CITY OF COLUMBUS
 DIVISION OF WATER
 910 DUBLIN ROAD
 COLUMBUS, OHIO 43215
 (614) 645-7677

UTILITIES

THE LOCATION OF THE UNDERGROUND UTILITIES SHOWN ON THE PLANS ARE AS OBTAINED FROM THE OWNERS AS REQUIRED BY SECTION 153.64 O.R.C.

SURVEYING PARAMETERS

PRIMARY PROJECT CONTROL MONUMENTS GOVERN ALL POSITIONING ON ODOT PROJECTS. SEE THIS SHEET FOR A TABLE CONTAINING PRIMARY PROJECT CONTROL INFORMATION.

USE THE FOLLOWING PRIMARY PROJECT CONTROL, VERTICAL POSITIONING, AND HORIZONTAL POSITIONING PARAMETERS FOR ALL SURVEYING:

PRIMARY PROJECT CONTROL

POSITIONING METHOD: STATIC GNSS
 MONUMENT TYPE: A

VERTICAL POSITIONING

ORTHOMETRIC HEIGHT DATUM: NAVD88
 GEOID: GEOID09

HORIZONTAL POSITIONING

REFERENCE FRAME: NAD83(CORS96)
 ELLIPSOID: GRS80
 MAP PROJECTION: LAMBERT CONFORMAL CONIC
 COORDINATE SYSTEM: OHIO STATE PLANE - SOUTH ZONE
 COMBINED SCALE FACTOR: 1.000059007
 ORIGIN OF COORDINATE SYSTEM: 0,0

USE THE POSITIONING METHOD AND MONUMENT TYPE USED IN THE ORIGINAL SURVEY TO RESTORE ALL MONUMENTS RELATED TO PRIMARY PROJECT CONTROL THAT ARE DAMAGED OR DESTROYED BY CONSTRUCTION ACTIVITIES. RESTORE THE DAMAGED OR DESTROYED MONUMENTS IN ACCORDANCE WITH CMS 623 - CONSTRUCTION LAYOUT STAKES AND SURVEY MONUMENTS.

UNITS ARE IN U.S. SURVEY FEET.
 USE THE FOLLOWING CONVERSION FACTOR:
 1 METER = 3.280833333 U.S. SURVEY FEET

WORK LIMITS

THE WORK LIMITS SHOWN ON THESE PLANS ARE FOR PHYSICAL CONSTRUCTION ONLY. PROVIDE THE INSTALLATION AND OPERATION OF ALL WORK ZONE TRAFFIC CONTROL AND WORK ZONE TRAFFIC CONTROL DEVICES REQUIRED BY THESE PLANS WHETHER INSIDE OR OUTSIDE THESE WORK LIMITS.

CLEARING AND GRUBBING

REMOVE ALL TREES AND STUMPS SPECIFICALLY MARKED FOR REMOVAL WITHIN THE CONSTRUCTION LIMITS UNDER THE LUMP SUM BID FOR ITEM 201, CLEARING AND GRUBBING. THE FOLLOWING IS AN APPROXIMATE ESTIMATE OF THE NUMBER OF TREES AND STUMPS TO BE REMOVED.

| SIZES | NO. TREES | NO. STUMPS | TOTAL |
|-------|-----------|------------|-------|
| 18" | 8 | 2 | 10 |
| 30" | 1 | 2 | 3 |
| 48" | 0 | 1 | 1 |
| 60" | 1 | 0 | 1 |

SEEDING AND MULCHING

THE FOLLOWING QUANTITIES ARE PROVIDED TO PROMOTE GROWTH AND CARE OF PERMANENT SEEDED AREAS:

659, SEEDING AND MULCHING 310 SY

659, REPAIR SEEDING AND MULCHING 16 SY
 (310) X (0.05) = 15.5 SY

659, SOIL ANALYSIS TEST 2 EACH

659, TOPSOIL 34 CY
 (310) X (111 CY PER 1000 SY) = 34.4 CY

659, COMMERCIAL FERTILIZER 0.05 TON
 [(310) X (1 TON / 7410 SY)] + [(16 SY) X (1 TON / 11115 SY)] = 0.05 TON

659, LIME 0.1 ACRE
 (310) X (1 ACRE / 4840 SY) = 0.06 ACRE

659, INTER-SEEDING 16 SY
 (310) X (0.05) = 15.5 SY

659, WATER 2 MGAL
 [(310) X (0.0054 MGAL / SY)] + [(16) X (.0027 GAL/SY)] = 2 MGAL

APPLY SEEDING AND MULCHING TO ALL AREAS OF EXPOSED SOIL BETWEEN THE RIGHT-OF-WAY LINES, AND WITHIN THE CONSTRUCTION LIMITS, FOR AREAS OUTSIDE THE RIGHT-OF-WAY LINES COVERED BY WORK AGREEMENT AND TEMPORARY EASEMENT. QUANTITY CALCULATIONS FOR SEEDING AND MULCHING ARE BASED ON THESE LIMITS.

RESIDENTIAL AND COMMERCIAL DRAINAGE CONNECTIONS

EXISTING ROOF DRAINS, FOOTER DRAINS, OR YARD DRAINS, DISTURBED BY THE WORK, SHALL BE PROVIDED WITH UNOBSTRUCTED OUTLETS BY CONNECTING A CONDUIT THROUGH THE CURB OR INTO A DRAINAGE STRUCTURE. THE LOCATION, TYPE, SIZE AND GRADE OF THE NEW CONDUIT REQUIRED TO REPLACE, OR EXTEND, THE EXISTING DRAIN WILL BE DETERMINED BY THE ENGINEER.

THE FOLLOWING CONDUIT TYPES MAY BE USED: 707.33, 707.41 NON-PERFORATED, 707.42, 707.43, 707.45, 707.46, 707.47, 707.51, 707.52 SDR35.

THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN INCLUDED IN THE GENERAL SUMMARY FOR USE AS DIRECTED BY THE ENGINEER FOR THE WORK NOTED ABOVE:

| | |
|-------------------------|--------|
| 611, 6" CONDUIT, TYPE B | 50 FT. |
| 611, 6" CONDUIT, TYPE C | 50 FT. |
| 611, 6" CONDUIT, TYPE E | 50 FT. |
| 611, 6" CONDUIT, TYPE F | 50 FT. |

PROFILE AND ALIGNMENT

THE PROPOSED PAVEMENT RESURFACING SHALL FOLLOW THE ALIGNMENT SHOWN ON THE PLAN VIEW SHEETS. THE PROPOSED PROFILE SHALL FOLLOW THE PROPOSED ELEVATIONS SHOWN ON THE CROSS SECTION SHEETS. THE PROPOSED ASPHALT CONCRETE OVERLAY SHALL VARY TO PRODUCE THE PROPOSED ELEVATIONS SHOWN ON THE CROSS SECTIONS.

| PRIMARY PROJECT CONTROL INFORMATION | | | | | | |
|-------------------------------------|--------------------------------------|-------------|--|-------------|--------------------------------------|---|
| POINT NUMBER | GRID COORDINATES U.S. SURVEY FEET | | SCALED COORDINATES U.S. SURVEY FEET | | ORTHOMETRIC HEIGHT (ELEVATION) | DESCRIPTION |
| | NORTHING | EASTING | NORTHING | EASTING | | |
| CP1 | 648471.989 | 2085554.754 | 648510.253 | 2085677.816 | 634.80 | PROJECT CONTROL - STEEL ROD SET IN CONCRETE |
| CP2 | 646970.005 | 2084508.912 | 647008.181 | 2084631.913 | 636.54 | PROJECT CONTROL - STEEL ROD SET IN CONCRETE |
| CP3 | 647678.067 | 2084753.211 | 647716.285 | 2084876.226 | 655.38 | AZIMUTH MARK - STEEL ROD SET IN CONCRETE |
| CP4 | 647186.714 | 2084974.770 | 647224.903 | 2084974.711 | 656.63 | AZIMUTH MARK - STEEL ROD SET IN CONCRETE |

ITEM 659, SEEDING AND MULCHING

SEEDING AND MULCHING SHALL BE APPLIED TO ALL AREAS OF EXPOSED SOIL BETWEEN THE RIGHT-OF-WAY LINES, AND WITHIN THE CONSTRUCTION LIMITS FOR AREAS OUTSIDE THE RIGHT-OF-WAY LINES COVERED BY WORK AGREEMENT OR SLOPE EASEMENT. QUANTITY CALCULATIONS FOR ITEM 659, SEEDING AND MULCHING, ARE BASED ON THESE LIMITS.

SEE SHEET 18 FOR SEEDING AND MULCHING SUBSUMMARY.

WATERING AND MOWING PERMANENT SEEDED AREAS

THE FOLLOWING ESTIMATED QUANTITIES ARE TO BE USED AS DIRECTED BY THE ENGINEER TO PROMOTE GROWTH AND TO CARE FOR PERMANENT SEEDED AREAS PER 659.09:

| | |
|-------------|--------------|
| 659, WATER | 22 M.GAL. |
| 659, MOWING | 23 M SQ. FT. |

EROSION CONTROL

ITEMS 601, 660 AND 670 ARE PROVIDED IN THE PLANS FOR EROSION CONTROL. ROCK OF A STABLE NATURE SHALL NOT BE REMOVED IN ORDER TO PLACE ANY OF THESE ITEMS AND TURF OF A STABLE NATURE SHALL NOT BE REMOVED IN ORDER TO PLACE 660 OR 670. THE ENGINEER SHALL CHECK AND NON-PERFORM QUANTITIES OR ADJUST LOCATIONS AND QUANTITIES OF THESE ITEMS WHERE INDICATED BY FIELD CONDITIONS DURING CONSTRUCTION.

ITEM 604, CATCH BASIN NO. 2-3 AND 2-5 AS PER PLAN

CATCH BASINS SHALL BE CONSTRUCTED IN CONFORMANCE WITH ITEM 604 EXCEPT THAT THE GRATES SHALL BE NEENAH NO. R-4859-C OR EAST JORDAN NO. 5110 TYPE M2 OR APPROVED EQUALS.

ITEM 611 - CONDUIT BORED OR JACKED

WHERE IT IS SPECIFIED THAT A CONDUIT BE INSTALLED BY THE METHOD OF BORING OR JACKING, NO TRENCH EXCAVATION SHALL BE CLOSER THAN 10 FEET TO THE (EDGE OF PAVEMENT) NEAREST RAIL). PROVIDE A 0.50 INCH UNGALVANIZED CASING PIPE CONFORMING TO 748.06 THAT HAS JOINT WITH A CIRCUMFERENTIAL FULLY PENETRATING B-U4B WELD THAT IS PERFORMED BY AN ODOT APPROVED FIELD WELDER. THE INSTALLED CASING PIPE IN THE STORM WATER CONVEYANCE CARRIER UNLESS OTHERWISE SPECIFIED IN THE PLANS. HYDROSTATIC TESTING IS NOT REQUIRED FOR THE CASING PIPE.

CROSSINGS AND CONNECTIONS TO EXISTING PIPES AND UTILITIES

WHERE PLANS PROVIDE FOR A PROPOSED CONDUIT TO BE CONNECTED TO, OR CROSS OVER OR UNDER AN EXISTING SEWER OR UNDERGROUND UTILITY, THE CONTRACTOR SHALL LOCATE THE EXISTING PIPES OR UTILITIES BOTH AS TO LINE AND GRADE BEFORE STARTING TO LAY THE PROPOSED CONDUIT.

IF IT IS DETERMINED THAT THE ELEVATION OF THE EXISTING CONDUIT, OR EXISTING APPURTENANCE TO BE CONNECTED, DIFFERS FROM THE PLAN ELEVATION OR RESULTS IN A CHANGE IN THE PLAN CONDUIT SLOPE, THE ENGINEER SHALL BE NOTIFIED BEFORE STARTING CONSTRUCTION OF ANY PORTION OF THE PROPOSED CONDUIT WHICH WILL BE AFFECTED BY THE VARIANCE IN THE EXISTING ELEVATIONS.

IF IT IS DETERMINED THAT THE PROPOSED CONDUIT WILL INTERSECT AN EXISTING SEWER OR UNDERGROUND UTILITY IF CONSTRUCTED AS SHOWN ON THE PLAN, THE ENGINEER SHALL BE NOTIFIED BEFORE STARTING CONSTRUCTION OF ANY PORTION OF THE PROPOSED CONDUIT WHICH WOULD BE AFFECTED BY THE INTERFERENCE WITH AN EXISTING FACILITY.

PAYMENT FOR ALL THE OPERATIONS DESCRIBED ABOVE SHALL BE INCLUDED IN THE CONTRACT PRICE FOR THE PERTINENT 603 CONDUIT ITEM.

ITEM 605, AGGREGATE DRAINS

AGGREGATE DRAINS SHALL BE PLACED AT FIFTY (50) FOOT INTERVALS ON EACH SIDE OF NORMAL CROWNED SECTIONS, STAGGERED SO THAT EACH DRAIN IS 25 FEET FROM THE ADJACENT DRAIN ON THE OPPOSITE SIDE AND AT TWENTY-FIVE (25) FOOT INTERVALS ON THE LOW SIDE ONLY OF SUPERELEVATED SECTIONS. AN AGGREGATE DRAIN SHALL BE PLACED AT THE LOW POINT OF EACH SAG VERTICAL CURVE.

UNRECORDED UNTREATED NON-STORMWATER DRAINAGE

FURNISH NO CONTINUANCE FOR ANY UNRECORDED UNTREATED NON-STORMWATER DRAINAGE SUCH AS UNTREATED SEPTIC, UNTREATED WASTEWATER, UNTREATED CURTAIN/GRADIENT DRAINS, AND UNTREATED FOUNDATION FLOOR DRAINS DISTURBED BY THE WORK. PLUG ANY UNRECORDED, UNTREATED, NON-STORMWATER DRAINAGE WITH CLASS C CONCRETE AT THE RIGHT-OF-WAY LINE. PAYMENT FOR PLUGGING SHALL BE INCLUDED IN THE CONTRACT PRICE FOR THE PERTINENT 202 OR 203 ITEM.

REVIEW OF DRAINAGE FACILITIES

BEFORE ANY WORK IS STARTED ON THE PROJECT AND AGAIN BEFORE FINAL ACCEPTANCE BY THE STATE, REPRESENTATIVES OF THE STATE AND CONTRACTOR, ALONG WITH LOCAL REPRESENTATIVES SHALL MAKE AN INSPECTION OF ALL EXISTING SEWERS WHICH ARE TO REMAIN IN SERVICE AND WHICH MAY BE AFFECTED BY THE WORK. THE CONDITION OF THE EXISTING CONDUITS AND THEIR APPURTENANCES SHALL BE DETERMINED FROM FIELD OBSERVATIONS. RECORDS OF THE INSPECTION SHALL BE KEPT IN WRITING BY THE STATE.

ALL NEW CONDUITS, INLETS, CATCH BASINS, AND MANHOLES CONSTRUCTED AS A PART OF THE PROJECT SHALL BE FREE OF ALL FOREIGN MATTER AND IN A CLEAN CONDITION BEFORE THE PROJECT WILL BE ACCEPTED BY THE STATE.

ALL EXISTING SEWERS INSPECTED INITIALLY BY THE ABOVE MENTIONED PARTIES SHALL BE MAINTAINED AND LEFT IN A CONDITION REASONABLY COMPARABLE TO THAT DETERMINED BY THE ORIGINAL INSPECTION. ANY CHANGE IN THE CONDITION RESULTING FROM THE CONTRACTOR'S OPERATIONS SHALL BE CORRECTED BY THE CONTRACTOR TO THE SATISFACTION OF THE ENGINEER.

PAYMENT FOR ALL OPERATIONS DESCRIBED ABOVE SHALL BE INCLUDED IN THE CONTRACT PRICE FOR THE PERTINENT 603 CONDUIT ITEMS.

UNRECORDED ACTIVE SANITARY SEWER CONNECTIONS

FURNISH A CONTINUANCE FOR ALL UNRECORDED ACTIVE SANITARY SEWER CONNECTIONS SUCH AS SANITARY, WASTEWATER, CURTAIN/GRADIENT DRAINS, AND FOUNDATION FLOOR DRAINS DISTURBED BY THE WORK. FURNISH AN UNOBSTRUCTED CONTINUANCE OF THE UNRECORDED ACTIVE SANITARY SEWER CONNECTIONS TO THE SATISFACTIN OF THE ENGINEER. ALL SUCH CONTINUANCE REQUIRES A RIGHT-OF-WAY USE PERMIT. ALL SANITARY AND SANITARY WASTEWATER MAY ALSO REQUIRE A NPDES PERMIT FROM THE OHIO ENVIRONMENTAL PROTECTION AGENCY. REPORT ALL CONTINUANCE TO THE LOCAL HEALTH DEPARTMENT.

THE FOLLOWING CONDUIT TYPES MAY BE USED: 707.42, 707.43, 707.44, 707.45, 707.46, 707.47, 707.51, 707.52 SDR35, 706.01, 706.02, OR 706.08 WITH JOINTS AS PER 706.11 OR 706.12.

THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN INCLUDED IN THE GENERAL SUMMARY FOR USE AS DIRECTED BY THE ENGINEER FOR THE WORK NOTED ABOVE:

611, 8" CONDUIT, TYPE B, FOR SANITARY 100 FT.

611, 6" CONDUIT, TYPE C, FOR SANITARY 100 FT.

ITEM 611 - 10' X 8' CONDUIT, TYPE A, 706.05, AS PER PLAN (DESIGN EARTH COVER = 6 FEET)

SEGMENTAL, PRECAST CONCRETE FOUR SIDED STRUCTURES WHICH ARE BELOW FINISHED GRADE AND WILL NOT BE PAVED DIRECTLY OVER SHALL HAVE ITEM SPECIAL, MEMBRANE WATERPROOFING, SHEET TYPE 2 (SEE PROPOSAL NOTE) APPLIED TO THE TOP SURFACE AND VERTICALLY DOWN THE ENTIRE SIDES FOR ALL PORTIONS OF THE STRUCTURE WHICH SHALL BE IN CONTACT WITH THE BACKFILL.

THE EXTERIOR JOINT GAP ON THE TOP AND SIDES BETWEEN THE PRECAST STRUCTURE SECTIONS SHALL BE FILLED WITH PORTLAND CEMENT MORTAR PRIOR TO INSTALLING THE MEMBRANE WATERPROOFING. JOINT WRAP AS SPECIFIED IN 611.08 AND CONCRETE SEALING AS SPECIFIED IN 611.09 ARE NOT REQUIRED UNDER THE LIMITS OF THE MEMBRANE WATERPROOFING. PAYMENT FOR THE MEMBRANE WATERPROOFING SHALL BE AT THE CONTRACT PRICE BID PER SQUARE YARD FOR PERTINENT ITEM SPECIAL, MEMBRANE WATERPROOFING, SHEET TYPE (SEE PROPOSAL NOTE).

WHEN ITEM SPECIAL, SEALING OF CONCRETE SURFACES (EPOXY) (SEE PROPOSAL NOTE) IS SPECIFIED ON THE HEADWALLS OF A PRECAST CONCRETE STRUCTURE, ANY PRECAST STRUCTURE SECTIONS BEYOND THE LIMIT OF THE MEMBRANE WATERPROOFING SHALL ALSO BE SEALED WITH THE SAME SEALANT. PAYMENT FOR THE SEALING OF THE PRECAST CONCRETE STRUCTURE SURFACES SHALL BE MADE AT THE CONTRACT PRICE BID PER SQUARE YARD FOR ITEM SPECIAL, SEALING OF CONCRETE SURFACES (EPOXY) (SEE PROPOSAL NOTE).

GENERAL NOTES

FRA -44 -13.67

ITEM 614, MAINTAINING TRAFFIC

THE CONTRACTOR SHALL NOTIFY THE ENGINEER AND DIRECTOR OF PUBLIC WORKS, CITY OF PETERSBURG, AT LEAST 48 HOURS IN ADVANCE (EXCLUSIVE OF SATURDAY, SUNDAY OR HOLIDAYS) OF HIS INTENT TO DIVERT TRAFFIC AND TWO WEEKS IN ADVANCE OF A DETOUR.

NO CHANGE IN TRAFFIC PATTERNS SHALL TAKE PLACE DURING PEAK HOURS, 6:00 A.M. TO 9:00 A.M. AND 3:00 P.M. TO 6:00 P.M. MONDAY THROUGH FRIDAY.

THE CONTRACTOR SHALL NOTIFY CONRAIL (PHONE: 215-596-2923) AND THE ENGINEER AT LEAST ONE WEEK IN ADVANCE OF HIS INTENT TO CLOSE CONRAIL TRACKS TO TRAFFIC FOR THE REMOVAL OF PORTIONS OF EXISTING BRIDGE OVER AND/OR NEAR THE TRACKS. THE TRACK CLOSURES SHALL BE LIMITED TO SATURDAY, SUNDAY AND/OR MONDAY.

ACCESS TO THE PARKING LOT ON BEECHMONT COURT (EAST OF CONRAIL TRACKS) SHALL BE MAINTAINED AT ALL TIMES AND OTHER LOCAL TRAFFIC SHALL BE MAINTAINED AS PER CMS 614.02(A).

S.R. 86 - TWO LANE, TWO WAY TRAFFIC SHALL BE MAINTAINED DURING PEAK HOURS AND AT ALL OTHER TIMES EXCEPT AS FOLLOWS:

ONE LANE, TWO WAY TRAFFIC (USING STANDARD DWG. MT-97.10) WILL BE PERMITTED FOR MINIMUM PERIODS CONSISTENT WITH REQUIREMENTS OF THE SPECIFICATIONS FOR COMPLETED ASPHALT COURSES AND WHEN NECESSARY FOR THE CONTRACTOR'S EQUIPMENT TO OCCUPY THE PAVEMENT FOR A SHORT TIME.

S.R. 86 MAY BE CLOSED TO TRAFFIC UNDER CONDITIONS STATED IN THE SEQUENCE OF CONSTRUCTION.

EASTERN AVENUE AND BEECHMONT CIRCLE MAY BE CLOSED FOR SHORT DURATIONS (15 MINUTES) DURING BRIDGE DEMOLITION OR BRIDGE BEAM ERECTION. TRAFFIC BACKUP SHALL BE CLEARED AFTER EACH CLOSURE AND ALLOWED TO PASS FREELY WITH NO RESTRICTION (ONE LANE IN EACH DIRECTION FOR 10 MINUTES BEFORE ANOTHER CLOSURE IS MADE. TWO LANE, TWO WAY TRAFFIC SHALL BE MAINTAINED DURING PEAK HOURS NOTED ABOVE.

RAMP C AND E MAY BE CLOSED AS PER THE SEQUENCE OF CONSTRUCTION; OTHERWISE, TRAFFIC SHALL BE MAINTAINED ON EXISTING, PAVEMENT FOR MAINTAINING TRAFFIC OR PROPOSED PAVEMENT BASE COURSES.

THE FINAL SURFACE AND INTERMEDIATE PAVEMENT COURSES SHALL BE COMPLETED TO THE EXTENT POSSIBLE DURING THE "FINAL DETOUR" PHASE. THE REMAINING WORK SHALL BE COMPLETED AFTER THE "FINAL DETOUR" PHASE WHILE MAINTAINING TRAFFIC.

BEECHMONT COURT SHALL BE OPEN AT ALL TIMES EXCEPT THAT ACCESS TO #3753 BEECHMONT COURT MAY BE CUT OFF CUT OFF WHEN THE DRIVE TO BEECHMONT CIRCLE IS COMPLETED. ACCESS TO #3755, #3711 BEECHMONT COURT AND #4747 EASTERN AVENUE SHALL BE MAINTAINED AT ALL TIMES.

THE CONTRACTOR SHALL MAINTAIN PEDESTRIAN TRAFFIC THROUGHOUT THE PROJECT CONSTRUCTION FROM BEACHMONT AVENUE/CHURCH PLACE INTERSECTION TO EASTERN AVENUE BY KEEPING THE EXISTING STAIRS LOCATED IN THE NORTHEAST QUADRANT OF THE INTERSECTION OPEN FOR THE DURATION OF THE "INITIAL DETOUR PHASE" AND "PHASE I". THE EXISTING STAIRS SHALL REMAIN OPEN UNTIL PEDESTRIAN ACCESS IS PROVIDED BY OPENING THE PROPOSED STAIRS LOCATED IN THE SOUTHEAST QUADRANT AND CONSTRUCTED DURING PHASE I FOR PEDESTRIAN USE DURING "PHASE II" AND THE "FINAL DETOUR" PHASE.

ALL WORK AND TRAFFIC CONTROL DEVICES SHALL BE IN ACCORDANCE WITH CMS 614 AND OTHER APPLICABLE PORTIONS OF THE SPECIFICATIONS, AS WELL AS THE OHIO MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES. PAYMENT FOR ALL LABOR, EQUIPMENT AND MATERIALS SHALL BE INCLUDED IN THE LUMP SUM CONTRACT PRICE FOR ITEM 614, MAINTAINING TRAFFIC, UNLESS SEPARATELY ITEMIZED IN THE PLAN.

SEQUENCE OF CONSTRUCTION

INITIAL DETOUR PHASE

PREPARE TO CLOSE S.R. 86 TO TRAFFIC BY ERECTING TRAFFIC CONTROL (SEE SHEET 32 AND 33) AND COORDINATING THE DETOUR WITH THE CITY OF PETERSBURG. AT THE SAME TIME, SHORE OR BRACE PORTIONS OF THE EXISTING BRIDGE THAT WILL BE USED TO MAINTAIN TRAFFIC. PERFORM ANY OTHER WORK THAT CAN REDUCE THE TIME REQUIRED TO DETOUR TRAFFIC. SEE SHEET NO. 31 FOR DETOUR MAP.

WHEN CITY OF PETERSBURG FORCES HAVE COMPLETED THE DETOUR SIGNING OUTSIDE THE PROJECT AREA AND THE CONTRACTOR HAS COMPLETED ALL DETOUR SIGNING, CLOSURE SIGNING AND BARRIER PLACEMENT WITHIN THE PROJECT AREA, S.R. 86, RAMP C AND RAMP E SHALL BE CLOSED TO TRAFFIC. THIS CLOSURE SHALL BE LIMITED TO 60 CALENDAR DAYS.

WHILE THE HIGHWAY IS CLOSED PRIOR TO "PHASE I", THE FOLLOWING WORK SHALL BE COMPLETED.

- REMOVE THE PLATE GIRDER BRIDGES OVER EASTERN AVENUE AND CONRAIL.

- CONSTRUCT A TEMPORARY BRIDGE AT EACH LOCATION.

- COMPLETE SHORING AND BRACING.

- SAW CUT THE EXISTING CONCRETE BRIDGE SUPERSTRUCTURE AND PIERS AND BEGIN TO REMOVE THE SOUTH PORTION OF THE EXISTING BRIDGE.

- COMPLETE DRIVE TO #3753-55 BEECHMONT COURT.

- CONSTRUCT PAVEMENT FOR MAINTAINING TRAFFIC, AS PER PLAN, AT RAMP C AND E.

- INSTALL THE TEMPORARY TRAFFIC SIGNAL (INCLUDING THE "PREPARE TO STOP WHEN FLASHING" ADVANCE WARNING SIGN AT THE INTERSECTION OF RAMP F/CHURCH AND S.R. 86.

- ERECT TRAFFIC CONTROL AND PORTABLE CONCRETE BARRIER FOR "PHASE I" PRIOR TO OPENING RAMP C. THE SOLID, DOUBLE YELLOW CENTERLINE SHALL BE IN PLACE PRIOR TO PHASE I OPENING TO TRAFFIC.

PHASE I AND II

THE CONTRACTOR IS EXPECTED TO USE ALL MEANS POSSIBLE POSSIBLE INCLUDING, BUT NOT RESTRICTED TO, MULTIPLE SHIFTS, TWENTY-FOUR (24) HOURS PER DAY SCHEDULING SEVEN (7) DAYS A WEEK (SUBJECT TO THE RESTRICTIONS OF SECTION 910.8 OF THE CITY OF PETERSBURG MUNICIPAL CODE GOVERN-

ING NIGHTTIME CONSTRUCTION BETWEEN THE HOURS OF 11:00 P.M. AND 7:00 A.M.), ADDITIONAL CREWS, LIGHTING FOR NIGHT WORK, MULTIPLE MATERIAL SOURCES, MULTIPLE SUBCONTRACTORS, ETC., IN ORDER TO COMPLETE PHASE I AND II WITHIN 120 CALENDAR DAYS. NO TIME EXTENSIONS (SEE PROPOSAL NOTE) OF THIS INTERIM COMPLETION PERIOD WILL BE CONSIDERED. FAILURE TO OPEN THE HIGHWAY TO FOUR LANE TRAFFIC WILL RESULT IN THE ASSESSMENT OF \$15,000.00 LIQUIDATED DAMAGES FOR EACH CALENDAR DAY (INCLUDING WEEKENDS AND HOLIDAYS) BEYOND THE ALLOTTED TIME.

PHASE I

AFTER THE INITIAL PHASE DETOUR WORK IS COMPLETED, RE-OPEN S.R. 86 AND RAMPS C AND E TO TRAFFIC USING THE TEMPORARY BRIDGES AND A PORTION OF THE EXISTING BRIDGE TO MAINTAIN ONE LANE OF TRAFFIC IN EACH DIRECTION.

COVER DETOUR SIGNS FOR RE-USE DURING THE "FINAL DETOUR" PHASE.

COMPLETE CONSTRUCTION OF THE SOUTH ONE HALF OF THE PROPOSED BRIDGE, RETAINING WALLS, TEMPORARY RETAINING WALLS AND STAIRS IN THE SE QUADRANT OF S.R. 86 AND CHURCH PLACE/RAMP F INTERSECTION.

ERECT TRAFFIC CONTROL AND PORTABLE CONCRETE BARRIER, AND ADJUST TEMPORARY TRAFFIC SIGNAL FOR "PHASE II". THE SOLID, DOUBLE YELLOW CENTERLINE SHALL BE IN PLACE PRIOR TO "PHASE II" OPENING TO TRAFFIC.

PHASE II

AFTER PHASE I WORK IS COMPLETED, RELOCATE TRAFFIC ON S.R. 86 AND RAMPS C AND E FOR "PHASE II" USING THE COMPLETED PORTION OF THE NEW STRUCTURE (MAINTAINING ONE LANE OF TRAFFIC IN EACH DIRECTION) AND NEW FULL DEPTH BASE COURSES ON THE RAMPS.

REMOVE THE TEMPORARY BRIDGES AND THE BALANCE OF THE EXISTING BRIDGE. COMPLETE CONSTRUCTION (EXCEPT THE GAP (SECTION OF DECK).

COMPLETE WORK ON BEECHMONT COURT.

SOME ITEMS (I.E. SANITARY) ARE NOT INCLUDED IN THE SEQUENCE, BECAUSE THEY HAVE ONLY MINOR EFFECT ON MAINTAINING TRAFFIC. THE CONTRACTOR MAY COMPLETE THIS WORK WHEN CONVENIENT DURING THE SEQUENCE OF CONSTRUCTION.

FINAL DETOUR PHASE

UNCOVER DETOUR SIGNS, SET UP CLOSURE SIGNING AND PLACE BARRIER TO CLOSE S.R. 86 AND RAMP C TO TRAFFIC. COORDINATE THE CLOSURE WITH THE CITY OF PETERSBURG, AS BEFORE. SEE SHEET 31 FOR DETOUR MAP.

WHILE THE HIGHWAY IS CLOSED, THE FOLLOWING WORK SHALL BE CONSTRUCTED:

- CLOSE THE REMAINING GAP IN THE DECK NOT COMPLETED IN "PHASE I AND II".

- COMPLETE THE PLACEMENT OF FULL DEPTH PAVEMENT BASE COURSES.

REMOVE TRAFFIC SIGNAL FOR MAINTAINING TRAFFIC.

THIS CLOSURE WILL BE LIMITED TO FIVE DAYS, TWO OF WHICH SHALL BE SATURDAY AND SUNDAY.

FAILURE TO RE-OPEN ON TIME WILL RESULT IN THE ASSESSMENT OF \$25,000.00 LIQUIDATED DAMAGES FOR EACH CALENDAR DAY (INCLUDING WEEKENDS AND HOLIDAYS) BEYOND THE ALLOTTED TIME.

PRIOR TO OPENING THE PROJECT TO TRAFFIC, THE SOLID, DOUBLE YELLOW CENTERLINE SHALL BE IN PLACE AND MAINTAINED DURING SURFACE AND INTERMEDIATE PAVEMENT COURSE PLACEMENT OPERATIONS NOT COMPLETED IN THE "FINAL DETOUR" PHASE.

AFTER THE "FINAL DETOUR" PHASE, IT MAY BE NECESSARY TO REDUCE THE NUMBER OF LANES TO LESS THAN FOUR IN ORDER TO COMPLETE THE PROJECT. THIS WILL BE ACCEPTABLE BUT ONLY DURING ACTUAL CONTRACTOR WORKING HOURS WITH TRAFFIC CONTROL PER APPROPRIATE STANDARD DRAWINGS. NO REDUCTION IN THE NUMBER OF THE LANES SHALL BE PERMITTED DURING PEAK HOURS, THAT BEING FROM 6:00 A.M. TO 9:00 A.M. AND FROM 3:00 P.M. TO 6:00 P.M.

MAINTENANCE OF TRAFFIC GENERAL NOTES

FAY-86-7.39

SEQUENCE OF CONSTRUCTION

IT IS THE INTENT OF THE FOLLOWING SEQUENCE OF CONSTRUCTION TO PROVIDE A WORK AREA FOR THE CONTRACTOR WHILE ALSO MAINTAINING TRAFFIC IN A MANNER WHICH IS SAFE FOR THE TRAVELING PUBLIC; THEREFORE, ALL PHASES SHALL HAVE STRICT ADHERENCE.

ALL TEMPORARY OR PERMANENT PAVEMENT MARKINGS SHALL BE IN PLACE BEFORE ANY PAVEMENT IS OPENED TO TRAFFIC.

PHASE ONE

THE CONTRACTOR SHALL REPLACE THE OUTSIDE BERM WITH AN 8' SHOULDER IN THE DESIGNATED AREAS WITH TEMPORARY PAVEMENT USING A ONE LANE CLOSURE PER MT-95.30. LANE CLOSURE PER MT-95.30.

AREAS OF SHOULDER REPLACEMENT:

| EASTBOUND | WESTBOUND |
|---------------------|---------------------|
| 50+49 to 51+28.25 | 1833+00 to 8+86 |
| 55+81.25 to 58+20 | 48+90 to 51+28.25 |
| 116+23 to 128+26 | 55+81.25 to 60+36 |
| 150+12 to 160+10 | 72+48 to 88+20.5 |
| 167+67 to 175+76.71 | 95+78 to 102+82 |
| 177+35.21 to 183+56 | 112+72 TO 126+26 |
| | 136+82 to 144+13 |
| | 172+63 to 175+76.71 |
| | 177+35.21 to 180+55 |

AFTER THE SHOULDER REPLACEMENT WORK IS COMPLETED, THE CONTRACTOR SHALL THEN PERFORM THE JOINT REPAIRS IN THE FOLLOWING AREAS:

EASTBOUND AREA

| | |
|---|------------------------------|
| A | STA. 147+97 TO STA. 150+05 |
| B | STA. 113+12 TO STA. 115+94 |
| C | STA. 58+26 TO STA. 63+00 |
| D | STA. 1828+26 TO STA. 1832+61 |

WESTBOUND AREA

| | |
|---|----------------------------|
| E | STA. 103+30 TO STA. 107+08 |
| F | STA. 109+40 TO STA. 112+44 |
| G | STA. 129+43 TO STA. 136+63 |
| H | STA. 144+25 TO STA. 147+82 |

THE JOINT REPAIRS SHALL BE PERFORMED IN ALPHABETICAL ORDER ON EACH SIDE AND THE PAVEMENT WILL BE OPEN TO TRAFFIC AS SPECIFIED IN THE PLAN NOTE.

FOR ADDITIONAL PHASE I DETAILS AND QUANTITIES SEE SHEETS 22-23.

PHASE TWO

THE CONTRACTOR SHALL PERFORM THE WORK ON THE INSIDE LANES, WHICH SHALL INCLUDE THE JOINT REPAIR, FULL-DEPTH PAVEMENT, BERM REPLACEMENT, AND BRIDGE REHABILITATION. THE JOINT REPAIRS SHALL BE DONE PRIOR TO THE BERM REPLACEMENT. TRAFFIC SHALL BE MAINTAINED DURING THIS PHASE PER THE DETAILS SHOWN ON SHEETS 24 THRU 37, EXCEPT THAT

CORES WILL BE TAKEN DURING THIS PHASE WHICH WILL REQUIRE THE CLOSING OF BOTH LANES FOR A BRIEF PERIOD. ODOT WILL PROVIDE TRAFFIC MAINTENANCE FOR THE CORING PRO-

PHASE THREE

THE CONTRACTOR SHALL PERFORM THE WORK ON THE OUTSIDE LANES, WHICH SHALL INCLUDE THE JOINT REPAIR, FULL-DEPTH PAVEMENT, BERM REPLACEMENT, AND BRIDGE REHABILITATION. THE JOINT REPAIRS SHALL BE DONE PRIOR TO THE BERM REPLACEMENT. TRAFFIC MAINTENANCE DETAILS FOR THIS PHASE ARE SHOWN ON SHEETS 38 THRU 52.

PHASE FOUR

THE CONTRACTOR SHALL GRIND AND SEAL THE PAVEMENT MAINTAINING TRAFFIC BY USE OF A ONE-LANE CLOSURE PER STANDARD DRAWING MT-95.30. THIS WORK SHALL BE PERFORMED ON BOTH LANES AND IN BOTH DIRECTIONS.

BRIDGES

WEST RIVER ROAD AND VERMILION ROAD BRIDGES WILL BE CONSTRUCTED PART-WIDTH USING A TEMPORARY SIGNAL INSTALLATION TO MAINTAIN ONE LANE, TWO-WAY TRAFFIC. DETAILS FOR MAINTAINING TRAFFIC AT THESE BRIDGES ARE SHOWN ON SHEETS 53 AND 54. SUNNYSIDE ROAD AND CLAUS ROAD BRIDGES MAY BE CLOSED FOR A MAXIMUM OF 30 DAYS EACH. BUT THEY SHALL NOT BE CLOSED AT THE SAME TIME. THE DETOUR PLAN FOR THESE BRIDGES IS SHOWN ON SHEETS 19 AND 20. DETAILS FOR THE VERMILION INTERCHANGE BRIDGE CLOSURE ARE SHOWN ON SHEET 21.

SIDE ROAD STRUCTURES OVER FREEWAY

FOUR LANE, TWO WAY TRAFFIC ON THE FREEWAY SHALL BE MAINTAINED AT ALL TIMES DURING THE REHABILITATION OF THE EXISTING STRUCTURES OVER THE FREEWAY, EXCEPT AS FOLLOWS:

1. DURING THE RETROFITTING OF THE EXISTING OVERHEAD PARAPETS.
2. UNLESS OTHERWISE SHOWN IN THE PLAN.

A SAFETY NET OR PLATFORM SHALL BE REQUIRED TO PROTECT TO THE TRAVEL LANES OF THE FREEWAY DURING RETROFITTING OF EXISTING CONCRETE PARAPETS. THE DESIGN OF THE NET OR PLATFORM SHALL CONFORM WITH OSHA REQUIREMENTS, SHALL HAVE APPROVAL FROM THE ODOT OFFICE OF STRUCTURAL ENGINEERING, AND SHALL REMAIN IN PLACE UNTIL WORK HAS BEEN COMPLETED. THE EXISTING VERTICAL CLEARANCE OVER THE FREEWAY SHALL BE MAINTAINED AT ALL TIMES.

IN THE EVENT A LANE RESTRICTION ON THE FREEWAY IS NECESSARY, THE METHOD OF INSTALLATION AND DESIGN OF TEMPORARY AND DESIGN OF TEMPORARY LANE CLOSURE SHALL BE IN ACCORDANCE WITH STANDARD DRAWING MT-95.30. COST FOR THE ABOVE WORK SHALL BE CONSIDERED INCIDENTAL AND SHALL BE INCLUDED IN ITEM 614, MAINTAINING TRAFFIC.

FREEWAY STRUCTURES OVER SIDE ROADS

TWO LANE, TWO WAY TRAFFIC ON SIDE ROADS SHALL BE MAINTAINED AT ALL TIMES DURING REPLACEMENT OF BEARINGS AND REHABILITATION OF MAINLINE BRIDGES, EXCEPT DURING THE FOLLOWING OPERATIONS:

- 1.) DEMOLITION OF THE EXISTING BRIDGE PARAPETS.
- 2.) CONSTRUCTION OF THE PROPOSED PARAPET OVER THE LOCAL ROAD OR STATE ROUTE WHERE THE ENGINEER BELIEVES TEMPORARY CLOSURE OF A TRAFFIC LANE IS WARRANTED.

A SAFETY NET OR PLATFORM SHALL BE REQUIRED TO PROTECT THE UNDERPASS ROADWAY DURING REMOVAL OF EXISTING AND CONSTRUCTION OF NEW CONCRETE PARAPETS. THE DESIGN OF THE NET OR PLATFORM SHALL CONFORM WITH OSHA REQUIREMENTS, SHALL HAVE APPROVAL FROM THE ODOT OFFICE OF STRUCTURAL ENGINEERING, AND SHALL REMAIN IN PLACE UNTIL WORK HAS BEEN COMPLETED. THE EXISTING VERTICAL CLEARANCE

OVER THE UNDERPASS ROADWAY SHALL BE MAINTAINED AT ALL TIMES. IN THE EVENT A LANE RESTRICTION IS NECESSARY, THE METHOD OF INSTALLATION AND DESIGN OF THE TEMPORARY LANE CLOSURE SHALL CONFORM TO STANDARD DRAWINGS MT-95.30 OR MT-97.10. COST FOR THE ABOVE WORK SHALL BE CONSIDERED INCIDENTAL AND INCLUDED IN THE LUMP SUM PRICE BID FOR ITEM 614 MAINTAINING TRAFFIC.

PAVEMENT FOR MAINTAINING TRAFFIC, CLASS A, AS PER PLAN

THE PAVEMENT BUILDUP SHALL BE:

- 6" - ITEM 301, ASPHALT CONCRETE BASE, PG64-22
- 4" - ITEM 304, AGGREGATE BASE

PAYMENT SHALL INCLUDE ANY ADDITIONAL COST OF ITEM 203, EXCAVATION TO PLACE THE ITEM 301 OR ITEM 304. THE PAVEMENT FOR MAINTAINING TRAFFIC SHALL BE REMOVED UNDER ITEM 203.

PAVEMENT FOR MAINTAINING TRAFFIC, CLASS B, AS PER PLAN

THE PAVEMENT BUILDUP SHALL BE:

- 6" - ITEM 301, ASPHALT CONCRETE BASE, PG64-22
- 4" - ITEM 304, AGGREGATE BASE.

PAYMENT SHALL INCLUDE ANY ADDITIONAL COST OF ITEM 203, EXCAVATION TO PLACE THE ITEM 301 OR ITEM 304. THE SUBGRADE SHALL BE COMPACTED TO A DEPTH OF 12" ACCORDING TO THE CONSTRUCTION AND MATERIALS SPECIFICATION, SECTION 204.03 AND PAYMENT FOR SUCH WORK SHALL BE INCLUDED IN THE UNIT PRICE BID FOR ITEM 204, SUBGRADE COMPACTION (SEE SHEETS 148 THRU 151 FOR QUANTITIES). THIS PAVEMENT SHALL REMAIN IN PLACE.

NOTICE OF CLOSURE SIGNS

THESE SIGNS SHALL BE ERECTED BY THE CONTRACTOR AT LEAST ONE WEEK IN ADVANCE OF THE SCHEDULED ROAD OR RAMP CLOSURE. THE SIGNS SHALL BE ERECTED ON THE RIGHT HAND BESIDE OF THE ROAD/RAMP FACING TRAFFIC AND SHALL BE LOCATED IN THE FIELD SO AS NOT TO INTERFERE WITH ANY

PERMANENT SIGNS. THE SIGNS SHOULD BE ERECTED ALONG ROADWAYS AT THE POINT OF CLOSURE. THE SIGNS MAY BE ANYWHERE ALONG RAMPS WHERE THEY ARE VISIBLE TO THE MOTORIST USING THE RAMP, EXCEPT THAT ON ENTRANCE RAMPS, THE SIGNS SHALL BE ERECTED WELL IN ADVANCE OF THE MERGE AREA TO AVOID DISTRACTION TO THE MOTORIST.

PAYMENT FOR THIS WORK SHALL BE INCLUDED IN THE LUMP SUM BID FOR ITEM 614 MAINTAINING TRAFFIC AND SHALL INCLUDE FURNISHING, ERECTING, MAINTAINING AND REMOVING THE SIGNS, INCLUDING SUPPORTS.

WILL BE
CLOSED
FOR _____ DAYS
OHIO DEPT. OF TRANSPORTATION


W20-H14-60

MAINTENANCE OF TRAFFIC GENERAL NOTES


WOO-96-16.21




I:\pr\35\ids\SamplePlans\Future Revision\Draft_0908\1306_DGN\1306_3.dgn 30-SEP-2008 1:07PM mwawski




For Maintenance of Traffic Notes, see Sheet 7.




DETOUR SIGNING



| ESTIMATED QUANTITIES | | | | | | | | |
|-------------------------------|--------------------|------|-----------------------------|----------------------------|------------------------|---|--|--------------------------------|
| REF No. | Station to Station | Side | 614 | | | | 622 | |
| | | | WORK ZONE IMPACT ATTENUATOR | BARRIER REFLECTOR, TYPE B2 | OBJECT MARKER, TWO WAY | WORK ZONE CENTER LINE, CLASS I, 740.06, TYPE I (DOUBLE SOLID) | WORK ZONE EDGE LINE, CLASS I, 704.06, TYPE I (WHITE) | PORTABLE CONCRETE BARRIER, 32" |
| | | | EACH | EACH | EACH | MILE | MILE | FT |
| CL-1 | 59+00 to 66+89 | Lt. | | | | 0.15 | | |
| EL-1 | 59+00 to 66+89 | Lt. | | | | | 0.15 | |
| EL-2 | 59+00 to 66+89 | Rt. | | | | | 0.15 | |
| PCB-1 | 59+00 to 66+14 | Lt. | | 15 | 15 | | 714 | |
| IA-1 | 66+14 to 66+39 | Lt. | 1 | | | | | |
| TOTALS CARRIED TO SUB-SUMMARY | | | 1 | 15 | 15 | 0.15 | 0.30 | 714 |




SECTION A-A



LEGEND

- 32" Portable Concrete Barrier
- Area to be Constructed
- Pavement for Maintaining Traffic, As Per Plan (Constructed in Phase One)
- Direction of Traffic







CALCULATED
DAN
CHECKED
DEK

MAINTENANCE OF TRAFFIC PHASE THREE
STA. 54+00 TO STA. 59+00

SCI-138-11.44



- Legend**
- 32" Portable Concrete Barrier
 - Area to be Constructed
 - Drums Spaced at 10' Center to Center

ESTIMATED QUANTITIES

| REF No. | Station to Station | Side | 614 | | | | | 622 | |
|-------------------------------------|------------------------------------|------|-----------------------------|----------------------------|------------------------|---|--|--|--------------------------------|
| | | | WORK ZONE IMPACT ATTENUATOR | BARRIER REFLECTOR, TYPE B2 | OBJECT MARKER, TWO WAY | WORK ZONE CENTER LINE, CLASS 1, 740.06, TYPE I (DOUBLE SOLID) | WORK ZONE EDGE LINE, CLASS 1, 704.06, TYPE I (WHITE) | WORK ZONE STOP LINE, CLASS 1, 740.06, TYPE I | PORTABLE CONCRETE BARRIER, 32" |
| | | | EACH | EACH | EACH | MILE | MILE | FT | FT |
| CL-1 | 54+00 to 57+79 | Lt. | | | | 0.072 | | | |
| CL-2 | 58+85 to 59+00 | Lt. | | | | 0.003 | | | |
| CL-3 | 7+45 Kipper Rd. to 9+90 Kipper Rd. | Rt. | | | | 0.046 | | | |
| EL-1 | 54+00 to 57+95 | Lt. | | | | | 0.075 | | |
| EL-2 | 54+00 to 57+79 | Rt. | | | | | 0.072 | | |
| EL-3 | 57+79 to 7+45 Kipper Rd. | Rt. | | | | | 0.051 | | |
| EL-4 | 7+45 Kipper Rd. to 58+50 | Rt. | | | | | 0.049 | | |
| EL-5 | 58+85 to 59+00 | Lt. | | | | | 0.003 | | |
| EL-6 | 58+50 to 59+00 | Rt. | | | | | 0.009 | | |
| SL-1 | 57+79 | Rt. | | | | | | 15 | |
| SL-2 | 9+90 Kipper Rd. | Rt. | | | | | | 18 | |
| SL-3 | 58+85 | Rt. | | | | | | 10 | 50 |
| PCB-1 | 54+00 to 54+50 | Rt. | | 2 | 2 | | | | |
| IA-1 | 54+50 to 54+75 | Rt. | 1 | | | | | | |
| TOTALS CARRIED TO SUBSUMMARY | | | 1 | 2 | 2 | 0.05 | 0.10 | 43 | 50 |





0 20 40
HORIZONTAL SCALE IN FEET

CALCULATED
CAN
CHECKED
DEK

MAINTENANCE OF TRAFFIC PHASE FOUR
STA. 54+00 TO STA. 59+00




SCI-138-11.44

| ESTIMATED QUANTITIES | | | | | | | | | | | | | | | | | | | | |
|------------------------------|--------------------------------------|------|-----------------------------|----------------------------|------------------------|---|--|--|--|-----------------------|----|----|-----|--|--|--|--|--|--|--|
| REF No. | Station to Station | SIDE | 614 | | | | 615 | 622 | | | | | | | | | | | | |
| | | | WORK ZONE IMPACT ATTENUATOR | BARRIER REFLECTOR, TYPE B2 | OBJECT MARKER, TWO WAY | WORK ZONE CENTER LINE, CLASS I, 740.06, TYPE I (DOUBLE SOLID) | WORK ZONE EDGE LINE, CLASS I, 704.06, TYPE I (WHITE) | WORK ZONE STOP LINE, CLASS I, 740.06, TYPE I | PAVEMENT FOR MAINTAINING TRAFFIC, CLASS A, AS PER PLAN | PORTABLE BARRIER, 32" | | | | | | | | | | |
| | | | EACH | EACH | EACH | MILE | MILE | FT | SY | FT | | | | | | | | | | |
| CL-1 | 54+00 to 57+83 | Rt. | | | | 0.07 | | | | | | | | | | | | | | |
| CL-2 | 8+55 Kipper Rd. to 9+70 Kipper Rd. | Rt. | | | | 0.02 | | | | | | | | | | | | | | |
| CL-3 | 10+15 Kipper Rd. to 11+45 Kipper Rd. | Lt. | | | | 0.03 | | | | | | | | | | | | | | |
| CL-4 | 58+75 to 59+00 | Rt. | | | | 0.01 | | | | | | | | | | | | | | |
| EL-1 | 54+00 to 8+55 Kipper Rd | Rt. | | | | | | | | 0.09 | | | | | | | | | | |
| EL-2 | 54+00 to 12+00 Kipper Rd. | Lt. | | | | | | | | 0.12 | | | | | | | | | | |
| EL-3 | 8+55 Kipper Rd. to 59+00 | Rt. | | | | | | | | 0.04 | | | | | | | | | | |
| EL-4 | 11+45 Kipper Rd. to 59+00 | Lt. | | | | | | | | 0.03 | | | | | | | | | | |
| SL-1 | 10+15 Kipper Rd | Lt. | | | | | | | | | 24 | | | | | | | | | |
| SL-2 | 9+70 Kipper Rd. | Rt. | | | | | | | | | 20 | | | | | | | | | |
| PCB-1 | 54+00 to 11+48 Kipper Rd. | Lt. | | 11 | 11 | | | | | | | | 578 | | | | | | | |
| IA-1 | 11+48 Kipper Rd. to 11+73 Kipper Rd. | Lt. | 1 | | | | | | | | | | | | | | | | | |
| TP-1 | 10+50 Kipper Rd. to 11+70 Kipper Rd. | Rt. | | | | | | | | | | 20 | | | | | | | | |
| TOTALS CARRIED TO SUBSUMMARY | | | 1 | 11 | 11 | 0.13 | 0.28 | 44 | 20 | 578 | | | | | | | | | | |



SECTION A-A



- LEGEND**
- 32" Portable Barrier
 - Area to be Constructed
 - Pavement for Maintaining Traffic, Class A, As Per Plan
 - Direction of Traffic



LEGEND

- 32" Portable Barrier
- Area to be Constructed
- Direction of Traffic

| REF No. | STATION TO STATION | SIDE | 614 | | | | 622 | |
|-------------------------------------|--------------------|------|--------------------------------------|----------------------------|------------------------|---|--|-----------------------|
| | | | REMOVE AND REPLACE IMPACT ATTENUATOR | BARRIER REFLECTOR, TYPE B2 | OBJECT MARKER, TWO WAY | WORK ZONE CENTER LINE, CLASS I, 740.06, TYPE 1 (DOUBLE SOLID) | WORK ZONE EDGE LINE, CLASS I, 704.06, TYPE 1 (WHITE) | PORTABLE BARRIER, 32" |
| | | | EACH | EACH | EACH | MILE | MILE | FT |
| CL-1 | 59+00 to 66+10 | Rt. | | | | 0.13 | | |
| EL-1 | 59+00 to 65+70 | Rt. | | | | | 0.13 | |
| EL-2 | 59+00 to 66+24 | Lt. | | | | | 0.14 | |
| PB-1 | 59+00 to 65+38 | Lt. | | 14 | 14 | | 638 | |
| IA-1 | 65+38 to 65+63 | Lt. | 1 | | | | | |
| TOTALS CARRIED TO SUBSUMMARY | | | 1 | 14 | 14 | 0.13 | 0.27 | 638 |





CALCULATED TD CHECKED NEM
HORIZONTAL SCALE IN FEET
0 25 50 100

TEMPORARY ROAD PLAN AND PROFILE


LIC-599-8.54

CURVE DATA
P.I. Sta. 4+50.00, $\text{\textcircled{C}}$ Temp. Rd.
 $\Delta = 4^\circ 42' 00''$ LT
 $D_C = 4^\circ 42' 00''$
 $R = 1218.28'$
 $T = 50.00'$
 $L = 100.00'$
 $E = 1.03'$
 $e_{max} = 0.040$


CURVE DATA
P.I. Sta. 5+83.56, $\text{\textcircled{C}}$ Temp. Rd.
 $\Delta = 27^\circ 03' 36''$ LT
 $D_C = 16^\circ 30' 00''$
 $R = 347.25'$
 $T = 83.56'$
 $L = 164.00'$
 $E = 9.91'$
 $e_{max} = 0.040$

CURVE DATA
P.I. Sta. 7+48.31, $\text{\textcircled{C}}$ Temp. Rd.
 $\Delta = 27^\circ 17' 40''$ RT
 $D_C = 16^\circ 30' 00''$
 $R = 347.25'$
 $T = 84.31'$
 $L = 165.42'$
 $E = 10.09'$
 $e_{max} = 0.040$


CURVE DATA
P.I. Sta. 12+59.19, $\text{\textcircled{C}}$ Temp. Rd.
 $\Delta = 09^\circ 16' 18''$ RT
 $D_C = 09^\circ 15' 00''$
 $R = 619.41'$
 $T = 50.23'$
 $L = 100.23'$
 $E = 2.03'$
 $e_{max} = 0.040$




- NOTES:**
- FOR TEMPORARY ROAD TYPICAL SECTIONS AND PAVEMENT EDGE ELEVATIONS, SEE SHEET 100.
 - FOR DRIVEWAY AND DRAINAGE DETAILS, SEE S.R. 599 PLAN & PROFILE, SHEET 38.
- PAVEMENT FOR MAINTAINING TRAFFIC, CLASS A
 - PHASE IV CONSTRUCTION
 - DIRECTION OF TRAFFIC




| ROAD FOR MAINTAINING TRAFFIC PAVEMENT EDGE ELEVATIONS | | |
|--|---------|--------------------|
| 11' LEFT | STATION | 11' RIGHT |
| MEET EXISTING | 5+65 | MEET EXISTING |
| 846.84 | 5+75 | 847.72 |
| 845.60 | 6+00 | 846.23 |
| 844.52 | 6+25 | 844.90 |
| 843.57 | 6+50 | 842.71 |
| 842.75 | 6+75 | 842.67 |
| 842.06 | 7+00 | 841.78 |
| 841.51 | 7+25 | 841.05 |
| 841.10 | 7+50 | 840.45 |
| 840.84 | 7+75 | 839.99 |
| 840.54 | 8+00 | 839.85 |
| 840.36 | 8+25 | 839.88 |
| 840.32 | 8+50 | 840.02 |
| 840.42 | 8+75 | 840.23 |
| 840.66 | 9+00 | 840.58 |
| 841.07 | 9+25 | 841.07 |
| 841.70 | 9+50 | 841.70 |
| 842.48 | 9+75 | 842.48 |
| 843.40 | 10+00 | 843.40 |
| 844.46 | 10+25 | 844.46 |
| 845.66 | 10+50 | 845.66 |
| 847.01 | 10+75 | 847.01 |
| 848.49 | 11+00 | 848.49 |
| 850.08 | 11+25 | 850.08 |
| 851.58 | 11+50 | 851.54 |
| 852.99 | 11+75 | 852.84 |
| 854.21 | 12+00 | 853.98 |
| 855.25 | 12+25 | 854.95 |
| 856.10 | 12+50 | 855.76 |
| 856.75 | 12+75 | 856.41 |
| 857.13 | 13+00 | 857.01 |
| 857.33 | 13+25 | 857.45 |
| MEET TAPER SECTION | 13+50 | MEET TAPER SECTION |




SUPERELEVATED SECTION
 STA. 5+65.00 TO STA. 6+64.00
 STA. 6+64.00 TO STA. 9+20.00 (OPPOSITE HAND)
 STA. 11+40.00 TO STA. 13+50.00




DETAIL "A"



DETAIL "B"



NORMAL SECTION
 STA. 9+20.00 TO STA. 11+40.00




TAPER SECTION
 STA. 13+50.00 TO STA. 18+10.24

TEMPORARY ROAD
TYPICAL SECTIONS AND ELEVATIONS



LIC-599-8.54

NOTE: FOR PLAN & PROFILE OF ROAD FOR MAINTAINING TRAFFIC, SEE SHEET 99.



See sheet 18 for Guardrail and Portable Barrier (PB) Connection Details.
See sheet 19 for MOT quantities.
See sheet 67 for Stage Construction Details.

Note:
For placement of advance warning signs see Standard Construction Drawing MT-96.11.



Legend

32" Concrete Barrier

Area to be constructed

| REF NO. | STORM SEWER PROFILE SHEET NO. | STATION | | SIDE | 202 | | 601 | 602 | 611 | | | | | | | | | | 605 | 670 | SP 1307-2 | | |
|---|-------------------------------|---------|--------|-------|-----------------------------|---------------------|---|------------------|--------------------|---------------------|---------------------|---------------------|---------------------|-----------------------------|--------------------|---------------------|--------------------|---------------------|-----------------------------|--------------------------|----------------------|--|--|
| | | | | | PIPE REMOVED, 24" AND UNDER | CATCH BASIN REMOVED | ROCK CHANNEL PROTECTION, TYPE B WITH FILTER | CONCRETE MASONRY | 6" CONDUIT, TYPE F | 12" CONDUIT, TYPE B | 15" CONDUIT, TYPE C | 18" CONDUIT, TYPE B | 24" CONDUIT, TYPE B | 42" CONDUIT, TYPE B, 706.02 | CATCH BASIN, NO. 4 | CATCH BASIN, NO. 4A | CATCH BASIN, NO. 5 | CATCH BASIN, NO. 5A | 4" SHALLOW PIPE UNDERDRAINS | DITCH EROSION PROTECTION | DATE: JULY 2016 | | |
| | | | | | | | | | | | | | | | | | | | | | BENDS AND BRANCHES | | |
| | | | | | | | | | | | | | | | | | | | | | FOR INFORMATION ONLY | | |
| FT | EACH | CY | CY | FT | FT | FT | FT | FT | FT | FT | EACH | EACH | EACH | EACH | FT | SY | 6"X6" TEE | 6"X6" CROSS | 6"X90° BEND | | | | |
| FROM | TO | | | | | | | | | | | | | | | | EACH | EACH | EACH | | | | |
| D1 | 209 & 210 | 360+00 | 364+00 | ℄ | | | | | | 400 | | | | 1 | | | | | 125 | | | | |
| D2 | 210 | | 364+00 | RT | | | | | | 200 | | | | | | | | | 250 | | | | |
| D3 | 154 | | 363+60 | LT&RT | | | | | 160 | | | | | | | | | | | | | | |
| D4 | 154 | | 364+00 | LT | | | | | | | | | | | | | | | 125 | | | | |
| D5 | 154 | | 364+00 | ℄ | | | | | | | | | | | | | | | | | | | |
| D6 | 154 | | 364+00 | RT | | | 6 | | | | | | | | | | | | | | | | |
| D7 | 154 | | 364+00 | LT | | | | | | | | | | | | | | | | | | | |
| D8 | 210 | 364+00 | 365+00 | RT | | | | | | 100 | | | | | | | 1 | | 197 | | | | |
| D9 | 210 | 364+00 | 365+35 | ℄ | | | | | | | | | | | | | | | 226 | | | | |
| D10 | 210 | 364+00 | 365+75 | LT | | | | | | 175 | | | | | | | 1 | | 259 | | | | |
| D11 | 157 | | 368+20 | ℄ | | | | | | | | | 64 | | | | | | | | | | |
| D12 | 157 | | 368+20 | LT | | | | | | | | | 68 | | | | | | | | | | |
| D13 | 157 | | 368+20 | RT | | | 1 | 0.4 | | | | | | | | | | | | | | | |
| D14 | 212 | 368+20 | 371+00 | LT | | | | | | | | | | | | | | | 125 | | | | |
| D15 | 212 | 368+20 | 371+00 | ℄ | | | | | | 280 | | | | | | | | | 125 | | | | |
| D16 | 212 | 368+20 | 371+00 | RT | | | | | | 280 | | | | | | | | | 125 | | | | |
| R1 | | | 368+00 | RT | 20 | 1 | | | | | | | | | | | | | | | | | |
| U1 | | 359+90 | 363+97 | RT | | | | | | 20 | | | | | | | | | 407 | | 1 | | |
| U2 | | 359+90 | 363+97 | LT | | | | | | 20 | | | | | | | | | 407 | | 1 | | |
| U3 | | 359+90 | 363+97 | LT | | | | | | 22 | | | | | | | | | 814 | 1 | 1 | | |
| U4 | | 359+90 | 363+97 | RT | | | | | | 22 | | | | | | | | | 814 | 1 | 1 | | |
| U5 | | 364+03 | 368+18 | RT | | | | | | 20 | | | | | | | | | 415 | 1 | | | |
| U6 | | 364+03 | 368+18 | RT | | | | | | 22 | | | | | | | | | 830 | 1 | 1 | | |
| U7 | | 364+03 | 368+18 | LT | | | | | | 22 | | | | | | | | | 830 | 1 | 1 | | |
| U8 | | 364+03 | 368+18 | LT | | | | | | 20 | | | | | | | | | 415 | 1 | | | |
| U9 | | 368+22 | 371+00 | LT | | | | | | 22 | | | | | | | | | 556 | 1 | 1 | | |
| U10 | | 368+22 | 371+00 | RT | | | | | | 22 | | | | | | | | | 556 | 1 | 1 | | |
| U11 | | 368+22 | 371+00 | RT | | | | | | 20 | | | | | | | | | 278 | | 1 | | |
| U12 | | 368+22 | 371+00 | LT | | | | | | 20 | | | | | | | | | 278 | | 1 | | |
| U13 | | 371+00 | 373+50 | LT | | | | | | | | | | | | | | | 500 | 2 | | | |
| U14 | | 371+00 | 373+50 | LT | | | | | | | | | | | | | | | 250 | 1 | | | |
| U15 | | 371+00 | 373+50 | RT | | | | | | | | | | | | | | | 500 | 2 | | | |
| U16 | | 371+00 | 373+50 | RT | | | | | | | | | | | | | | | 250 | 1 | | | |
| ALL QUANTITIES FROM PLAN & PROFILE SHEET 81 | | | | | | | | | | | | | | | | | | | | | | | |
| TOTALS CARRIED TO GENERAL SUMMARY | | | | | 20 | 1 | 7 | 0.4 | 252 | 160 | 1850 | 68 | 141 | 144 | 4 | 1 | 7 | 2 | 8100 | 1557 | | | |

CALCULATED: MTG
 CHECKED: CJM
ESTIMATED QUANTITIES
LUC-76-31.48
 82
 488

SHEET NUMBER

OFFICE CALCULCS 196

ITEM ITEM EXT. GRAND TOTAL UNIT DESCRIPTION

FIG. 1307-3(b)
DATE: JANUARY 2019

SEE SHEET NO. CALCULATED JKP CHECKED FGW

PAVEMENT

| | | | | | | | | | | | | | | | |
|-------|--|--|--|--|--|--|--|--|--|-----|-------|-------|-----|---|----|
| 312 | | | | | | | | | | 251 | 01000 | 312 | SY | PARTIAL DEPTH PAVEMENT REPAIR | |
| 4140 | | | | | | | | | | 253 | 01000 | 4140 | SY | PAVEMENT REPAIR | |
| 9005 | | | | | | | | | | 255 | 10011 | 9005 | SY | FULL DEPTH PAVEMENT REMOVAL AND RIGID REPLACEMENT, CLASS QC1P, AS PER PLAN | 16 |
| 2894 | | | | | | | | | | 255 | 10161 | 2894 | SY | FULL DEPTH PAVEMENT REMOVAL AND RIGID REPLACEMENT, CLASS QC MS, AS PER PLAN | 16 |
| 34828 | | | | | | | | | | 255 | 20000 | 34828 | FT | FULL DEPTH PAVEMENT SAWING | |
| 17759 | | | | | | | | | | 304 | 20000 | 17759 | CY | AGGREGATE BASE | |
| 3892 | | | | | | | | | | 305 | 13000 | 3892 | SY | 9" CONCRETE BASE | |
| 127 | | | | | | | | | | 407 | 10000 | 127 | GAL | TACK COAT | |
| 5813 | | | | | | | | | | 408 | 10000 | 5813 | GAL | PRIME COAT | |
| 1029 | | | | | | | | | | 451 | 14001 | 1029 | SY | 9" REINFORCED CONCRETE PAVEMENT, AS PER PLAN | 12 |
| 31690 | | | | | | | | | | 451 | 15001 | 31690 | SY | 10" REINFORCED CONCRETE PAVEMENT, AS PER PLAN | 12 |
| 6783 | | | | | | | | | | 452 | 13001 | 6783 | SY | 9" NON-REINFORCED CONCRETE PAVEMENT, AS PER PLAN | 12 |
| 50342 | | | | | | | | | | 452 | 17001 | 50342 | SY | VARIABLE THICKNESS NON-REINFORCED CONCRETE PAVEMENT, AS PER PLAN | 12 |

WATER WORK

| | | | | | | | | | | | | | | | | |
|--|--|--|--|--|--|--|--|--|--|------|-----|-------|------|------|--|--|
| | | | | | | | | | | 3649 | 638 | 02504 | 3649 | FT | 12" WATER MAIN DUCTILE IRON PIPE ANSI CLASS 53, MECHANICAL JOINTS AND FITTINGS | |
| | | | | | | | | | | 2481 | 638 | 02604 | 2481 | FT | 12" WATER MAIN DUCTILE IRON PIPE ANSI CLASS 53, BOLTLESS-RESTRAINED, JOINTS AND FITTINGS | |
| | | | | | | | | | | 2107 | 638 | 02700 | 2107 | FT | 12" WATER MAIN DUCTILE IRON PIPE ANSI CLASS 55, BALL AND SOCKET JOINTS AND FITTINGS | |
| | | | | | | | | | | 1608 | 638 | 02800 | 1608 | FT | 12" WATER MAIN POLYVINYL CHLORIDE PIPE AND FITTINGS, ASTM SDR 26 | |
| | | | | | | | | | | 1142 | 638 | 02900 | 1142 | FT | 12" WATER MAIN POLYVINYL CHLORIDE PIPE AND FITTINGS, AWWA CLASS 150 | |
| | | | | | | | | | | 438 | 638 | 04800 | 438 | FT | 3/4" COPPER SERVICE BRANCH | |
| | | | | | | | | | | 464 | 638 | 05300 | 464 | FT | 3/4" POLYETHYLENE SERVICE BRANCH | |
| | | | | | | | | | | 212 | 638 | 06704 | 212 | FT | 20" STEEL PIPE ENCASEMENT, OPEN CUT | |
| | | | | | | | | | | 310 | 638 | 07310 | 310 | FT | 24" STEEL PIPE ENCASEMENT, BORED OR JACKED | |
| | | | | | | | | | | 18 | 638 | 08100 | 18 | EACH | 12" GATE VALVE AND VALVE BOX | |
| | | | | | | | | | | 16 | 638 | 09200 | 16 | EACH | 12" CUTTING-IN SLEEVE, VALVE AND VALVE BOX | |
| | | | | | | | | | | 12 | 638 | 09700 | 12 | EACH | 12" X 6" TAPPING SLEEVE, VALVE AND VALVE BOX | |
| | | | | | | | | | | 36 | 638 | 10200 | 36 | EACH | 6" FIRE HYDRANT | |
| | | | | | | | | | | 10 | 638 | 10300 | 10 | EACH | FIRE HYDRANT EXTENDED AND ADJUSTED TO GRADE | |
| | | | | | | | | | | 8 | 638 | 10500 | 8 | EACH | FIRE HYDRANT REMOVED AND RESET | |
| | | | | | | | | | | 8 | 638 | 10600 | 8 | EACH | FIRE HYDRANT AND GATE VALVE REMOVED AND RESET | |
| | | | | | | | | | | 12 | 638 | 10800 | 12 | EACH | VALVE BOX ADJUSTED TO GRADE | |
| | | | | | | | | | | 6 | 638 | 10900 | 6 | EACH | SERVICE BOX ADJUSTED TO GRADE | |
| | | | | | | | | | | 4 | 638 | 11100 | 4 | EACH | METER AND CHAMBER REMOVED AND RESET | |

GENERAL SUMMARY

TRU-99-13.48

| SHEET NUMBER | | | | | | | | | | PARTICIPATION | ITEM | ITEM EXT. | GRAND TOTAL | UNIT | DESCRIPTION | FIG. 1307-3(d) | SEE SHEET NO. | CALCULATED | JKP CHECKED | FGW |
|---|-----|----|------|--|--|--|--|--|----------------|--------------------|------|-----------|-------------|------|---|----------------|---------------|------------|-------------|-----|
| 10 | 18 | 25 | | | | | | | 01/352/OT/HEBR | DATE: JANUARY 2019 | | | | | | | | | | |
| ADDITIVE ALTERNATE 1: SIDEWALK | | | | | | | | | | | | | | | | | | | | |
| 5985 | | | | | | | | | | 5985 | 608 | 10000 | 5985 | SF | 4" CONCRETE WALK | | | | | |
| 126 | | | | | | | | | | 126 | 608 | 52000 | 126 | SF | CURB RAMP | | | | | |
| | 5 | | | | | | | | | 5 | 616 | 10000 | 5 | MGAL | WATER | | | | | |
| | 105 | | | | | | | | | 105 | 659 | 00300 | 105 | CY | TOPSOIL | | | | | |
| | 940 | | | | | | | | | 940 | 659 | 10000 | 940 | SY | SEEDING AND MULCHING | | | | | |
| ADDITIVE ALTERNATE 2: PEDESTRIAN CROSSWALK | | | | | | | | | | | | | | | | | | | | |
| | | | 52 | | | | | | | 52 | 630 | 02100 | 52 | FT | GROUND MOUNTED SUPPORT, NO. 2 POST | | | | | |
| | | | 1 | | | | | | | 1 | 630 | 08600 | 1 | EACH | SIGN POST REFLECTOR | | | | | |
| | | | 27.8 | | | | | | | 27.8 | 630 | 80100 | 27.8 | SF | SIGN, FLAT SHEET | | | | | |
| | | | 2 | | | | | | | 2 | 630 | 84900 | 2 | EACH | REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL | | | | | |
| | | | 2 | | | | | | | 2 | 630 | 86002 | 2 | EACH | REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL | | | | | |
| | | | 2 | | | | | | | 2 | 631 | 92001 | 2 | EACH | SIGN FLASHER ASSEMBLY, AS PER PLAN | | | | | 5 |
| | | | 13 | | | | | | | 13 | 644 | 00500 | 13 | FT | STOP LINE | | | | | |
| | | | 200 | | | | | | | 200 | 644 | 00600 | 200 | FT | CROSSWALK LINE | | | | | |
| INCIDENTALS | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | 614 | 11000 | LS | | MAINTAINING TRAFFIC | | | | | |
| | | | | | | | | | | | 619 | 16010 | 6 | MNTH | FIELD OFFICE, TYPE B | | | | | |
| | | | | | | | | | | | 623 | 10000 | LS | | CONSTRUCTION LAYOUT STAKES AND SURVEYING | | | | | |
| | | | | | | | | | | | 624 | 10000 | LS | | MOBILIZATION | | | | | |

GENERAL SUMMARY

LIC-C.R. 79-0.89

| SHEET NUMBER | | | | PARTICIPATION | | ITEM | ITEM EXT. | GRAND TOTAL | UNIT | DESCRIPTION | SP 1307-5 DATE: JANUARY 2017 | SEE SHEET NO. | CALCULATED JKP | CHECKED FGW |
|--------------|----|--|--|---------------|---------------|------|-----------|-------------|------|-----------------|--|---------------|-------------------|----------------|
| 87 | 96 | | | 01/NHS/PV | 02/SK2/PV/ATB | | | | | | | | | |
| | | | | | | | | | | TRAFFIC CONTROL | | | | |
| | | | | | | 161 | 621 | 00100 | 161 | EACH | RPM | | | |
| | | | | | | 146 | 630 | 02100 | 146 | FT | GROUND MOUNTED SUPPORT, NO. 2 POST | | | |
| | | | | | | 229 | 630 | 03100 | 229 | FT | GROUND MOUNTED SUPPORT, NO. 3 POST | | | |
| | | | | | | 4 | 630 | 79500 | 4 | EACH | SIGN SUPPORT ASSEMBLY, POLE MOUNTED | | | |
| | | | | | | 96 | 630 | 80100 | 96 | SF | SIGN, FLAT SHEET | | | |
| | | | | | | 11 | 630 | 85000 | 11 | EACH | REMOVAL OF GROUND MOUNTED SIGN AND STORAGE | | | |
| | | | | | | 14 | 630 | 86002 | 14 | EACH | REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL | | | |
| | | | | | | 3.29 | 644 | 00100 | 3.29 | MILE | EDGE LINE, 4" | | | |
| | | | | | | 1.36 | 644 | 00200 | 1.36 | MILE | LANE LINE, 4" | | | |
| | | | | | | 1.25 | 644 | 00300 | 1.25 | MILE | CENTER LINE | | | |
| | | | | | | 1368 | 644 | 00400 | 1368 | FT | CHANNELIZING LINE, 8" | | | |
| | | | | | | 146 | 644 | 00500 | 146 | FT | STOP LINE | | | |
| | | | | | | 313 | 644 | 00600 | 313 | FT | CROSSWALK LINE | | | |
| | | | | | | 450 | 644 | 00700 | 450 | FT | TRANSVERSE/DIAGONAL LINE | | | |
| | | | | | | 24 | 644 | 00900 | 24 | SF | ISLAND MARKING | | | |
| | | | | | | 9 | 644 | 01300 | 9 | EACH | LANE ARROW | | | |
| | | | | | | 8 | 644 | 01410 | 8 | EACH | WORD ON PAVEMENT, 96" | | | |
| | | | | | | | | | | | TRAFFIC SIGNALS | | | |
| | | | | | | 122 | 625 | 25400 | 122 | FT | CONDUIT, 2", 725.04 | | | |
| | | | | | | 180 | 625 | 25500 | 180 | FT | CONDUIT, 3", 725.04 | | | |
| | | | | | | 182 | 625 | 29000 | 182 | FT | TRENCH | | | |
| | | | | | | 120 | 625 | 29600 | 120 | FT | TRENCH IN PAVED AREA, TYPE B | | | |
| | | | | | | 2 | 625 | 30706 | 2 | EACH | PULL BOX, 725.08, 24" | | | |
| | | | | | | 7 | 625 | 32000 | 7 | EACH | GROUND ROD | | | |
| | | | | | | 4 | 632 | 04910 | 4 | EACH | VEHICULAR SIGNAL HEAD, (LED), 3 SECTION, 12" LENS, 1-WAY, ALUMINUM | | | |
| | | | | | | 1 | 632 | 04916 | 1 | EACH | VEHICULAR SIGNAL HEAD, (LED), 3 SECTION, 12" LENS, 2-WAY, ALUMINUM | | | |
| | | | | | | 2 | 632 | 05080 | 2 | EACH | VEHICULAR SIGNAL HEAD, (LED), 5 SECTION, 12" LENS, 1-WAY, ALUMINUM | | | |
| | | | | | | 8 | 632 | 25000 | 8 | EACH | COVERING OF VEHICULAR SIGNAL HEAD | | | |
| | | | | | | 2 | 632 | 27004 | 2 | EACH | LOOP DETECTOR UNIT | | | |
| | | | | | | 3 | 632 | 27008 | 3 | EACH | LOOP DETECTOR UNIT, DELAY AND EXTENSION TYPE | | | |
| | | | | | | 139 | 632 | 30200 | 139 | FT | MESSENGER WIRE, 7 STRAND, 3/8" DIAMETER WITH ACCESSORIES | | | |
| | | | | | | 823 | 632 | 40300 | 823 | FT | SIGNAL CABLE, 3 CONDUCTOR, NO. 14 AWG | | | |
| | | | | | | 1168 | 632 | 40500 | 1168 | FT | SIGNAL CABLE, 5 CONDUCTOR, NO. 14 AWG | | | |
| | | | | | | 100 | 632 | 62810 | 100 | FT | INTERCONNECT CABLE, MISC.: INTEGRAL MESSENGER WIRE TYPE, 7 CONDUCTOR, NO. 12 AWG | 95 | | |
| | | | | | | 1601 | 632 | 65200 | 1601 | FT | LOOP DETECTOR LEAD-IN CABLE | | | |
| | | | | | | 25 | 632 | 67200 | 25 | FT | POWER CABLE, 2 CONDUCTOR, NO. 8 AWG | | | |
| | | | | | | 1 | 632 | 70001 | 1 | EACH | POWER SERVICE, AS PER PLAN | 95 | | |
| | | | | | | 2 | 632 | 85000 | 2 | EACH | COMBINATION STRAIN POLE, TYPE TC-81.10, DESIGN 10 | | | |
| | | | | | | 5 | 632 | 89900 | 5 | EACH | PEDESTAL, 8', TRANSFORMER BASE | | | |
| | | | | | | 1 | 632 | 90100 | 1 | EACH | REMOVAL OF TRAFFIC SIGNAL INSTALLATION | | | |
| | | | | | | 1 | 633 | 01661 | 1 | EACH | CONTROLLER UNIT, TYPE 2070E WITH SEPAC SOFTWARE, WITH CABINET, TYPE 332, AS PER PLAN | 95 | | |
| | | | | | | 1 | 633 | 67100 | 1 | EACH | CABINET FOUNDATION | | | |
| | | | | | | 1 | 633 | 67200 | 1 | EACH | CONTROLLER WORK PAD | | | |

GENERAL SUMMARY


ATB-208-13.43

| SHEET | | | | | | | | | ITEM | ITEM EXT. | GRAND TOTAL | UNIT | DESCRIPTION | SEE SHEET NO. |
|-------|--------|--------|--------|--------|-------|-------|--------|-------|------|-----------|-------------|------|--|---------------|
| GEN | DEL | MRW | FRA1 | FRA2 | MAD | MRW | PIC | UNI | | | | | | |
| 5 | 15 | 16 | 17 | 18 | 19 | 20 | 21 | 22 | | | | | | |
| | | | | | | | | | | | | | TRAFFIC CONTROL | |
| | 209.9 | 48.6 | 12.2 | 12.6 | 34.2 | 152.7 | 100.6 | 120.2 | 642 | 00090 | 691 | MILE | EDGE LINE, 4" | |
| | 113.0 | 33.3 | 369.9 | 298.0 | 29.9 | 59.8 | 94.3 | | 642 | 00094 | 885.2 | MILE | EDGE LINE, 6" | |
| | 70.0 | 32.7 | 273.0 | 314.1 | 22.2 | 30.6 | 59.6 | | 642 | 00194 | 732 | MILE | LANE LINE, 6" | |
| | 106.0 | 23.4 | 8.4 | 6.7 | 17.4 | 79.7 | 50.1 | | 642 | 00290 | 185.7 | MILE | CENTER LINE | |
| | 9201.0 | 3171.0 | 8512.0 | 4512.0 | 528.0 | | 7548.0 | | 642 | 00394 | 24271 | FT | CHANNELIZING LINE, 12" | |
| | | 106.0 | 7689.0 | 5459.0 | 897.0 | | 950.0 | | 642 | 01508 | 14995 | FT | DOTTED LINE, 6" | |
| LS | | | | | | | | | 642 | 20000 | LS | | TWO WAY RADIO EQUIPMENT | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | MAINTENANCE OF TRAFFIC | |
| 240 | | | | | | | | | 614 | 11110 | 240 | HOUR | LAW ENFORCEMENT WITH PATROL CAR FOR ASSISTANCE | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | INCIDENTALS | |
| LS | | | | | | | | | 614 | 11000 | LS | | MAINTAINING TRAFFIC | |
| LS | | | | | | | | | 614 | 11001 | LS | | MAINTAINING TRAFFIC, AS PER PLAN | 4 |
| LS | | | | | | | | | 624 | 10001 | LS | | MOBILIZATION, AS PER PLAN | 4 |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |



CALCULATED JOH CHECKED JDH
HORIZONTAL SCALE IN FEET
0 50 100 200

| PROJECT DATA | |
|--|---|
| Total Area (Right-Of-Way) ----- 120 Ac | Runoff Coefficient for Pre-Construction Site ----- 0.3-0.6 |
| Project Earth Disturbed Area ----- 106 Ac | Runoff Coefficient for Post Construction Site ----- 0.7 |
| Estimated Contractor Earth Disturbed Area ----- 7 Ac | Post Construction BMP: Vegetated biofilters were provided to meet NPDES post-construction requirements. See cross section sheets for locations. |
| Notice of Intent Earth Disturbed Area ----- 113 Ac | Immediate Receiving Waters ----- Pee Pee Creek |
| Impervious (Paved) Area for Pre-Construction Site ----- 10 Ac | Subsequent Receiving Water ----- Scioto River |
| Impervious (Paved) Area for Post Construction Site ----- 40 Ac | |



USGS Map: Cincinnati West Quadrangle
Cincinnati West, Ohio
Longitude: 84°-31'-30"*
Latitude: 39°-13'-10"*

* Longitude and Latitude to Approx. Center of Project

LEGEND

- Catch Basin, I-2A
- Catch Basin, CB-3, I-3A50
- Catch Basin, CB-5, CB-8
- Manhole
- ▨ Vegetated Biofilter
- Manufactured System (MS)

| BMP Type | Latitude/Longitude | | | | BMP Width (Feet) | EDA Treatment Credit (Acres) |
|------------------------------|--------------------|-----------|-----------|-----------|----------------------------|------------------------------|
| | Begin | | End | | | |
| Vegetated Biofilter 1 | 39.219722 | 84.524444 | 39.219444 | 84.523056 | 10 | 8.9 |
| Vegetated Biofilter 2 | 39.219167 | 84.524444 | 39.218889 | 84.522778 | 10 | 6.4 |
| Manufactured System I (MS I) | 37.220833 | 84.525833 | - | - | - | 9.7 |
| | | | | | Treatment Provided | 25.0 |
| | | | | | Treatment Required* | 24.4 |

* Calculated per L&D Vol. 2, Sec. 1115.7

PROJECT DESCRIPTION

The project consists of the construction of approximately two miles of four-lane, divided, limited access, urban expressway on new alignment in central Hamilton County in the Cincinnati Metropolitan area. The highway has an east-west orientation beginning 300 feet west of Clovernoll Drive, and ending 2,800 feet east of Sawmill Road. There is one interchange at Sawmill Road.



PROJECT SITE PLAN
STA. 320+00 TO STA. 350+00

HAM-745-18.36



CALCULATED MJD CHECKED DSN
0 10 20 40
HORIZONTAL SCALE IN FEET

| CROSS REFERENCES | |
|------------------|-------------------------------|
| Sheet No. | Description |
| 33 | Estimated Quantities |
| 79 | Driveway Details & Quantities |



PLAN AND PROFILE-S.R. 67
STA. 360+50 to STA. 366+00


CLI-67-16.86

I:\pr\V3Std\SamplePlans\Future Revision\Draft_0908\1309_DGN\1309_1(a).dgn 30-SEP-2008 1:08PM mwowski



0 20 40
HORIZONTAL SCALE IN FEET
CALCULATED M/JG CHECKED D/SN

| CROSS REFERENCES | |
|------------------|-------------------------------|
| Sheet No. | Description |
| 3-4 | References & Benchmarks |
| 37 | Profile |
| 38 | Estimated Quantities |
| 79 | Drive Details and Quantities |
| 86 | Culvert Detail and Quantities |
| 92 | Intersection Detail |




PLAN-S.R. 67
STA. 384+50 TO STA. 390+00

CLI-67-16.86

I:\pr\35\tds\SamplePlans\2011\April\1309_2.dgn 15-APR-2011 7:54AM mwawski




CALCULATED
DRT
CHECKED
TGH



For Quantities, See Sheet 20.



AREA FOR MANUFACTURED SYSTEM





PLAN AND PROFILE
STA. 55+00 TO STA. 60+00 S.R. 113

NOB-113-0.58

I:\pr\35\35\SamplePlans\Future Revision\Draft_0908\1309_DGN\1309_3.dgn 30-SEP-2008 1:08PM mwawski



| CROSS REFERENCES | |
|------------------|----------------------------------|
| Sheet No. | Description |
| 79 | Ref. Monuments, ODOT #418 & #419 |
| 46-67 | Estimated Quantities |
| 360, 368 | Ramps H & I |
| 486, 487 | Terminal Detail |
| 503 | Culvert Details |
| 667 | Fence Detail |



PLAN AND PROFILE - U.S. 33 BYPASS
STA. 469+50 TO STA. 418+50


FAI-33-13.25



CALCULATED MSO
CHECKED JAD


PLAN AND PROFILE - BUNNELL HILL RD
STA. 17+00 TO STA 21+00

WAR-48.19.40



CURVE DATA
P.I. Sta = 16+21.33
D = 58° 55' 58" (RT)
Dc = 16° 30' 00"
R = 347.25'
T = 196.19'
L = 357.17'
E = 51.59'
e_{max} = 0.04

| Sheet No. | Description |
|-----------|---|
| 3-4 | References & Benchmarks |
| 66 | Driveway Profiles |
| 87 | Driveway Details & Estimated Quantities |
| 89 | Drive Pipe Profiles |
| 94 | Culvert Detail |




| REF NO. | STATION | | SIDE | DESCRIPTION | QUANTITY | UNITS | BENDS & BRANCHES FOR INFO. ONLY | | | | | | |
|--|---------|-------|--------|-------------|----------|-------|---------------------------------|-----|-----|----|----|----|---|
| | FROM | TO | | | | | | | | | | | |
| R-14 | 18+86 | 19+20 | Rt. | | | | | | | | | | |
| R-15 | 19+52 | 19+55 | Center | | | | | | | | | | |
| R-16 | 16+60 | 20+20 | Lt. | | | | | | | | | | |
| R-17 | 19+70 | 20+19 | Rt. | | | | | | | | | | |
| UD-22 | 17+00 | 18+00 | Rt. | | | | | | | | | | |
| UD-23 | 18+00 | 18+00 | Center | | 96 | | | | | | | | |
| UD-24 | 18+05 | 19+45 | Rt. | | 140 | | | | | | | | |
| UD-25 | 18+05 | 19+45 | Lt. | | 140 | | | | | | | | |
| UD-26 | 19+45 | 19+45 | Center | | | | | | | | | | |
| D-9 | 18+83 | 19+17 | Rt. | | | | | | | | | | |
| F-1 | 16+62 | 20+19 | Lt. | | | | | | | | | | |
| TOTALS CARRIED TO GENERAL SUMMARY | | | | | 57 | 470 | 96 | 280 | 390 | 33 | 33 | 89 | 2 |


I:\pr\35\tds\SamplePlans\2013\January\DGN\1309_5_0118.dgn 18-JAN-2013 10:12AM fcheek



| CROSS REFERENCES | |
|------------------|---------------------------|
| SHEET NO. | DESCRIPTION |
| 3 | ☉ References & Benchmarks |
| 38 | Culvert Details |



Curve Data
 P.I. STA. 728+94.39 @ Const. SR 72
 $\Delta = 49^\circ 11' 35''$ (LT)
 $D_c = 4^\circ 30' 00''$
 $R = 1,273.24'$
 $L_s = 222.00'$
 $\theta_s = 4^\circ 59' 42''$
 $LT = 148.06'$
 $ST = 74.05'$
 $L_c = 871.18'$
 $T_s = 694.55'$
 $E_s = 128.83'$
 $e_{max} = 0.08$




| REF NO. | STATION | | SIDE | DESCRIPTION | QTY | UNIT | REMARKS |
|-----------------------------------|---------|--------|---------|----------------------|-----|------|---------|
| | FROM | TO | | | | | |
| R-1 | 727+43 | 727+56 | RT & LT | | | | |
| R-2 | 728+15 | 728+22 | RT | | 1 | | |
| R-3 | 728+17 | 728+23 | RT | | 1 | | |
| R-4 | 728+27 | 728+35 | RT | | 1 | | |
| R-5 | 728+51 | 728+53 | RT | | 1 | | |
| FD-1 | 727+43 | 727+56 | RT & LT | | | | |
| SD-1 | 727+50 | 729+50 | RT | | | | |
| TOTALS CARRIED TO GENERAL SUMMARY | | | | | | | |
| 202 | | | EACH | HEADWALL REMOVED | 2 | | |
| 202 | | | FT | PIPE REMOVED, 24\"/> | | | |

| | | | |
|------------|-----|---------|-----|
| CALCULATED | MSO | CHECKED | JAD |
|------------|-----|---------|-----|




PLAN AND PROFILE
 STA 727+00 TO 731+00


GRE-72-13.67



CALCULATED MSO
CHECKED JAD




FOR ESTIMATED QUANTITIES SEE SHEETS 20 - 24
FOR DRIVEWAY DETAILS AND QUANTITIES SEE SHEET 83
FOR STORM SEWER PROFILES SEE SHEETS 89 - 92
FOR ϵ REFERENCES AND BENCH MARKS SEE SHEETS 2 & 3




PLAN AND PROFILE
STA. 788+00 TO STA. 793+00

MOE-93-22.35


I:\pr\35\tds\SamplePlans\2006October\1309_7(a).dgn 15-APR-2011 7:39AM mwawski



CALCULATED MSO
CHECKED JAD





FOR ESTIMATED QUANTITIES SEE SHEETS 20 - 24
FOR DRIVEWAY DETAILS AND QUANTITIES SEE SHEET 83
FOR STORM SEWER PROFILES SEE SHEETS 89 - 92
FOR @ REFERENCES AND BENCH MARKS SEE SHEETS 2 & 3



PLAN AND PROFILE
STA. 793+00 TO STA. 798+00

MOE-93-22.35

I:\pr\35\35\SamplePlans\Future Revision\Draft_0908\1309_DGN\1309_7(b).dgn 30-SEP-2008 1:08PM mwawski




| REF NO. | STATION | | SIDE | DESCRIPTION | QUANTITY | UNIT |
|--|----------|----------|-------|--|----------|------|
| | FROM | TO | | | | |
| GR-1 | 334+02.5 | 335+49.5 | RT. | ANCHOR ASSEMBLY, TYPE A | 1 | EACH |
| GR-2 | 334+62.3 | 335+64.5 | LT. | ANCHOR ASSEMBLY, TYPE T | 1 | EACH |
| GR-3 | 336+54.6 | 337+77.2 | LT. | ANCHOR ASSEMBLY, TYPE T | 1 | EACH |
| GR-4 | 336+69.2 | 337+67.6 | RT. | ANCHOR ASSEMBLY, TYPE A | 1 | EACH |
| R-2 | 334+92 | 337+39 | LT. | BRIDGE TERMINAL ASSEMBLY, TYPE 4 | 1 | EACH |
| R-3 | 335+07 | 337+28 | RT. | BRIDGE TERMINAL ASSEMBLY, TYPE 4 | 1 | EACH |
| R-4 | 336+80 | 337+64 | RT. | BRIDGE TERMINAL ASSEMBLY, TYPE 4 | 1 | EACH |
| RPC-1 | 335+49 | 335+98 | LT/RT | CONCRETE WALK | 354 | SF |
| RPC-2 | 336+23 | 336+71 | LT/RT | CONCRETE WALK | 354 | SF |
| WK-2 | 336+92 | 337+64 | RT. | WALK REMOVED | 405 | SF |
| TOTALS CARRIED TO GENERAL SUMMARY | | | | | | |
| 601 | | | | ROCK CHANNEL PROTECTION TYPE C WITH FILTER | 120 | CY |
| 602 | | | | GUARDRAIL TYPE 5 | 387.5 | FT |
| 603 | | | | GUARDRAIL TYPE 5 | 250 | FT |
| 604 | | | | GUARDRAIL TYPE 5 | 225 | FT |
| 605 | | | | WALK REMOVED | 405 | SF |
| 606 | | | | GUARDRAIL TYPE 5 | 387.5 | FT |
| 607 | | | | ANCHOR ASSEMBLY, TYPE A | 3 | EACH |
| 608 | | | | ANCHOR ASSEMBLY, TYPE T | 1 | EACH |
| 609 | | | | BRIDGE TERMINAL ASSEMBLY, TYPE 4 | 4 | EACH |
| 610 | | | | 4" CONCRETE WALK | 354 | SF |
| 611 | | | | ROCK CHANNEL PROTECTION TYPE C WITH FILTER | 250 | CY |

PLAN AND PROFILE - S.R. 722
STA. 334+00 TO STA. 338+00

DAR-722-6.34

| SEEDING |
|-----------|
| END WIDTH |
| SO. YDS. |

| | |
|------------|------|
| CALCULATED | MT/G |
| CHECKED | C/M |



| END AREA | VOLUME | |
|--------------------|------------|-------------|
| | CUT | FILL |
| 950 | 0 | 919 |
| 950 | 7 | 1054 |
| 960 | 8 | 219 |
| 950 | 24 | 346 |
| 960 | 18 | 155 |
| 950 | 40 | 250 |
| 960 | 25 | 115 |
| 950 | 67 | 187 |
| SHEET TOTAL | 138 | 1837 |

CROSS SECTIONS - S.R. 76
STA. 362+50 TO STA. 364+00

LUC-76-31.48

154
488


| | | | | | | | | | | | | | |
|------|-------------|-----|----|----|----|----|---|----|----|----|----|-----|-------------|
| 2115 | SHEET TOTAL | 100 | 80 | 60 | 40 | 20 | 0 | 20 | 40 | 60 | 80 | 100 | SHEET TOTAL |
|------|-------------|-----|----|----|----|----|---|----|----|----|----|-----|-------------|

SEEDING
END WIDTH SQ. YDS.

ROAD FOR MAINT. TRAFFIC
SP 1310-2
DATE: OCT. 2006

CALCULATED RDN CHECKED PDG

517
104
583
106
586
105
581
104
2267 SHEET TOTAL




| END AREA | | VOLUME | | END AREA | | VOLUME | |
|----------|------|--------|------|----------|------|----------|------|
| CUT | FILL | CUT | FILL | CUT | FILL | CUT | FILL |
| 0 | 332 | | | 95 | 136 | 156 | 171 |
| 0 | 645 | | | 241 | 169 | | |
| 0 | 364 | | | 165 | 46 | | |
| 6 | 703 | | | 367 | 94 | | |
| 7 | 395 | | | 231 | 56 | | |
| 6 | 616 | | | 509 | 96 | | |
| 0 | 270 | | | 319 | 48 | | |
| 7 | 297 | | | | | | |
| *19 | | *2261 | | | | 1273 530 | |

Legend:
 Road for Maint. Traffic Earthwork
 Included with Permanent Earthwork Quantities
 *For Information Only

CROSS SECTIONS - S.R. 130
STA. 202+50 TO STA. 204+00

MED - 130-1.23

74
103



| END STA | AREA | VOLUME | CUT | | FILL | |
|-----------|------|--------|------|--------|------|--------|
| | | | AREA | VOLUME | AREA | VOLUME |
| 369+00 | 42 | 30 | | | | |
| 368+90 LT | | | | | 4 | 2 |
| 368+50 | 24 | 35 | 61 | 60 | | |
| 368+00 | 38 | 24 | | | 57 | 55 |
| 367+63 RT | | | | | 5 | 2 |
| 367+50 | 47 | 19 | 79 | 40 | | |
| 367+40 | | | | | 69 | 31 |
| 367+16 RT | | | | | 2 | 3 |
| 366+90 | 28 | 15 | | | | |
| 366+50 | 18 | 41 | | | 43 | 52 |
| 366+01 RT | | | | | 38 | 68 |
| 366+00 | 23 | 32 | | | 2 | 3 |
| TOTAL | | | | | 360 | 316 |


CROSS SECTIONS - S.R. 67
STA. 366+00 TO STA. 368+50



CLI-67-16.86

57
97

I:\pr\35\tds\SamplePlans\2006October\1310\1310_4.dgn 15-APR-2011 7:39AM mwowski


| SEEDING | | GEOTEXTILE FABRIC | |
|-----------|----------|-------------------|----------|
| END WIDTH | SO. YDS. | END WIDTH | SO. YDS. |
| 44 | 24 | 24 | 133 |
| 45 | 24 | 24 | 15 |
| 48 | 24 | 24 | 148 |
| 275 | 148 | SHEET TOTAL | |



 Item 204 - Excavation and
 Item 204 - Granular Material, Type B
 Item 204 - Granular Material, Type B

| SP 1310-4 | | | | | | | |
|--------------------|------|--------|------|----------|------|--------|------|
| DATE: OCTOBER 2006 | | | | | | | |
| ITEM 203 | | | | ITEM 204 | | | |
| END AREA | | VOLUME | | END AREA | | VOLUME | |
| CUT | FILL | CUT | FILL | CUT | FILL | CUT | FILL |
| 7 | 41 | | | 40 | 78 | | |
| | | 14 | 77 | | | 72 | 144 |
| 8 | 42 | | | 38 | 78 | | |
| | | 2 | 9 | | | 8 | 16 |
| 7 | 51 | | | 37 | 78 | | |
| SHEET TOTAL | | 16 | 86 | | | 80 | 160 |

CALCULATED GFR
 CHECKED JAD
CROSS SECTIONS - RELOCATED BOUNDARIES RD (C.R. 9)
STA. 75+92.89 TO STA. 76+50
PER / LIC-13-28.73 / 0.00
 (210 / 310)




LEFT EDGE OF PAVEMENT, S.R. 28



CALCULATED MSO
CHECKED JAD

CROSS SECTION LAYOUT



CLA-40-10.18




I:\pr\35\35\SamplePlans\Future Revision\1310\1310_6.dgn 03-OCT-2006 9:28AM mawowski

| SEEDING | |
|-----------|----------|
| END WIDTH | SO. YDS. |
| 315 | |
| 68 | |
| 81 | |
| 64 | |
| 355 | |
| 64 | |
| 1489 | |

| END AREA | | VOLUME | |
|----------|------|--------|------|
| CUT | FILL | CUT | FILL |
| 81 | 26 | | |
| | | 224 | 32 |
| | | -157 | 0 |
| 160 | 9 | | |
| | | 459 | 3 |
| | | -124 | 0 |
| 335 | 4 | | |
| | | 602 | 8 |
| 315 | 5 | | |
| | | 605 | 16 |
| | | 1609 | 59 |

 Item 202 - Pavement Removed, Asphalt Concrete
 Item 202 - Pavement Removed, Asphalt Concrete and Item 203 - Embankment



CROSS SECTIONS - S.R. 315
STA. 95+00 TO STA. 96+50

FRA - 315 - 12.18

SUPERELEVATION TABLE

P. I. Station 20+00.00

Dc = 6° 00'

| LEFT SIDE | | | | | CENTERLINE CONTROL | | RIGHT SIDE | | | | | REMARKS |
|----------------|-----------------|-----------------------|-------------|-------|--------------------|---------------|------------|-------------|-----------------------|-----------------|----------------|-----------|
| EDGE ELEVATION | TRANSITION RATE | *ELEVATION CORRECTION | CROSS SLOPE | WIDTH | STATION | PROFILE GRADE | WIDTH | CROSS SLOPE | *ELEVATION CORRECTION | TRANSITION RATE | EDGE ELEVATION | |
| 840.79 | ▲ | -0.17 | -0.0156 | 11.01 | 14+95.00 | 840.96 | 11.01 | -0.0156 | -0.17 | | 840.79 | N.C. |
| 840.81 | | -0.15 | -0.0135 | 11.10 | 15+00.00 | 840.96 | 11.10 | -0.0156 | -0.17 | | 840.79 | |
| 840.93 | | -0.03 | -0.0026 | 11.55 | 15+25.00 | 840.96 | 11.55 | -0.0156 | -0.18 | | 840.78 | |
| 840.96 | | 0.00 | 0.0000 | 11.66 | 15+31.25 | 840.96 | 11.66 | -0.0156 | -0.18 | | 840.78 | 1/2 LEVEL |
| 841.05 | | +0.09 | +0.0075 | 12.00 | 15+50.00 | 840.96 | 12.00 | -0.0156 | -0.19 | | 840.77 | |
| 841.14 | | +0.19 | +0.0156 | 12.00 | 15+68.80 | 840.96 | 12.00 | -0.0156 | -0.19 | ▲ | 840.77 | R.C. |
| 841.17 | | +0.21 | +0.0179 | 12.00 | 15+75.00 | 840.96 | 12.00 | -0.0179 | -0.21 | | 840.75 | |
| 841.28 | 2/11 | +0.33 | +0.0278 | 12.00 | 16+00.00 | 840.95 | 12.00 | -0.0278 | -0.33 | | 840.62 | |
| 841.40 | | +0.45 | +0.0397 | 12.00 | 16+25.00 | 840.95 | 12.00 | -0.0377 | -0.45 | | 840.50 | |
| 841.52 | | +0.57 | +0.0476 | 12.00 | 16+50.00 | 840.95 | 12.00 | -0.0476 | -0.57 | | 840.38 | |
| 841.61 | | +0.66 | +0.0553 | 12.00 | 16+69.40 | 840.95 | 12.00 | -0.0553 | -0.66 | 2/11 | 840.29 | P.C. |
| 841.64 | | +0.69 | +0.0575 | 12.00 | 16+75.00 | 840.95 | 12.00 | -0.0575 | -0.69 | | 840.26 | |
| 841.76 | | +0.81 | +0.0674 | 12.00 | 17+00.00 | 840.95 | 12.00 | -0.0674 | -0.81 | | 840.14 | |
| 841.88 | | +0.93 | +0.0773 | 12.00 | 17+25.00 | 840.95 | 12.00 | -0.0773 | -0.93 | | 840.02 | |
| 841.95 | ▼ | +1.00 | +0.0830 | 12.00 | 17+39.33 | 840.95 | 12.00 | -0.0830 | -1.00 | | 839.95 | |
| 841.95 | | +1.00 | +0.0830 | 12.00 | 17+50.00 | 840.95 | 12.00 | -0.0830 | -1.00 | ▼ | 839.95 | F.S. |
| 842.00 | | +1.00 | +0.0830 | 12.00 | 17+75.00 | 841.00 | 12.00 | -0.0830 | -1.00 | | 840.00 | |
| 842.15 | | +1.00 | +0.0830 | 12.00 | 18+00.00 | 841.25 | 12.00 | -0.0830 | -1.00 | | 840.15 | |
| 842.42 | | +1.00 | +0.0830 | 12.00 | 18+25.00 | 841.42 | 12.00 | -0.0830 | -1.00 | | 840.42 | |
| 842.78 | | +1.00 | +0.0830 | 12.00 | 18+50.00 | 841.78 | 12.00 | -0.0830 | -1.00 | | 840.78 | |
| 843.26 | | +1.00 | +0.0830 | 12.00 | 18+75.00 | 842.26 | 12.00 | -0.0830 | -1.00 | | 841.26 | |
| 843.84 | | +1.00 | +0.0830 | 12.00 | 19+00.00 | 842.84 | 12.00 | -0.0830 | -1.00 | | 841.84 | |
| 844.52 | | +1.00 | +0.0830 | 12.00 | 19+25.00 | 843.52 | 12.00 | -0.0830 | -1.00 | | 842.52 | |
| 845.31 | | +1.00 | +0.0830 | 12.00 | 19+50.00 | 844.31 | 12.00 | -0.0830 | -1.00 | | 843.31 | |
| 846.21 | | +1.00 | +0.0830 | 12.00 | 19+75.00 | 845.21 | 12.00 | -0.0830 | -1.00 | | 844.21 | |
| 847.21 | | +1.00 | +0.0830 | 12.00 | 20+00.00 | 846.21 | 12.00 | -0.0830 | -1.00 | | 845.21 | |
| 848.32 | | +1.00 | +0.0830 | 12.00 | 20+25.00 | 847.32 | 12.00 | -0.0830 | -1.00 | | 846.32 | |
| 849.53 | | +1.00 | +0.0830 | 12.00 | 20+50.00 | 848.53 | 12.00 | -0.0830 | -1.00 | | 847.53 | |
| 850.85 | | +1.00 | +0.0830 | 12.00 | 20+75.00 | 849.85 | 12.00 | -0.0830 | -1.00 | | 848.85 | |
| 852.27 | | +1.00 | +0.0830 | 12.00 | 21+00.00 | 851.27 | 12.00 | -0.0830 | -1.00 | | 850.27 | |
| 853.80 | | +1.00 | +0.0830 | 12.00 | 21+25.00 | 852.80 | 12.00 | -0.0830 | -1.00 | | 851.80 | |
| 855.44 | | +1.00 | +0.0830 | 12.00 | 21+50.00 | 854.44 | 12.00 | -0.0830 | -1.00 | | 853.44 | |
| 857.18 | | +1.00 | +0.0830 | 12.00 | 21+75.00 | 856.18 | 12.00 | -0.0830 | -1.00 | | 855.18 | |
| 859.03 | | +1.00 | +0.0830 | 12.00 | 22+00.00 | 858.03 | 12.00 | -0.0830 | -1.00 | | 857.03 | |
| 860.98 | | +1.00 | +0.0830 | 12.00 | 22+25.00 | 859.98 | 12.00 | -0.0830 | -1.00 | | 858.98 | |
| 861.87 | ▲ | +1.00 | +0.0830 | 12.00 | 22+35.95 | 860.87 | 12.00 | -0.0830 | -1.00 | ▲ | 859.87 | F.S. |
| 862.96 | | +0.93 | +0.0775 | 12.00 | 22+50.00 | 862.03 | 12.00 | -0.0776 | -0.93 | | 861.10 | |
| 865.01 | | +0.81 | +0.0677 | 12.00 | 22+75.00 | 864.20 | 12.00 | -0.0677 | -0.81 | | 863.39 | |
| 867.16 | | +0.69 | +0.0578 | 12.00 | 23+00.00 | 866.47 | 12.00 | -0.0578 | -0.69 | | 865.78 | |
| 867.69 | | +0.67 | +0.0554 | 12.00 | 23+05.94 | 867.02 | 12.00 | -0.0554 | -0.67 | 2/11 | 866.35 | P.T. |
| 869.41 | | +0.57 | +0.0479 | 12.00 | 23+25.00 | 868.84 | 12.00 | -0.0479 | -0.57 | | 868.27 | |
| 871.78 | | +0.46 | +0.0380 | 12.00 | 23+50.00 | 871.32 | 12.00 | -0.0380 | -0.46 | | 870.86 | |
| 874.19 | 2/11 | +0.34 | +0.0281 | 12.00 | 23+75.00 | 873.85 | 12.00 | -0.0281 | -0.34 | | 873.51 | |
| 876.61 | | +0.22 | +0.0182 | 12.00 | 24+00.00 | 876.39 | 12.00 | -0.0182 | -0.22 | | 876.17 | |
| 877.24 | | +0.19 | +0.0156 | 12.00 | 24+06.48 | 877.05 | 12.00 | -0.0156 | -0.19 | ▼ | 876.86 | R.C. |
| 879.02 | | +0.10 | +0.0083 | 12.00 | 24+25.00 | 878.92 | 12.00 | -0.0156 | -0.19 | | 878.73 | |
| 881.03 | | 0.00 | 0.0000 | 11.62 | 24+45.83 | 881.03 | 11.62 | -0.0156 | -0.18 | | 880.85 | 1/2 LEVEL |
| 881.43 | | -0.02 | -0.0017 | 11.55 | 24+50.00 | 881.45 | 11.55 | -0.0156 | -0.18 | | 881.27 | |
| 883.84 | | -0.14 | -0.0126 | 11.10 | 24+75.00 | 883.98 | 11.10 | -0.0156 | -0.17 | | 883.81 | |
| 884.47 | ▼ | -0.17 | -0.0156 | 10.98 | 24+81.50 | 884.64 | 10.98 | -0.0156 | -0.17 | | 884.47 | N.C. |

* NEGATIVE CORRECTIONS MEANING BELOW PROFILE GRADE
POSITIVE CORRECTIONS MEANING ABOVE PROFILE GRADE.

SUPERELEVATION TABLE

P. I. Station 36+45.21

Dc = 3° 00'

SP 1311-1
DATE: OCTOBER 2006

| LEFT SIDE | | | | | CENTERLINE CONTROL | | RIGHT SIDE | | | | | REMARKS |
|----------------|-----------------|-----------------------|-------------|-------|--------------------|---------------|------------|-------------|-----------------------|-----------------|----------------|---------|
| EDGE ELEVATION | TRANSITION RATE | *ELEVATION CORRECTION | CROSS SLOPE | WIDTH | STATION | PROFILE GRADE | WIDTH | CROSS SLOPE | *ELEVATION CORRECTION | TRANSITION RATE | EDGE ELEVATION | |
| 606.93 | ▲ | -0.19 | -0.0156 | 12.00 | 33+92.16 | 607.12 | 12.00 | -0.0156 | -0.19 | | 606.93 | N.C. |
| 607.13 | | -0.16 | -0.0133 | 12.00 | 34+00.00 | 607.29 | 12.00 | -0.0156 | -0.19 | | 607.10 | |
| 607.76 | | -0.05 | -0.0042 | 12.00 | 34+25.00 | 607.81 | 12.00 | -0.0156 | -0.19 | | 607.62 | |
| 608.04 | | 0.00 | 0.0000 | 12.00 | 34+37.09 | 608.04 | 12.00 | -0.0156 | -0.19 | | 607.85 | T.S. |
| 608.34 | | +0.05 | +0.0042 | 12.00 | 34+50.00 | 608.29 | 12.00 | -0.0156 | -0.19 | | 608.10 | |
| 608.88 | | +0.16 | +0.0133 | 12.00 | 34+75.00 | 608.72 | 12.00 | -0.0156 | -0.19 | | 608.53 | |
| 609.02 | | +0.19 | +0.0156 | 12.00 | 34+82.02 | 608.83 | 12.00 | -0.0156 | -0.19 | ▲ | 608.64 | R.C. |
| 609.38 | 236.5/1 | +0.27 | +0.0225 | 12.00 | 35+00.00 | 609.11 | 12.00 | -0.0225 | -0.27 | | 608.84 | |
| 609.84 | | +0.37 | +0.0308 | 12.00 | 35+25.00 | 609.47 | 12.00 | -0.0308 | -0.37 | | 609.10 | |
| 610.26 | | +0.48 | +0.0400 | 12.00 | 35+50.00 | 609.78 | 12.00 | -0.0400 | -0.48 | | 609.30 | |
| 610.63 | | +0.58 | +0.0483 | 12.00 | 35+75.00 | 610.05 | 12.00 | -0.0483 | -0.58 | 236.5/1 | 609.47 | |
| 610.97 | | +0.69 | +0.0575 | 12.00 | 36+00.00 | 610.28 | 12.00 | -0.0575 | -0.69 | | 609.59 | |
| 611.12 | ▼ | +0.74 | +0.0620 | 12.00 | 36+12.09 | 610.38 | 12.00 | -0.0620 | -0.74 | ▼ | 609.64 | S.C. |
| 611.21 | | +0.74 | +0.0620 | 12.00 | 36+25.00 | 610.47 | 12.00 | -0.0620 | -0.74 | | 609.73 | |
| 611.36 | | +0.74 | +0.0620 | 12.00 | 36+50.00 | 610.62 | 12.00 | -0.0620 | -0.74 | | 609.88 | |
| 611.47 | | +0.74 | +0.0620 | 12.00 | 36+75.00 | 610.73 | 12.00 | -0.0620 | -0.74 | | 609.99 | |
| 611.48 | ▲ | +0.74 | +0.0620 | 12.00 | 36+77.94 | 610.74 | 12.00 | -0.0620 | -0.74 | ▲ | 610.00 | C.S. |
| 611.44 | | +0.65 | +0.0542 | 12.00 | 37+00.00 | 610.79 | 12.00 | -0.0542 | -0.65 | | 610.14 | |
| 611.36 | | +0.54 | +0.0450 | 12.00 | 37+25.00 | 610.82 | 12.00 | -0.0450 | -0.54 | | 610.28 | |
| 611.25 | | +0.44 | +0.0367 | 12.00 | 37+50.00 | 610.81 | 12.00 | -0.0367 | -0.44 | | 610.37 | |
| 611.08 | | +0.33 | +0.0275 | 12.00 | 37+75.00 | 610.75 | 12.00 | -0.0275 | -0.33 | 236.5/1 | 610.42 | |
| 610.87 | 236.5/1 | +0.22 | +0.0183 | 12.00 | 38+00.00 | 610.65 | 12.00 | -0.0183 | -0.22 | | 610.43 | |
| 610.80 | | +0.19 | +0.0156 | 12.00 | 38+08.01 | 610.61 | 12.00 | -0.0156 | -0.19 | ▼ | 610.42 | R.C. |
| 610.64 | | +0.12 | +0.0100 | 12.00 | 38+25.00 | 610.52 | 12.00 | -0.0156 | -0.19 | | 610.33 | |
| 610.35 | | +0.01 | +0.0008 | 12.00 | 38+50.00 | 610.34 | 12.00 | -0.0156 | -0.19 | | 610.15 | |
| 610.31 | | 0.00 | 0.0000 | 12.00 | 38+52.94 | 610.31 | 12.00 | -0.0156 | -0.19 | | 610.12 | S.T. |
| 610.03 | | -0.09 | -0.0075 | 12.00 | 38+75.00 | 610.12 | 12.00 | -0.0156 | -0.19 | | 609.93 | |
| 609.69 | ▼ | -0.19 | -0.0156 | 12.00 | 38+97.87 | 609.88 | 12.00 | -0.0156 | -0.19 | | 609.69 | N.C. |

SUPERELEVATION TABLE

BEL - 148 - 11.48

CALCULATED
KAK
CHECKED
LJS





CALCULATED
VHW
CHECKED
TLH

INTERSECTION DETAIL - S.R. 757 & DUCK ROAD

MEG-757-1.23

CURVE DATA

P.I. Sta. 261+49.40, S.R. 757
 $\Delta = 1^{\circ}44'50''$ Lt
 $D_c = 0^{\circ}30'00''$
 $R = 11459.16'$
 $T = 174.74'$
 $L = 349.44'$
 $E = 1.33'$
 $e_{max} = 0.010$



DETAIL A




0 10 20 40
HORIZONTAL
SCALE IN FEET

CALCULATED
WSR
CHECKED
SUB

INTERSECTION DETAIL & PAVEMENT ELEVATIONS
S.R. 621 AND S.R. 144

BEL-621-5.29

42
50





CURVE DATA FOR RADIUS RETURNS

| CURVE No. | RADIUS | INTERIOR ANGLE | LENGTH OF CURVE |
|-----------|--------|----------------|-----------------|
| 1 | 45' | 106.48° | 83.63' |
| 2 | 50' | 65.27° | 56.96' |
| 3 | 60' | 73.52° | 76.99' |
| 4 | 75' | 73.54° | 96.27' |
| 5 | 45' | 106.48° | 83.63' |
| 6 | 55' | 106.50° | 102.24' |
| 7 | 60' | 73.52° | 76.99' |


ALL DISTANCES ARE MEASURED TO THE FACE OF CURB.

NOTES
 ADD 1000 TO THE ELEVATION SHOWN FOR ACTUAL ELEVATION.
 * STATIONING BASED OFF \odot S.R. 144
 ALL ELEVATIONS ALONG THE CURB ARE TOP OF CURB ELEVATIONS.
 DEDUCT 6" IN AREAS OF FULL HEIGHT CURB AND 2" IN AREAS OF DROP CURB TO OBTAIN E.P. ELEVATIONS AT FACE OF CURB.
 FOR DRIVEWAY DETAILS, SEE SHEETS 44-45.







RESIDENTIAL DRIVES



COMMERCIAL DRIVES WITHOUT WRAP-AROUND CURB



SERVICE STATION DRIVES
FOR θ , SEE PLAN/PROFILE SHEETS.



COMMERCIAL DRIVES WITH WRAP-AROUND CURB

RESIDENTIAL DRIVES

- EXISTING AGGREGATE DRIVES
 - 452 - 6" NON-REINFORCED CONCRETE PAVEMENT (APRON)
 - 301 - 8" ASPHALT CONCRETE BASE, PG64-22
- EXISTING ASPHALT DRIVES
 - 452 - 6" NON-REINFORCED CONCRETE PAVEMENT (APRON)
 - 301 - 2" ASPHALT CONCRETE BASE, PG64-22
 - 407 - TACK COAT
 - 304 - 6" AGGREGATE BASE
- EXISTING CONCRETE DRIVES
 - 452 - 6" NON-REINFORCED CONCRETE PAVEMENT (APRON)

COMMERCIAL AND SERVICE STATION DRIVES

- EXISTING AGGREGATE DRIVE
 - 452 - 8" NON-REINFORCED CONCRETE PAVEMENT (APRON)
 - 304 - 10" AGGREGATE BASE
- EXISTING ASPHALT DRIVE
 - 452 - 8" NON-REINFORCED CONCRETE PAVEMENT (APRON)
 - 442 - 1/4" ASPHALT CONCRETE SURFACE COURSE, 12.5MM, TYPE A, (448)
 - 442 - 1 3/4" ASPHALT CONCRETE, INTERMEDIATE COURSE, TYPE 1, (448)
 - 407 - TACK COAT
 - 304 - 8" AGGREGATE BASE
- EXISTING CONCRETE DRIVE
 - 452 - 8" NON-REINFORCED CONCRETE PAVEMENT (APRON)

SEE SHEET 41 FOR DRIVEWAY QUANTITIES.



DRIVEWAY DETAILS

CAR-38-22.56

| SHEET NO. | REFERENCE NO. | STATION | SIDE | DRIVE TYPE | APRON LENGTH "L1" | DRIVEWAY LENGTH "L2" | WIDTH "W" | R1 (LEFT SIDE RADIUS OF DRIVE LOOKING FROM ☐) | R2 (RIGHT SIDE RADIUS OF DRIVE LOOKING FROM ☐) | 202 | 203 | | 301 | 304 | | | 407 | 442 | | 452 | | SP 1311-5 | | | | |
|--|---------------|-------------------|------|------------|-------------------|----------------------|-----------|---|--|------------------|------------|------------|-----------------------------------|-------------------|-------------------|--------------------|-----------|--|---|-------------------------------------|-------------------------------------|-----------------|-------------|-----|---------|-----|
| | | | | | | | | | | PAVEMENT REMOVED | EMBANKMENT | EXCAVATION | 8" ASPHALT CONCRETE BASE, PG64-22 | 6" AGGREGATE BASE | 8" AGGREGATE BASE | 10" AGGREGATE BASE | TACK COAT | 1 1/2" ASPHALT CONCRETE, INTERMEDIATE COURSE, 19MM, TYPE A (446) | 1/4" ASPHALT CONCRETE SURFACE COURSE, 4.5MM, TYPE A (446) | 6" NON-REINFORCED CONCRETE PAVEMENT | 8" NON-REINFORCED CONCRETE PAVEMENT | DATE: JULY 2016 | CALCULATED | WSR | CHECKED | SJB |
| | | | | | | | | | | SY | CY | CY | CY | CY | CY | CY | CY | CY | CY | CY | CY | CY | CY | CY | SY | SY |
| 71 | DR-1 | 695+70 | RT | COMM. | 9.50 | 13.0 | 35.0 | 15.0 | 15.0 | 186.6 | | 8 | | | | | | | | | | | 120.7 | | | |
| 71 | DR-2 | 696+27.03 | RT | COMM. | 11.0 | 17.0 | 12.0 | 15.0 | 6.00 | | | 5 | 1.1 | | 5.2 | | 9.3 | | 0.8 | | | | 17.1 | | | |
| 71 | DR-3 | 696+62 | RT | COMM. | 9.50 | 15.0 | 35.0 | 15.0 | 15.0 | 217.7 | | 7 | | | | | | | | | | | 218.9 | | | |
| | | PARKING | RT | | | | | | | 111.7 | | 26 | 2.2 | | 10.6 | | 19.0 | | 1.6 | | | | | | | |
| 71 | DR-4 | 697+25 | LT | COMM. | 9.50 | 20.0 | 26.0 | 15.0 | 15.0 | | | 19 | 2.8 | | 12.8 | | 23.1 | | 2.0 | | | | 31.8 | | | |
| 71 | DR-5 | 697+68 | RT | COMM. | 9.50 | 10.0 | 35.0 | 15.0 | 15.0 | 141.7 | | 11 | | | | | | | | | | | 85.6 | | | |
| 71 | | PARKING TO 698+00 | RT | | | | | | | 26.1 | | 12 | | | | | | | | | | | 26.1 | | | |
| 74 | DR-1 | 10+75 | RT | COMM. | 17.5 | -- | 35.0 | 15.0 | 3.00 | 67.7 | | 4 | | | | | | | | | | | 66.2 | | | |
| | | 2ND ST. N.W. | | | | | | | | | | | | | | | | | | | | | | | | |
| 74 | DR-2 | 10+36 | LT | RES. | 17.0 | 23.3 | 8.00 | 4.00 | 6.00 | | | 15 | | 2.7 | | 6.4 | 0.9 | | | 30.0 | | | | | | |
| | | 2ND ST. N.W. | | | | | | | | | | | | | | | | | | | | | | | | |
| 74 | DR-3 | 698+87 | LT | COMM. | 9.50 | 28.0 | 25.0 | 15.0 | 15.0 | | 6 | 10 | 3.8 | 17.3 | | 31.1 | | 2.7 | | | | | 32.0 | | | |
| 74 | DR-4 | 699+96 | RT | RES. | 10.0 | 9.50 | 15.0 | 6.00 | 6.00 | | | 13 | 3.9 | | | | | | | 7.8 | | | | | | |
| | | PARKING | | | | | | | | 29.3 | | 5 | 3.1 | | | | | | | 1.6 | | | | | | |
| 74 | DR-5 | 700+77 | RT | COMM. | 9.50 | 5.00 | 35.0 | 15.0 | 15.0 | | | 16 | | | | | | | | | | | 40.7 | | | |
| | | PARKING | RT | | | | | | | | | 2 | | | | | | | | | | | | | | |
| 74 | DR-6 | 701+32 | RT | COMM. | 10.0 | 11.0 | 21.0 | -- | 6.00 | | | 6 | | | | | | | | | | | 27.1 | | | |
| 76 | DR-1 | 702+45 | RT | COMM. | 9.50 | 12.5 | 35.0 | 15.0 | 15.0 | 165.6 | 16 | | | | | | | | | | | | 94.9 | | | |
| | | PARKING | | | | | | | | 53.7 | 3 | | | | | | | | | | | | 53.7 | | | |
| 76 | DR-2 | 703+60 | RT | COMM. | 10.0 | 26.5 | 35.0 | 15.0 | 15.0 | | | 29 | 5.5 | | 24.8 | | 44.7 | | 3.9 | | | | 51.8 | | | |
| 76 | DR-3 | 706+69 | LT | RES. | 9.50 | 5.00 | 13.0 | 6.00 | 6.00 | | | 3 | 1.5 | | | | | | | 14.4 | | | | | | |
| 76 | DR-4 | 704+21 | LT | RES. | 9.50 | 5.00 | 21.0 | 6.00 | 6.00 | | 1 | 1 | 1.5 | | | | | | | 14.4 | | | | | | |
| 76 | DR-5 | 705+14 | LT | RES. | 9.50 | -- | 28.0 | 6.00 | 6.00 | | 4 | | | | | | | | | 29.1 | | | | | | |
| 77 | DR-1 | 706+39 | LT | RES. | 9.50 | 5.00 | 8.00 | 6.00 | 6.00 | | | 2 | 1.0 | | | | | | | 8.7 | | | | | | |
| 77 | DR-2 | 707+44 | LT | RES. | 9.50 | 1.00 | 12.0 | 6.00 | 6.00 | | | 5 | | 0.2 | | 0.5 | 0.1 | | | 13.1 | | | | | | |
| 77 | DR-3 | 708+05 | RT | COMM. | 9.50 | 9.50 | 35.0 | 15.0 | 15.0 | | | 22 | 1.0 | | 4.2 | | 7.6 | | 0.7 | | | | 41.1 | | | |
| | | PARKING | | | | | | | | | 11 | 1.8 | | 8.0 | | 14.4 | | 1.3 | | | | | | | | |
| 77 | DR-4 | 709+01 | RT | COMM. | 9.50 | 5.00 | 19.0 | 15.0 | 15.0 | | | 5 | 0.6 | | 2.8 | | 5.1 | | 0.4 | | | | 24.0 | | | |
| 77 | DR-5 | 709+81 | LT | RES. | 9.50 | 10.5 | 17.0 | 6.00 | 6.00 | | | 5 | | 1.8 | | 4.2 | 0.6 | | | 19.6 | | | | | | |
| | | PARKING | | | | | | | | | 3 | | | 3.7 | | 8.9 | 1.2 | | | | | | | | | |
| 77 | DR-6 | 10+51 | LT | COMM. | 17.0 | 17.5 | 16.0 | 15.0 | 2.30 | | | | | | | | | | | | | | 35.6 | | | |
| | | 5TH ST. N.W. | | | | | | | | | | | | | | | | | | | | | | | | |
| 77 | DR-7 | 10+67 | LT | RES. | 17.0 | -- | 6.00 | 2.30 | 6.00 | 35.6 | | | | | | | | | | | | | 18.9 | | | |
| | | 5TH ST. N.W. | | | | | | | | | | | | | | | | | | | | | | | | |
| 78 | DR-1 | 710+44 | LT | COMM. | 9.50 | 10.0 | 21.5 | 15.0 | 15.0 | | | 13 | 1.4 | | 6.7 | | 12.0 | | 1.0 | | | | 29.1 | | | |
| | | PARKING | | | | | | | | | 17 | 3.1 | | | 13.7 | | 24.7 | | 2.2 | | | | | | | |
| 78 | DR-2 | 711+08 | LT | RES. | 9.50 | 39.0 | 17.0 | 6.00 | 6.00 | | 2 | 7 | | 9.1 | | 21.9 | 3.0 | | | 20.2 | | | | | | |
| 78 | DR-3 | 711+58 | RT | COMM. | 9.50 | 6.00 | 35.0 | 15.0 | 15.0 | | | 15 | 1.4 | | 6.4 | | 11.5 | | 1.0 | | | | 42.7 | | | |
| | | PARKING | | | | | | | | | 16 | 2.8 | | | 12.8 | | 23.1 | | 2.0 | | | | | | | |
| 78 | DR-4 | 711+96 | LT | COMM. | 9.50 | 16.5 | 35.0 | 15.0 | 5.00 | | | 16 | 3.9 | | 17.9 | | 32.3 | | 2.8 | | | | 40.9 | | | |
| | | PARKING | | | | | | | | | 14 | 2.2 | | | 10.4 | | 18.7 | | 1.6 | | | | | | | |
| 78 | DR-5 | 712+53 | RT | COMM. | 9.50 | 3.00 | 35.0 | 15.0 | 15.0 | | | 15 | | | | | | | | | | | 42.7 | | | |
| | | PARKING | RT | | | | | | | | 2 | | | | | | | | | | | | | | | |
| 78 | DR-6 | 713+39 | LT | COMM. | 9.50 | 13.0 | 35.0 | 5.00 | 15.0 | | | 9 | 2.8 | | 12.8 | | 23.1 | | 2.0 | | | | 36.4 | | | |
| | | PARKING | LT | | | | | | | | 1 | | 0.1 | | 0.7 | | 1.3 | | 0.1 | | | | | | | |
| 78 | DR-7 | 713+18 | RT | COMM. | 9.50 | 3.00 | 35.0 | 15.0 | 15.0 | | | 15 | | | | | | | | | | | 42.7 | | | |
| | | PARKING | RT | | | | | | | | 6 | | | | | | | | | | | | | | | |
| 78 | DR-8 | 713+64 | LT | RES. | 9.50 | 20.0 | 14.0 | 6.00 | 6.00 | | | 1 | | 6.4 | | 8.0 | | 0.7 | | | | | 16.2 | | | |
| TOTALS CARRIED TO GENERAL SUMMARY | | | | | | | | | | 1036 | 33 | 393 | | 55 | | 214 | | 351 | | 33 | | 194 | 1202 | | | |

DRIVEWAY SUBSUMMARY


CAR - 38 - 22.56



PAVEMENT TRANSITION DETAIL

LEGEND

- (1) ITEM 301 - 5" ASPHALT CONCRETE BASE, PG64-22
- (2) ITEM 304 - 6" AGGREGATE BASE
- (3) ITEM 407 - TACK COAT (Applied at a rate of 0.075 gal/yd²)
- (4) NOT USED
- (5) ITEM 408 - PRIME COAT (Applied at a rate of 0.4 gal/yd²)
- (6) ITEM 441 - 1/4" ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (446) PG64-22
- (7) ITEM 441 - 3/4" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (446)
- (A) ± 5" Asphalt
- (B) ± 8" Macadam Base



SECTION A-A

PAVEMENT TRANSITION DETAILS



PIC-46-27.22



CALCULATED
AAM
CHECKED
DEM

PAVEMENT JOINT DETAIL
S.R. 28

LOR-28-0.00



TYPICAL SECTION
OF ADJOINING PAVEMENT
STA. 2+25, S.R. 28

LEGEND

- (L) Standard Longitudinal Joint As Per BP-2.1
- (S) Standard Longitudinal Joint As Per BP-2.1 Without Tie Bars
- (C) Contraction Joint As Per BP-2.2
- (Y) Butt Joint Between Existing Pavement and Proposed Pavement, A Dowelled Type Y Joint As Per BP-2.5 Shall Be Provided. Grouting and Drilling Requirements Shall Be Per Specification 255 and BP-2.5 Except The Requirement That The Drilling Device Shall Be Capable Of Drilling Three Holes At One Time Shall Be Waived.
- (A) 10" Reinforced Concrete Pavement
- (B) 10" Non-Reinforced Concrete Pavement
- (C) 10" Granular Subbase
- (D) Tied Longitudinal Joint




CALCULATED
VHW
CHECKED
TLH

0 20 40
HORIZONTAL
SCALE IN FEET



PAVEMENT JOINT DETAIL
U.S.R. 81 AND S.R. 329

HOC-81-18.58

103
189




TYPICAL SECTION OF
ADJOINING PAVEMENT S.R. 329
Sta. 10+82




TYPICAL SECTION OF
ADJOINING PAVEMENT S.R. 329
Sta. 9+18

LEGEND

- | | |
|---|--|
| (E) Expansion Joint As Per BP-2.2 | (A) 10" Reinforced Concrete Pavement |
| (W) Expansion Joint As Per BP-2.2 Without Dowel Bars | (B) 10" Non-Reinforced Concrete Pavement |
| (L) Standard Longitudinal Joint As Per BP-2.1 | (C) 10" Granular Subbase |
| (S) Standard Longitudinal Joint As Per BP-2.1 Without Tie Bars | (D) Tied Longitudinal Joint |
| (C) Contraction Joint As Per BP-2.2 | (E) Asphalt Concrete Pavement, Depth Unknown |
| (Y) Butt Joint Between Existing Pavement and Proposed Pavement, A Dowelled Type Y Joint As Per BP-2.5 Shall Be Provided. Grouting and Drilling Requirements Shall Be Per Specification 255 and BP-2.5 Except The Requirement That The Drilling Device Shall Be Capable Of Drilling Three Holes At One Time Shall Be Waived. | (F) Aggregate Base, Depth Unknown |




TYPICAL MEDIAN CROSSOVER DETAIL
Applies: Sta. 5+00 and Sta. 124+00



MEDIAN CROSSOVER JOINT DETAIL

NOTES:


1. The above is a suggested joint diagram. The contractor may submit an alternate joint diagram to the Engineer for approval.
2. Align joints in median crossover to form continuous joints with traverse joints in the mainline pavement.



SECTION B-B

LEGEND


- | | |
|---|--|
| ① ITEM 452 - 9" Non-Reinforced Concrete Pavement, Class QCIP, As Per Plan | ⓐ Contraction Joint As Per BP-2.2 |
| ② ITEM 304 - 6" Aggregate Base | ⓓ Not Used |
| ③ ITEM 204 - Subgrade Compaction | ⓔ Expansion Joint (Without Dowels), As Per BP-2.2 |
| ④ ITEM 659 - Seeding And Mulching | Ⓢ Standard Longitudinal Joint, As Per BP 2.1 without Tie Bar 3 |
| | Ⓛ Longitudinal Joint, As Per BP-2.1 |



SECTION A-A

PROPOSED LEGEND


- ① ITEM 254 Pavement Planing, Asphalt Concrete (Depth As Shown)
- ② ITEM 407 Tack Coat
- ③ NOT USED
- ④ ITEM 441 1 1/4" Asphalt Concrete Surface Course, Type 1, (446) PG64-22
- ⑤ ITEM 441 1 3/4" Asphalt Concrete Intermediate Course, Type 1, (446)
- ⑥ ITEM 441 Var. Thickness Asphalt Concrete Surface Course, Type 1, (446) PG64-22
- ⑦ ITEM 441 Var. Thickness Asphalt Concrete Intermediate Course, Type 1, (446)
- ⑧ ITEM 848 1 3/4" Superplasticized Dense Concrete Overlay Using Hydrodemolition



EXISTING LEGEND


- (A) ± 6 1/2" Asphalt Concrete
 - (B) ± 6" Subbase
 - (C) ± 9" Reinforced Portland Cement Concrete Pavement
- = Item 254 Pavement Planing, Asphalt Concrete

PAVEMENT TRANSITION AT BEGIN/END PAVEMENT



TRANSITION AT STRUCTURES

DETAIL APPLIES AT:
VAN-277-0585 Lt. & Rt. (North & South End)
VAN-277-1041 Lt. & Rt. (South Only)
VAN-277-1246 Lt. & Rt. (North Only)




PAVEMENT TRANSITION AT OVERHEAD BRIDGE

DETAIL APPLIES AT STRUCTURES:

- VAN-277-0378 VAN-277-0776
- VAN-277-1234 VAN-277-0911
- VAN-277-1303 VAN-277-0493
- VAN-277-0633

| STRUCTURE | a | b |
|--------------|--------|-------|
| VAN-277-0378 | 144.0' | 72.0' |
| VAN-277-0493 | 160.0' | 80.0' |
| VAN-277-0633 | 166.0' | 83.0' |
| VAN-277-0776 | 165.0' | 82.5' |
| VAN-277-0911 | 179.0' | 89.5' |
| VAN-277-1234 | 155.0' | 77.5' |
| VAN-277-1383 | 156.0' | 78.0' |



PAVEMENT TRANSITION AT OVERHEAD AND MAINLINE BRIDGES

DETAIL APPLIES AT STRUCTURES:


- VAN-277-1047
- VAN-277-1041 (North Side Only)

PROPOSED LEGEND

- ① ITEM 441 1 1/4" Asphalt Concrete Surface Course, Type 1, (446), PG 64-22
- ② ITEM 441 1 3/4" Asphalt Concrete Intermediate Course, Type 2, (446)
- ③ ITEM 441 Var. Thickness Asphalt Concrete Surface Course, Type 2, (446), PG 64-22
- ④ ITEM 441 Var. Thickness Asphalt Concrete Intermediate Course, Type 2, (446)
- ⑤ ITEM 407 Tack Coat
- ⑥ ITEM 848 Micro Silica Modified Concrete using Hydrodemolition (Thickness 1 1/4" Nominal)
- ⑦ ITEM 254 Pavement Planing, Asphalt Concrete (Depth = 2")


EXISTING LEGEND

- (A) ±6 1/2" Asphalt Concrete
- (B) ±6" Subbase
- (C) ±9" Reinforced Portland Cement Concrete Pavement
- ▨ ITEM 254 - Pavement Planing, Asphalt Concrete



* Note: Widen outside shoulder as per plan


PLAN VIEW




SECTION A-A

TRANSITION AT RAMP/CROSSROAD INTERSECTION

DETAIL APPLIES AT:
S.R. 666 Interchange



PLAN VIEW



SECTION B-B

TRANSITION AT REST AREA ENTRANCE/EXIT RAMP DETAIL


PROPOSED LEGEND

- | | |
|--|--|
| (1) ITEM 441 1 1/4" Asphalt Concrete Surface Course, Type 1, (446), PG 64-22 | (5) ITEM 407 Tack Coat |
| (2) ITEM 441 1 3/4" Asphalt Concrete Intermediate Course, Type 2, (446) | (6) ITEM 254 Pavement Planing, Asphalt Concrete (Depth = 2") |
| (3) ITEM 441 Var. Thickness Asphalt Concrete Surface Course, Type 1, (446), PG 64-22 | (7) ITEM 254 Pavement Planing, Asphalt Concrete (Var. Thickness) |
| (4) ITEM 441 Var. Thickness Asphalt Concrete Intermediate Course, Type 2, (446) | |

ITEM 254 Pavement Planing, Asphalt Concrete

EXISTING LEGEND


- (A) ±6 1/2" Asphalt Concrete
(B) ±9" Reinforced Portland Cement Concrete Pavement
(C) ±6" Aggregate Base



CALCULATED
DMK
CHECKED
CML

**GRADING DETAILS
I.R. 73 INTERCHANGE**

HAN-73-19.11






CALCULATED
CHG
CHECKED
LJS


**WEST RAMP TERMINAL DETAILS
STA. 458+00 TO STA. 462+50**

FAI-33-13.25



NOTE: ELEVATIONS SHOWN AT 25' INTERVALS

I:\pr\35\tds\SamplePlans\2011\April\1311\1311_DGN\1311_13.dgn 15-APR-2011 7:54 AM mwawszki



ROUNDABOUT GEOMETRIC LAYOUT


FRA - 62 - 26.34

| REF. LINE | P.I. STATION | P.I. NORTHING | P.I. EASTING | Dc | Δ | T (FT.) | L (FT.) | R (FT.) | BEGIN CURVE | END CURVE |
|-----------|--------------|---------------|--------------|-----------|-----------|---------|---------|---------|-------------|-----------|
| NL | 70+40.53 | 748634.87 | 1872871.53 | 54°03'09" | 28°58'34" | 27.39 | 53.61 | 106.00 | 70+13.14 | 70+66.75 |
| NW | 80+32.67 | 748603.36 | 1872689.89 | 32°44'26" | 21°09'05" | 32.67 | 64.60 | 175.00 | 80+00.00 | 80+64.60 |
| | 81+19.61 | 748614.67 | 1872776.83 | 57°17'45" | 23°17'51" | 20.62 | 40.66 | 100.00 | 80+98.99 | 81+39.65 |
| | 82+02.76 | 748657.43 | 1872848.81 | 76°23'40" | 28°58'32" | 19.38 | 37.93 | 75.00 | 81+83.38 | 82+21.31 |
| WL | 91+25.59 | 748615.56 | 1872530.06 | 14°19'26" | 34°51'45" | 125.59 | 243.39 | 400.00 | 90+00.00 | 92+43.39 |
| | 92+59.84 | 748577.09 | 1872666.79 | 27°48'49" | 09°07'57" | 16.45 | 32.83 | 206.00 | 92+43.39 | 92+76.22 |

| REF. LINE | P.I. STATION | P.I. NORTHING | P.I. EASTING | Dc | Δ | T (FT.) | L (FT.) | R (FT.) | BEGIN CURVE | END CURVE |
|-----------|--------------|---------------|--------------|------------|-----------|---------|---------|---------|-------------|-----------|
| EL | 40+56.33 | 748441.10 | 1872927.68 | 62°57'45" | 59°58'13" | 52.51 | 95.25 | 91.00 | 40+03.82 | 40+99.07 |
| NE | 50+43.68 | 748466.75 | 1872951.54 | 71°37'11" | 57°16'00" | 43.68 | 79.96 | 80.00 | 50+00.00 | 50+79.96 |
| | 51+29.09 | 748547.62 | 1872906.01 | 163°42'08" | 27°30'05" | 8.56 | 16.80 | 35.00 | 51+20.52 | 51+37.32 |
| | 51+94.09 | 748612.92 | 1872903.87 | 38°11'50" | 32°11'22" | 43.28 | 84.27 | 150.00 | 51+50.81 | 52+35.08 |
| NR | 60+58.05 | 748650.93 | 1872890.18 | 31°39'18" | 10°58'01" | 17.38 | 34.64 | 181.00 | 60+40.68 | 60+75.32 |


* CENTER OF ROUNDABOUT
 STA. 446+23.93 @ CONST. MORSE RD. =
 STA. 1406+63.08 @ CONST. U.S.R. 62
 NORTHING= 748520.58
 EASTING= 1872809.34
 RADIUS= 97.50'

| | NORTHING | EASTING |
|-------------------------------|-----------|------------|
| ⓐ 130+84.85 CC = 30+00.00 ER | 748447.66 | 1872874.06 |
| ⓑ 131+37.64 CC = 40+00.00 EL | 748491.44 | 1872902.39 |
| ⓒ 132+53.70 CC = 60+00.00 NR | 748596.15 | 1872870.95 |
| ⓓ 132+92.67 CC = 70+00.00 NL | 748614.17 | 1872836.68 |
| ⓔ 134+19.05 CC = 93+19.85 WL | 748572.28 | 1872726.68 |
| ⓕ 134+66.86 CC = 103+15.26 WR | 748527.25 | 1872712.07 |
| ⓖ 135+73.38 CC = 121+74.46 SL | 748437.30 | 1872758.65 |
| ⓗ 136+11.23 CC = 11+83.64 SR | 748424.30 | 1872793.95 |




| REF. LINE | P.I. STATION | P.I. NORTHING | P.I. EASTING | Dc | Δ | T (FT.) | L (FT.) | R (FT.) | BEGIN CURVE | END CURVE |
|-----------|--------------|---------------|--------------|------------|-----------|---------|---------|---------|-------------|-----------|
| SR | 10+46.08 | 748311.80 | 1872716.20 | 33°30'23" | 21°28'53" | 32.44 | 64.11 | 171.00 | 10+13.64 | 10+77.75 |
| | 11+47.52 | 748401.67 | 1872764.89 | 47°21'07" | 23°38'27" | 25.32 | 49.93 | 121.00 | 11+22.20 | 11+72.12 |
| SE | 20+43.29 | 748419.37 | 1872838.06 | 114°35'30" | 44°08'27" | 20.27 | 38.52 | 50.00 | 20+23.01 | 20+61.53 |
| ER | 30+90.67 | 748433.00 | 1872963.47 | 32°00'32" | 04°13'17" | 6.60 | 13.19 | 179.00 | 30+84.08 | 30+97.26 |


FOR DETAILS "N", "E", "S", "W", "SE" AND "NW" SEE SHEET 4
 FOR U.S.R.62 AND MORSE ROAD DETAILS SEE SHEET 2




DETAIL "N"
NOT TO SCALE




DETAIL "NW"
NOT TO SCALE




DETAIL "S"
NOT TO SCALE



DETAIL "W"
NOT TO SCALE




DETAIL "SE"
NOT TO SCALE





DETAIL "E"
NOT TO SCALE


I:\pr\35\35\SamplePlans\Future Revision\1311\1311_14b.dgn 03-OCT-2006 9:30AM mwawski



| HYDRAULIC DESIGN DATA | |
|--------------------------|-----------|
| Drainage Area | = 28 Ac. |
| Q_{50} | = 22 cfs |
| Q_{100} | = 25 cfs |
| HW_{50} | = 829.7' |
| HW_{100} | = 830.1' |
| V_{50} | = 5.6 fps |
| V_{100} | = 6.1 fps |
| Ordinary High Water Mark | = 827.3' |
| Design Service Life | = 75 Yr. |
| pH | = 7.8 |
| Abrasion Level: 4 | |
| CFN | = 1234567 |



| ESTIMATED QUANTITIES (Carried to General Summary) | |
|---|---------------|
| 601 Rock Channel Protection, Type C, with Filter | = 2.8 Cu.Yd. |
| 601 Riprap using 6" Reinforced | = 2.0 Sq.Yd. |
| 602 Concrete Masonry | = 1.15 Cu.Yd. |
| 611 27" Conduit, Type A, 706.02 | = 183 Ft. |



CALCULATED
DMK
CHECKED
CML


CULVERT DETAILS
U.S. 233 - STA. 572+00

ALL-233-22.69



0 5 10 20
HORIZONTAL SCALE IN FEET

CALCULATED JOH
CHECKED JDH



HYDRAULIC DESIGN DATA


| | |
|--------------------------|------------|
| Drainage Area | = 108 Ac. |
| Q_{25} | = 188 cfs |
| Q_{100} | = 260 cfs |
| HW_{25} | = 815.6' |
| HW_{100} | = 817.6' |
| V_{25} | = 16.0 fps |
| V_{100} | = 18.5 fps |
| ORDINARY HIGH WATER MARK | = 810.3' |
| DESIGN SERVICE LIFE | = 75 YR |
| pH | = 7.5 |
| Abrasion Level: | 3 |
| CFN | = 1234567 |

EXISTING STRUCTURE
 TYPE: STONE ARCH W/72" CMP EXTENSIONS
 SIZE: 6'X5'X58' ARCH
 SKEW: 26° 30' R.F.
 ALIGNMENT: TANGENT
 DATE BUILT: 1908
 CONDITION: POOR
 CFN: 7654321

ESTIMATED QUANTITIES

| ITEM | QUAN | UNIT | DESCRIPTION |
|------|------|------|--|
| 202 | LS | LS | STRUCTURE REMOVED |
| 601 | 60 | CY | ROCK CHANNEL PROTECTION, TYPE A WITH FILTER |
| 601 | 8 | SY | RIPRAP |
| 602 | 5.9 | CY | CONCRETE MASONRY |
| 611 | 184 | FT | 66" CONDUIT, TYPE A, 706.02; OR 78" 707.02 (0.28) GALVANIZED, 707.02 (0.064) ALUMINIZED, 707.03 (0.138) W/CFP, 707.04 (1") (0.064), 707.05 (0.064), 707.07 (0.109) |
| 670 | 72 | SY | DITCH EROSION PROTECTION MAT TYPE C |

QUANTITIES CARRIED TO DRAINAGE SUBSUMMARY, SHEET 37




CULVERT DETAIL
S.R. 437 STA. 158+30

PRE-437-2.65




0 25 50 100
HORIZONTAL SCALE IN FEET


CALCULATED
R/JG
CHECKED
HAG



MATCHLINE STA. 108+50 S.R. 161




CFN = 1234567 (STA. 99+00 TO STA. 107+50)



S.R. 161 DRAINAGE PLAN AND PROFILE
STA. 96+00 TO STA. 108+50

LIC-161-1.83

206
336




CALCULATED MSO
CHECKED PDC

S.R. 166 DRAINAGE PROFILE

RIC-166-8.37



Outlet:
Drainage Area = 4.3 acres
 $Q_{10} = 7.3$ cfs
 $Q_{25} = 8.9$ cfs
HGL₁₀ = 1087.1
HGL₂₅ = 1087.9

Outlet:
Drainage Area = 3.6 acres
 $Q_{10} = 5.8$ cfs
 $Q_{25} = 6.7$ cfs
HGL₁₀ = 1086.8
HGL₂₅ = 1087.6



NOTES




- A. For profile of D-1 & D-2 outlets, see sheet 20.
- B. For profile between D-11 & D13, see sheet 26.
- C. For Abby Rd. drainage profile, see sheet 41.
- D. For drainage sub-summary, see sheets 14-16.
- E. For S.R.166 plan & profile, see sheets 17-19.



CALCULATED
MTC
CHECKED
CJM


LONGITUDINAL SEWER PROFILE

LUC-76-31.48





CALCULATED KEW
CHECKED JOH




| HYDRAULIC DATA | |
|------------------------------------|---------------------|
| DRAINAGE AREA: 0.79 SQ.MI. | |
| EXISTING WATERWAY OPENING: 60.0 SF | |
| PROPOSED WATERWAY OPENING: 70.0 SF | |
| ORDINARY HIGH WATER MARK: 822.9 FT | |
| SFN: 3006914 | |
| DESIGN SERVICE LIFE: 75 YRS | |
| pH: 7.4 | |
| Abrasion Level: 3 | |
| $Q_{10} = 297$ CFS | $Q_{100} = 518$ CFS |
| $V_{10} = 6.9$ FPS | $V_{100} = 7.9$ FPS |
| $HW_{10} = 827.8$ | $HW_{100} = 829.9$ |

EXISTING STRUCTURE

TYPE: CONCRETE SLAB SUPPORTED ON GRAVITY WALL ABUTMENT
 SPAN: 12'-0"
 ROADWAY: 22'-5" F/F RAILS
 ALIGNMENT: CURVE
 APPROACH SLAB: NONE
 SUPERELEVATION: VARIES
 DATE BUILT: 1900
 STRUCTURE FILE NO. 3006514
 SKEW: 0° REFERENCE CHORD
 DISPOSITION: TO BE REPLACED
 LOADING: S-II.3(7)

PROPOSED STRUCTURE

TYPE: PRECAST REINFORCED CONCRETE FLAT-TOPPED THREE-SIDED CULVERT
 SPAN: 14'-0" F/F CULVERT
 ROADWAY: 34'-0" F/F RAILS
 ALIGNMENT: 1°19'11" CURVED TO THE RIGHT
 SUPERELEVATION: VARIES
 APPROACH SLAB: NONE
 SKEW: 0°
 WEARING SURFACE: ASPHALT CONCRETE
 LOADING: HL93
 FUTURE WEARING SURFACE: 60 PSF
 SFN: 3006914



CULVERT PLAN AND PROFILE
STA. 133+13.00

GUE-660-2.52

DESIGN SPECIFICATIONS:

THIS STRUCTURE CONFORMS TO "STANDARD SPECIFICATIONS FOR HIGHWAY BRIDGES" ADOPTED BY THE AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS, 2002 AND THE ODOT BRIDGE DESIGN MANUAL.

DESIGN LOADING:

HS25 AND THE ALTERNATE MILITARY LOADING.

DESIGN STRESSES:

CAST-IN-PLACE STRUCTURES
CONCRETE CLASS "QC MISC." - $f'_c = 4,000$ psi SUBSTRUCTURE
REINFORCING STEEL - ASTM A615, A616, OR A617
 $F_y = 60,000$ psi.

PRECAST STRUCTURES: FOR THREE-SIDED STRUCTURES SEE CULVERT NOTES. FOR BOX AND PIPE CULVERT CMS 611.

REMOVAL OF EXISTING STRUCTURE:

PORTIONS OF THE EXISTING STRUCTURE SHALL BE REMOVED AS INDICATED.

FOUNDATION BEARING PRESSURE:

WINGWALL AND CULVERT FOOTINGS, AS DESIGNED PRODUCE A MAXIMUM BEARING PRESSURE OF 1.5 TONS PER SQUARE FOOT.

THREE-SIDED CULVERT WALL AND TOP SLAB THICKNESS

THE WALL AND TOP SLAB THICKNESSES SHOWN ON THE PLANS WERE OBTAINED FROM THE MANUFACTURERS AT THE TIME THE PLANS WERE PREPARED. IF THE WALL AND/OR TOP SLAB THICKNESS OF THE CULVERT PROPOSED ARE DIFFERENT FROM WHAT IS SHOWN IN THE PLANS, A MARKED COPY OF THE PROJECT PLANS, INCLUDING ALL PLAN NOTES AND DETAILS SHOWING ALL ITEMS AFFECTED BY THE DIFFERENT CULVERT DIMENSIONS, SHALL BE SUBMITTED FOR APPROVAL WITH THE SHOP DRAWINGS. ALL WORK REQUIRED TO ACCOMMODATE ANY REVISED DIMENSIONS SHALL BE AT NO EXTRA COST TO THE STATE.

ITEM 512, TYPE 2 WATERPROOFING


MEMBRANE WATERPROOFING (SHEET TYPE 2) SHALL BE APPLIED TO THE TOP SURFACE OF THE PRECAST CULVERT SECTIONS AND SHALL EXTEND VERTICALLY DOWN ALL SIDES FORTH PORTIONS OF THE CULVERT WHICH SHALL BE IN CONTACT WITH THE BACKFILL. THE EXTERIOR JOINT GAP ON THE TOP AND SIDES BETWEEN THE PRECAST CULVERT SECTIONS SHALL BE FILLED WITH PORTLAND CEMENT MORTAR PRIOR TO INSTALLING THE MEMBRANE WATERPROOFING. JOINT WRAP AS SPECIFIED IN 611.08 AND CONCRETE SEALING AS SPECIFIED IN 611.09 ARE NOT REQUIRED UNDER THE LIMITS OF THE MEMBRANE WATERPROOFING. PAYMENT FOR THE MEMBRANE WATERPROOFING SHALL BE AT THE CONTRACT PRICE BID PER SQUARE YARD FOR ITEM 512, TYPE 2 WATERPROOFING.

PRECAST WINGWALLS, HEADWALLS AND FOOTERS

AT THE OPTION OF THE CONTRACTOR, A PRECAST WINGWALL, HEADWALL, OR FOOTER MAY BE FURNISHED PER ITEM 602. THE PRECAST OPTION FURNISHED WILL MEET THE CAST-IN-PLACE STRUCTURAL DESIGN LOADINGS, DESIGN HEIGHT, AND DESIGN LENGTH DIMENSIONS.

FULL COMPENSATION FOR THE PRECAST WINGWALL, HEADWALL, OR FOOTER IS THE NUMBER OF CUBIC YARDS OF ITEM 511 AND POUNDS OF ITEM 509 FOR THE CORRESPONDING CAST-IN-PLACE STRUCTURE.

WHEN SEALING OF CONCRETE SURFACES (EPOXY) IS SPECIFIED ON THE HEADWALLS OF A PRECAST CONCRETE BOX CULVERT, ANY PRECAST CULVERT SECTIONS BEYOND THE LIMIT OF THE MEMBRANE WATERPROOFING SHALL BE SEALED USING EPOXY SEALER. PAYMENT FOR THE SEALING OF THE PRECAST CONCRETE BOX SURFACES SHALL BE MADE AT THE CONTRACT PRICE BID PER SQUARE YARD FOR ITEM 512 - SEALING OF CONCRETE SURFACES (EPOXY URETHANE).




| GENERAL SUMMARY (GUE - 660 - 2.52) | | | | |
|------------------------------------|-----------|-------|------|--|
| ITEM | ITEM EXT. | TOTAL | UNIT | DESCRIPTION |
| 202 | 11000 | LS | | STRUCTURE REMOVED |
| 503 | 21100 | 67 | CY | UNCLASSIFIED EXCAVATION |
| 509 | 10000 | 6015 | LB | EPOXY COATED REINFORCING STEEL |
| 511 | 46000 | 12 | CY | CLASS QC MISC. CONCRETE, WINGWALL |
| 511 | 46500 | 54 | CY | CLASS QC MISC. CONCRETE, FOOTING |
| 511 | 46600 | 1 | CY | CLASS QC MISC. CONCRETE, MISC. : HEADWALLS |
| 512 | 33000 | 128 | SY | TYPE 2 WATERPROOFING |
| 512 | 10100 | 34 | SY | SEALING OF CONCRETE SURFACES (EPOXY URETHANE) |
| 516 | 13600 | 27 | SF | 1" PREFORMED EXPANSION JOINT FILLER |
| 518 | 21200 | 16 | CY | POROUS BACKFILL WITH FILTER FABRIC |
| 601 | 32100 | 57 | CY | ROCK CHANNEL PROTECTION, TYPE B WITH FILTER |
| 601 | 34200 | 43 | CY | ROCK CHANNEL PROTECTION, TYPE C WITHOUT FILTER |
| 611 | 70000 | 40 | FT | CONDUIT, TYPE A, PRECAST REINFORCED CONCRETE FLAT TOPPED, THREE SIDED CULVERT (14'-0" SPAN X 6'-0" RISE) |

CULVERT ESTIMATED QUANTITIES
STA. 133+13.00

GUE - 660 - 2.52



CALCULATED
KEW
CHECKED
JOH



SEE WINGWALL/FOOTING
KEYWAY DETAIL ON
SHEET 8


1" P.E.J.F. AND
MEMBRANE WATERPROOFING
SHEET TYPE 2
(12" EACH SIDE OF JOINT)

CONSTRUCTION
S.R. 660

SEE SHEET 6 FOR
CULVERT FOOTING DETAIL

(WINGWALL NO. 1)

(WINGWALL NO. 2)



REFERENCE DIAGRAM

| WINGWALL ANGLES | |
|-----------------|---------|
| A1 | 45°0'0" |
| A2 | 45°0'0" |
| A3 | 45°0'0" |
| A4 | 45°0'0" |

CULVERT & WINGWALL LAYOUT


NOTE: SEE TABLE THIS SHEET FOR VALUES OF A1,A2,A3,A4

CULVERT LAYOUT
STA. 133+13.00



GUE-660-2.52

3 / 8


102
125



NOTE: ① - SHORT HAUNCH PRECAST UNIT
② - LONG HAUNCH PRECAST UNIT



INLET HEADWALL REINFORCING DETAIL
(FOR FLAT-TOPPED CULVERTS ONLY)




OUTLET HEADWALL REINFORCING DETAIL
(FOR FLAT-TOPPED CULVERTS ONLY)

CULVERT ELEVATION
STA. 133+13.00

GUE-660-2.52


LEGEND
F.F. - FRONT FACE
R.F. - REAR FACE
B.F. - BOTH FACE




NOTE: 4" DIA. WEEPHOLE
ELEV. = 824.13

WINGWALL 1 ELEVATION

- ① SER. OF 5 @ 1'-6"
- ② 3 SPACES @ 1'-1 3/4"
- ③ 4 SPACES @ 1'-6"




SECTION A-A



SECTION X-X


MECHANICAL CONNECTOR
CONFORM TO 509 OR PARTIAL DEPTH
RESIN BONDED ANCHORS PER STD.
CONST. DWG. GR-2.2. PAYMENT TO BE
INCLUDED WITH ITEM 603



NOTE: 4" DIA. WEEPHOLE
ELEV. = 824.14

WINGWALL 4 ELEVATION


- ① SER. OF 5 @ 1'-6"
- ② 3 SPACES @ 1'-1 3/4"
- ③ 5 SPACES @ 1'-2 1/2"



SECTION B-B

- NOTES:**
1. ITEM 518 - POROUS BACKFILL W/FILTER FABRIC
1'-6" THICK SHALL BE PLACED BEHIND THE WINGWALLS ONLY AND SHALL
EXTEND 1' BELOW THE EMBANKMENT SURFACE. GEOTEXTILE FABRIC SHALL
BE PLACED BETWEEN THE POROUS BACKFILL AND REPLACED EXCAVATION
ADJACENT TO THE STRUCTURE. IT SHALL TURN UNDER THE BOTTOM OF THE
POROUS BACKFILL, AND RETURN 6" ABOVE THE WEEPHOLE.
 2. 1" PREFORMED EXPANSION JOINT FILLER SHALL BE EXTENDED FROM TOP OF
FOOTING TO TOP OF WALL.


LEGEND
F.F. - FRONT FACE
R.F. - REAR FACE
B.F. - BOTH FACE




WINGWALL 2 ELEVATION

NOTE: 4" DIA. WEEPHOLE
ELEV. = 823.65

- ① SER. OF 5 @ 1'-6"
- ② 3 SPACES @ 1'-1"
- ③ 4 SPACES @ 1'-2³/₄"




SECTION D-D




WINGWALL 3 ELEVATION

NOTE: 4" DIA. WEEPHOLE
ELEV. = 823.66

- ① SER. OF 5 @ 1'-6"
- ② 3 SPACES @ 1'-0³/₄"
- ③ 4 SPACES @ 1'-3"



SECTION C-C



CULVERT FOOTING SECTION




CALCULATED
KEW
CHECKED
JOH

FOOTING DETAILS
STA. 133+13.00

GUE-660-2.52


7/8

106
125




FOOTING LAYOUT

SEE TABLE ON SHEET 3 FOR VALUES OF A1 THRU A4




FOOTING REINFORCING PLAN


REINFORCING STEEL LIST




ROCK CHANNEL PROTECTION INSIDE CULVERT



LIMITS OF UNCLASSIFIED EXCAVATION (WINGWALL)




LIMITS OF UNCLASSIFIED EXCAVATION (CULVERT)




TYPE 1

TYPE 2



TYPE 3



TYPE 4

BENDING DIAGRAMS

| MARK | NO. | LENGTH | WEIGHT | TYPE | A | B | C | INCR | REMARKS |
|------------------|------|--------|--------|------|--------|--------|-------|-------|---------|
| WINGWALL 1 | | | | | | | | | |
| W511 | 3 | 9'-9" | 31 | STR | | | | | |
| | 1 | 6'-3" | | | | | | | |
| W512 | S.O. | TO | 40 | STR | | | | 0'-9" | |
| | 5 | 9'-1" | | | | | | | |
| W513 | 16 | 2'-4" | 39 | 2 | 0'-10" | 0'-10" | 1'-2" | | |
| | 2 | 4'-0" | | | | | | | |
| W514 | S.O. | TO | 41 | STR | | | | 2'-7" | |
| | 3 | 9'-1" | | | | | | | |
| W515 | 8 | 9'-1" | 76 | STR | | | | | |
| W516 | 2 | 9'-9" | 20 | 2 | 3'-4" | 7'-11" | 1'-2" | | |
| W611 | 3 | 9'-9" | 44 | STR | | | | | |
| | 1 | 6'-3" | | | | | | | |
| W612 | S.O. | TO | 58 | STR | | | | 0'-9" | |
| | 5 | 9'-1" | | | | | | | |
| W613 | 9 | 9'-0" | 122 | STR | | | | | |
| W614 | 6 | 7'-4" | 66 | STR | | | | | |
| W711 | 14 | 8'-9" | 250 | 3 | 6'-3" | 2'-8" | | | |
| WINGWALL 2 | | | | | | | | | |
| W521 | 3 | 8'-6" | 27 | STR | | | | | |
| | 1 | 5'-2" | | | | | | | |
| W522 | S.O. | TO | 34 | STR | | | | 0'-8" | |
| | 5 | 7'-10" | | | | | | | |
| W523 | 16 | 2'-4" | 39 | 2 | 0'-10" | 0'-10" | 1'-2" | | |
| | 2 | 4'-1" | | | | | | | |
| W524 | S.O. | TO | 41 | STR | | | | 2'-6" | |
| | 3 | 9'-1" | | | | | | | |
| W525 | 8 | 9'-1" | 76 | STR | | | | | |
| W526 | 2 | 9'-8" | 20 | 2 | 3'-2" | 7'-11" | 1'-2" | | |
| W621 | 3 | 8'-6" | 38 | STR | | | | | |
| | 1 | 5'-2" | | | | | | | |
| W622 | S.O. | TO | 49 | STR | | | | 0'-8" | |
| | 5 | 7'-10" | | | | | | | |
| W623 | 9 | 9'-0" | 122 | STR | | | | | |
| W624 | 6 | 7'-4" | 66 | STR | | | | | |
| W721 | 14 | 8'-9" | 250 | 3 | 6'-3" | 2'-8" | | | |
| WINGWALL 3 | | | | | | | | | |
| W531 | 3 | 8'-6" | 27 | STR | | | | | |
| | 1 | 5'-3" | | | | | | | |
| W532 | S.O. | TO | 34 | STR | | | | 0'-8" | |
| | 5 | 7'-10" | | | | | | | |
| W533 | 16 | 2'-4" | 39 | 2 | 0'-10" | 0'-10" | 1'-2" | | |
| | 2 | 4'-0" | | | | | | | |
| W534 | S.O. | TO | 41 | STR | | | | 2'-6" | |
| | 3 | 9'-1" | | | | | | | |
| W535 | 8 | 9'-1" | 76 | STR | | | | | |
| W536 | 2 | 9'-8" | 20 | 2 | 3'-2" | 7'-11" | 1'-2" | | |
| SUBTOTAL | | | 1768 | | | | | | |
| S.O. - SERIES OF | | | | | | | | | |

| MARK | NO. | LENGTH | WEIGHT | TYPE | A | B | C | INCR | REMARKS |
|-------------------------------|------|---------|--------|------|--------|--------|-------|-------|---------|
| W631 | 3 | 8'-6" | 38 | STR | | | | | |
| | 1 | 5'-3" | | | | | | | |
| W632 | S.O. | TO | 49 | STR | | | | 0'-8" | |
| | 5 | 7'-10" | | | | | | | |
| W633 | 9 | 9'-0" | 122 | STR | | | | | |
| W634 | 6 | 7'-4" | 66 | STR | | | | | |
| W731 | 14 | 8'-9" | 250 | 3 | 6'-3" | 2'-8" | | | |
| WINGWALL 4 | | | | | | | | | |
| W541 | 3 | 9'-9" | 31 | STR | | | | | |
| | 1 | 6'-3" | | | | | | | |
| W542 | S.O. | TO | 40 | STR | | | | 0'-8" | |
| | 5 | 9'-1" | | | | | | | |
| W543 | 18 | 2'-4" | 44 | 2 | 0'-10" | 0'-10" | 1'-2" | | |
| | 2 | 4'-1" | | | | | | | |
| W544 | S.O. | TO | 41 | STR | | | | 2'-6" | |
| | 3 | 9'-1" | | | | | | | |
| W545 | 10 | 9'-1" | 95 | STR | | | | | |
| W546 | 2 | 9'-9" | 20 | 2 | 3'-4" | 7'-11" | 1'-2" | | |
| W641 | 3 | 9'-9" | 44 | STR | | | | | |
| | 1 | 6'-3" | | | | | | | |
| W642 | S.O. | TO | 58 | STR | | | | 0'-8" | |
| | 5 | 9'-1" | | | | | | | |
| W643 | 9 | 9'-0" | 122 | STR | | | | | |
| W644 | 6 | 7'-4" | 66 | STR | | | | | |
| W741 | 14 | 8'-9" | 250 | 3 | 6'-3" | 2'-8" | | | |
| CULVERT FOOTING | | | | | | | | | |
| F401 | 56 | 12'-0" | 449 | 1 | 3'-2" | 2'-7" | | | |
| F701 | 32 | 21'-11" | 1434 | STR | | | | | |
| | 1 | 10'-3" | | | 3'-3" | 3'-3" | | | |
| F711 | S.O. | TO | 214 | 2 | TO | TO | 5'-8" | 0'-4" | |
| | 9 | 13'-0" | | | 5'-2" | 5'-2" | | | |
| | 1 | 10'-3" | | | 3'-3" | 3'-3" | | | |
| F721 | S.O. | TO | 214 | 2 | TO | TO | 5'-8" | 0'-4" | |
| | 9 | 13'-0" | | | 5'-2" | 5'-2" | | | |
| | 1 | 10'-3" | | | 3'-3" | 3'-3" | | | |
| F731 | S.O. | TO | 214 | 2 | TO | TO | 5'-8" | 0'-4" | |
| | 9 | 13'-0" | | | 5'-2" | 5'-2" | | | |
| | 1 | 10'-3" | | | 3'-3" | 3'-3" | | | |
| F741 | S.O. | TO | 214 | 2 | TO | TO | 5'-8" | 0'-4" | |
| | 9 | 13'-0" | | | 5'-2" | 5'-2" | | | |
| HEADWALL | | | | | | | | | |
| H501 | 11 | 2'-7" | 30 | 4 | 1'-1" | 0'-8" | 1'-1" | | |
| H502 | 2 | 15'-10" | 33 | STR | | | | | |
| H511 | 11 | 5'-1" | 58 | 4 | 2'-4" | 0'-8" | 2'-4" | | |
| H512 | 2 | 15'-10" | 33 | STR | | | | | |
| SUBTOTAL | | | 4229 | | | | | | |
| TOTAL CARRIED TO SHEET 2 OF 8 | | | | | | | | | |



CALCULATED
MRV
CHECKED
MLC

EXISTING STRUCTURE

TYPE: 48" AND 54" CORRUGATED METAL PIPES
SKEW: 16° L.F.
ALIGNMENT: TANGENT
CFN: 7654321

PROPOSED STRUCTURE



TYPE: 53"X83" ELLIPTICAL CONCRETE PIPE
SKEW: 16° L.F.
ALIGNMENT: TANGENT

HYDRAULIC DESIGN DATA

DRAINAGE AREA: 344 ACRES
Q(25): 230 CFS
HW(25): 666.24 FT
V(25): 11 FT/S
Q(100): 325 CFS
HW(100): 668.81 FT
V(100): 13 FT/S
ORDINARY HIGH WATER MARK: 661.0'
DESIGN SERVICE LIFE: 50 YRS
pH: 6.8
Abrasion Level: 4
CFN: 1234567


ESTIMATED QUANTITIES CARRIED TO GENERAL SUMMARY

| ITEM | QUANTITY | UNIT | DESCRIPTION |
|------|----------|------|---|
| 601 | 9 | CY | ROCK CHANNEL PROTECTION, TYPE B, W/FILTER |
| 602 | 3.3 | CY | CONCRETE MASONRY |
| 611 | 75 | FT | 53" X 83" CONDUIT, TYPE A, 706.04 |



CULVERT DETAIL
STA 781+16.50

JAC-93-14.35



SP 1312-8
DATE: JULY 2018

| END AREA | VOLUME | CALCULATED | RJC | CHECKED | HAG |
|----------|--------|------------|-----|---------|-----|
| | | | | | |
| 40 | 14 | | | | |
| 63 | 24 | | | | |
| 28 | 11 | | | | |
| 63 | 27 | | | | |
| 40 | 18 | | | | |
| 63 | 46 | | | | |
| 189 | 97 | | | | |

CROSS SECTIONS - MINK STREET
STA. 22+00 TO STA. 23+00

LIC+161-1.83

146
336

SEE SHEET 20 FOR NOTES AND QUANTITIES
 ITEM 204 EXCAVATION OF SUBGRADE (1.5')
 ITEM 204 GRANULAR MATERIAL, TYPE B
 ITEM 204 GEOTEXTILE FABRIC

D-19
 CB #3A, A.P.P.
 28.0' LT, +00
 GRATE - 1173.98
 E 6" (N) - 1171.90
 E 12" (W) - 1171.70

D-22
 CB #3A, A.P.P.
 28.0' RT, +00
 GRATE - 1173.98
 E 6" (N) - 1171.90
 E 12" (E) - 1171.27

D-21
 CB #3, (SAG) A.P.P.
 28.0' RT, +50
 GRATE - 1173.93
 E 6" (N) - 1171.80
 E 12" (S) - 1171.80

D-18
 CB #3, (SAG) A.P.P.
 28.0' LT, +50
 GRATE - 1173.93
 E 6" (N) - 1171.83
 E 12" (S) - 1171.70

D-16
 CB #3A, A.P.P.
 28.0' LT, +00
 GRATE - 1174.00
 E 12" (N) - 1170.80
 E 15" (E) - 1170.45
 E 18" (S) - 1170.30

D-20
 CB #3A, A.P.P.
 28.0' RT, +00
 GRATE - 1174.00
 E 12" (N) - 1170.91
 E 15" (W) - 1170.66

1171.58
 41.7' LT.
 HW-2.1 OR 2.2

1171.17
 42.7' RT
 HW-2.1 OR 2.2

42.9' LT.
 1171.21

42.7' RT.
 1171.70

43.1' LT.
 1170.90

43.5' RT.
 1170.95

44.8' LT.
 1170.60

44.0' RT.
 1170.72

1174.60
 STA. 23+00
 1174.26

1174.55
 STA. 22+50
 1174.00

1174.62
 STA. 22+00
 1173.91

14'-12" TYPE C
 @ 0.86%

15'-12" TYPE C
 @ 0.67%

55'-15" TYPE B @ 0.38%
 CFN = 1234567



ITEM 204 EXCAVATION OF SUBGRADE (1.5')
 ITEM 204 GRANULAR MATERIAL, TYPE B
 ITEM 204 GEOTEXTILE FABRIC

ITEM 204 EXCAVATION OF SUBGRADE (1.5')
 ITEM 204 GRANULAR MATERIAL, TYPE B
 ITEM 204 GEOTEXTILE FABRIC

ITEM 204 EXCAVATION OF SUBGRADE (1.5')
 ITEM 204 GRANULAR MATERIAL, TYPE B
 ITEM 204 GEOTEXTILE FABRIC

SEE SHEET 20 FOR NOTES AND QUANTITIES
 ITEM 204 EXCAVATION OF SUBGRADE (1.5')
 ITEM 204 GRANULAR MATERIAL, TYPE B
 ITEM 204 GEOTEXTILE FABRIC

For Roadway and Drainage Details
See Plan and Profile Sheets 10-14.
For Storm Sewer Profiles See Sheet 17.



| STATION | | SIDE | | TOTALS CARRIED TO GENERAL SUMMARY | | | | | | | |
|-----------------------------------|---------|---------|-------|-----------------------------------|----|---|----|---|---|---|---|
| REF NO. | FROM TO | FROM TO | RT LT | | | | | | | | |
| WW-7 | 13+66 | 13+70 | RT | | | | | | | | |
| WW-8 | 13+67 | 13+70 | RT | | | | | | | | |
| WW-9 | 13+88 | 16+07 | RT | 235 | | | | | | | |
| WW-10 | 14+65 | 15+01 | RT | 36 | | | | | | | |
| WW-11 | 16+00 | | RT | | | | | | | | |
| WW-12 | 16+08 | | RT | 1 | | | | | | | |
| WW-13 | 16+20 | | LT | 15 | | | | | | | |
| TOTALS CARRIED TO GENERAL SUMMARY | | | | 250 | 36 | 1 | 30 | 1 | 1 | 1 | 1 |

SP. 1313-1
DATE: OCTOBER 2006




CALCULATED GJB
CHECKED DJK


WATER WORK PLAN
STA. 12+50 TO STA. 16+00

CUY-CR123-6.55


I:\pr\35\tds\SamplePlans\2006October\1313\1313-1.dgn 15-APR-2011 7:39AM mwawski




DETAIL "A"
 EXISTING WATER MAIN RELOCATION
 UNDER PROPOSED UTILITY LINE
 (ELEVATION)




DETAIL "B"
 TYPICAL 2" OR LESS SERVICE CONNECTION
 (ELEVATION)




DETAIL "C"
 HYDRANT ASSEMBLY
 PERPENDICULAR TO WATER
 (ELEVATION)



DETAIL "D"
 HYDRANT ASSEMBLY
 PARALLEL TO WATER MAIN
 (ELEVATION)




DETAIL "E"
 FIRE HYDRANT EXTENDED AND ADJUSTED TO GRADE
 (PLAN)



| TYPE | SIZE | CROSS | | WYE | |
|------------------|------|-------|-----|-----|-----|
| | | A | B | A | B |
| 2000 P.S.F. SOIL | 6" | 11" | 13" | 10" | 12" |
| | 8" | 15" | 17" | 14" | 14" |
| | 10" | 18" | 22" | 15" | 20" |
| | 12" | 21" | 26" | 18" | 23" |
| | 14" | 24" | 30" | 21" | 27" |
| | 16" | 28" | 33" | 24" | 30" |
| | 20" | 33" | 42" | 27" | 43" |
| | 24" | 40" | 49" | 32" | 50" |

*6" OR LESS
 NOTE: BASED ON 150 P.S.I. STATIC PRESSURE PLUS A.W.W.A. WATER HAMMER.
 ALL BEARING SURFACES TO BE CARRIED TO UNDISTURBED GROUND.



| TYPE | SIZE | 90° BENDS | | 45° BENDS | | 22-1/2° & 11-1/4° BENDS | | TEES | | PLUGS | |
|------------------|------|-----------|-----|-----------|-----|-------------------------|-----|------|-----|-------|-----|
| | | A | B | A | B | A | B | A | B | C | D |
| 2000 P.S.F. SOIL | 6" | 18" | 11" | 10" | 11" | 6" | 9" | 11" | 13" | 10" | 24" |
| | 8" | 25" | 14" | 14" | 14" | 9" | 11" | 15" | 17" | 12" | 32" |
| | 10" | 27" | 20" | 16" | 19" | 10" | 15" | 18" | 22" | 14" | 40" |
| | 12" | 33" | 23" | 18" | 23" | 12" | 18" | 21" | 26" | 16" | 47" |
| | 14" | 39" | 26" | 22" | 26" | 13" | 22" | 24" | 30" | 18" | 54" |
| | 16" | 43" | 30" | 24" | 30" | 14" | 26" | 28" | 33" | 20" | 61" |
| | 20" | 50" | 39" | 27" | 39" | 17" | 32" | 33" | 42" | 24" | 74" |
| | 24" | 60" | 45" | 33" | 45" | 20" | 38" | 40" | 49" | 28" | 88" |

NOTE: BASED ON 150 P.S.I. STATIC PRESSURE PLUS A.W.W.A. WATER HAMMER.
 ALL BEARING SURFACES TO BE CARRIED TO UNDISTURBED GROUND.
 *6" OR LESS

I:\pr\351ids\SamplePlans\Future Revision\1313\1313_2.dgn 03-OCT-2006 9:31AM mwawski

| SHEET NO. | REFERENCE NO. | LOCATION | STATION | | SIDE | 202 | | | 621 | | | 642 | | | | | | |
|--|---------------|-------------------|---------|-------|-------|--------------------------------|--------------------|-------------------|-------------------|---------------------------|------------------------------------|---------------------------|-------------------|--------------------|-------------------------------|---------------------------------|-----|--|
| | | | FROM | TO | | RAISED PAVEMENT MARKER REMOVED | RPM (2-way yellow) | RPM (1-way white) | EDGE LINE (White) | EDGE LINE, TYPE 1 (White) | CENTER LINE, TYPE 1 (Dashed-Solid) | CHANNELIZING LINE, TYPE 1 | STOP LINE, TYPE 1 | LANE ARROW, TYPE 1 | WORD ON PAVEMENT, 96", TYPE 1 | ISLAND MARKING, TYPE 1 (Yellow) | | |
| | | | EACH | EACH | | EACH | MILE | MILE | MILE | FT | FT | EACH | EACH | SQ FT | | | | |
| 56 | CL-1 | Const. S.R. 17 | 46+73 | 48+00 | RT. | 7 | 7 | | | | 0.024 | | | | | | | |
| 56 | CL-2 | Const. S.R. 17 | 47+90 | 48+47 | LT. | | 2 | | | | 0.010 | | | | | | | |
| 56 | CL-3 | Const. S.R. 17 | 48+00 | 48+47 | RT. | 2 | 11 | | | | 0.009 | | | | | | | |
| 56 | CL-4 | Const. S.R. 17 | 48+47 | 53+00 | LT. | | 11 | | | | 0.086 | | | | | | | |
| 56 | CL-5 | Const. S.R. 17 | 48+47 | 53+00 | RT. | 11 | 6 | | | | 0.086 | | | | | | | |
| 57 | CL-6 | Const. S.R. 17 | 53+00 | 55+48 | LT. | 6 | 6 | | | | 0.047 | | | | | | | |
| 57 | CL-7 | Const. S.R. 17 | 53+00 | 55+48 | RT. | | 12 | | | | 0.047 | | | | | | | |
| 57 | CL-8 | Const. S.R. 17 | 55+48 | 57+86 | LT. | 12 | | | | | 0.045 | | | | | | | |
| 57 | CL-9 | Const. S.R. 17 | 55+48 | 56+00 | RT. | | 3 | | | | 0.011 | | | | | | | |
| 57 | CL-10 | Const. S.R. 17 | 58+68 | 59+25 | RT. | 3 | 4 | | | | 0.011 | | | | | | | |
| 57 | CL-11 | Const. MEYERS RD. | 10+40 | 11+15 | CL | 4 | 5 | | | | 0.014 | | | | | | | |
| 57 | CL-12 | Const. MEYERS RD. | 8+55 | 9+41 | CL | 5 | 6 | | | | 0.016 | | | | | | | |
| 58 | CL-13 | Const. S.R. 17 | 59+25 | 60+39 | RT. | 6 | 1 | | | | 0.022 | | | | | | | |
| 58 | CL-14 | Const. S.R. 17 | 64+16 | 65+00 | CL | 1 | 1 | | | | 0.016 | | | | | | | |
| 58 | CL-15 | Const. S.R. 17 | 65+00 | 65+66 | CL | 2 | | | | | 0.013 | | | | | | | |
| 56 | EL-1 | Const. RAMP A | 10+25 | 10+65 | RT. | 2 | | | 0.009 | | | | | | | | | |
| 56 | EL-2 | Const. S.R. 17 | 45+52 | 48+00 | LT. | 12 | 2 | | | 0.047 | | | | | | | | |
| 56 | EL-3 | Const. S.R. 17 | 45+30 | 48+00 | RT. | 14 | 12 | | | 0.051 | | | | | | | | |
| 56 | EL-4 | Const. RAMP B | 9+18 | 9+75 | RT. | 3 | 14 | | 0.011 | | | | | | | | | |
| 56 | EL-5 | Const. S.R. 17 | 48+00 | 53+00 | LT. | 14 | 3 | | | 0.095 | | | | | | | | |
| 56 | EL-6 | Const. S.R. 17 | 48+00 | 53+00 | RT. | 14 | 14 | | | 0.095 | | | | | | | | |
| 57 | EL-7 | Const. MEYERS RD. | 53+00 | 11+00 | LT. | 24 | 14 | | | 0.113 | | | | | | | | |
| 57 | EL-8 | Const. MEYERS RD. | 53+00 | 8+55 | RT. | 23 | 24 | | | 0.111 | | | | | | | | |
| 57 | EL-9 | Const. MEYERS RD. | 11+15 | 59+25 | LT. | 8 | 23 | | | 0.029 | | | | | | | | |
| 57 | EL-10 | Const. MEYERS RD. | 8+55 | 59+25 | RT. | 11 | 8 | | | 0.041 | | | | | | | | |
| 58 | EL-11 | Const. S.R. 17 | 59+25 | 65+00 | LT. | 21 | 11 | | | 0.109 | | | | | | | | |
| 58 | EL-12 | Const. S.R. 17 | 59+25 | 65+00 | RT. | 16 | 22 | | | 0.109 | | | | | | | | |
| 58 | EL-13 | Const. S.R. 17 | 65+00 | 65+66 | LT. | 1 | 29 | | | 0.013 | | | | | | | | |
| 58 | EL-14 | Const. S.R. 17 | 65+00 | 65+66 | RT. | 1 | | | | 0.013 | | | | | | | | |
| 56 | CH-1 | Const. S.R. 17 | 45+52 | 47+70 | LT. | | | | | | 218 | | | | | | | |
| 57 | CH-2 | Const. S.R. 17 | 56+20 | 57+86 | RT. | | 11 | | | | 166 | | | | | | | |
| 57 | CH-3 | Const. S.R. 17 | 58+68 | 59+25 | LT. | | 9 | | | | 57 | | | | | | | |
| 58 | CH-4 | Const. S.R. 17 | 59+25 | 60+20 | LT. | | 3 | | | | 95 | | | | | | | |
| 56 | IM-1 | Const. S.R. 17 | 44+51 | 45+09 | RT. | | 5 | | | 0.019 | 110 | | | | | | | |
| 56 | IM-2 | Const. S.R. 17 | 45+52 | 46+73 | RT. | 6 | 6 | | | 0.046 | 10 | | | | | | | |
| 58 | IM-3 | Const. S.R. 17 | 60+39 | 64+16 | LT&RT | 11 | 12 | | | 0.143 | | | | | | | | |
| 56 | SL-1 | Const. RAMP A | 10+28 | | LT&RT | | 19 | | | | | 29 | | | | | | |
| 56 | SL-2 | Const. S.R. 17 | 50+07 | 50+27 | LT. | | | | | | | 20 | | | | 108 | | |
| 57 | SL-3 | Const. MEYERS RD. | 9+41 | | LT. | | | | | | | 12 | | | | 26 | | |
| 57 | SL-4 | Const. MEYERS RD. | 10+40 | | RT. | | | | | | | 14 | | | | 255 | | |
| 56 | | Const. S.R. 17 | 45+62 | | | | | | | | | 2 | | | | | | |
| 56 | | Const. S.R. 17 | 46+62 | | | | | | | | | | 2 | | 2 | | | |
| 56 | | Const. S.R. 17 | 47+60 | | | | | | | | | | 2 | | | | | |
| 56 | | Const. S.R. 17 | 52+11 | | | | | | | | | | 1 | | | | | |
| 56 | | Const. S.R. 17 | 52+25 | | | | | | | | | | 1 | | | | | |
| 57 | | Const. S.R. 17 | 56+98 | | | | | | | | | | | 1 | | | | |
| 57 | | Const. S.R. 17 | 56+20 | | | | | | | | | | | 1 | | | | |
| 57 | | Const. S.R. 17 | 57+76 | | | | | | | | | | | 1 | | | | |
| 57 | | Const. S.R. 17 | 58+78 | | | | | | | | | | | 1 | | | | |
| SUBTOTALS | | | | | | 240 | | 112 | 204 | 0.020 | | 0.663 | 656 | 75 | 9 | 3 | 389 | |
| TOTALS CARRIED TO GENERAL SUMMARY | | | | | | 240 | | 316 | | 0.84 | | 0.66 | 656 | 75 | 9 | 3 | 389 | |

PAVEMENT MARKING SUBSUMMARY


UNI-17-3.14



CALCULATED
DAM
CHECKED
JAG

SIGN AND PAVEMENT MARKING PLAN

UNI-17-3.14





LEGEND











- Proposed Sign
- Existing Sign to Remain (Relocations Noted in Plans)
- X Existing Sign to be Removed

SEE SHEET 57 FOR ISLAND MARKING DETAIL

I:\pr\355ids\SamplePlans\Future Revision\1314\1314_3.dgn 03-OCT-2006 9:31AM mwawski



LEGEND


-  PROPOSED GUARDRAIL
-  SUB-SUMMARY REFERENCE NUMBER
-  LIGHTING CIRCUIT
-  CONDUIT OR DUCT CABLE (AS LABELED)
-  WITH CONDUCTORS (AS INDICATED)
-  CATCH BASIN, PIPE AND HEADWALL
-  LIGHT POLE AND LUMINAIRE, INITIAL INSTALLATION
-  CONTROL CENTER
-  PULL BOX
-  CIRCUIT STUB AND CAP

POLE LEGEND

| TYPE OF LUMINAIRE | STATION | | OFFSET | | CIRCUIT NUMBER | POLE NUMBER | POLE REF NO. |
|-------------------|----------------------|----------------|--------------------|--|----------------|-------------|--------------|
| | WATTAGE OF LUMINAIRE | SUPPORT HEIGHT | BRACKET ARM LENGTH | | | | |
| | | | | | | | |



CALCULATED
RMM
CHECKED
CWR



MATCH LINE STA. 360+00

LIGHTING PLAN
STA. 345+50 TO STA. 360+00


CHP - 44 - 11.29

FOR LEGEND, SEE SHEET 264.
FOR QUANTITIES, SEE SHEET 267.

| REFERENCE NUMBER | SHEET No. | SIDE | ROADWAY | STATION TO STATION | 625 | | | | | | | | | | | | | | | | | Ground Rod | Structure Grounding System | Plastic Caution Tape |
|---|-----------|------|---------|--------------------|---|--|----------------------------|----------------------------|--------------------------------------|-----------------------|-------------|---------------------|---------------------|-------------------------------------|---------------------------------|---|------------------------------|--------------------------------|----------------------------|-------------------------------|----------------------------|------------|----------------------------|----------------------|
| | | | | | Luminaire, Style B, Type II, 200 W H.P.S., 480V | Luminaire, Style B, Type III, 200 W H.P.S., 480V | Light Pole, Design AT15B40 | Light Pole, Design AT20B40 | Light Pole Foundation, 24" x 8' Deep | Pull Box, 725.08, 18" | Trench, 24" | Conduit, 2", 725.04 | Conduit, 3", 725.04 | No. 4 AWG 5000 V Distribution Cable | No. 10 AWG Pole & Bracket Cable | 1/2" Duct Cable W/3 No. 4 AWG 5000 V Cables | Connection, Fused Pull-Apart | Connection, Unfused Pull-Apart | Connection, Unfused Bolted | Connection, Unfused Permanent | Power Service, As Per Plan | | | |
| | | | | | EACH | EACH | EACH | EACH | EACH | FT | FT | FT | FT | FT | FT | EACH | EACH | EACH | EACH | EACH | EACH | FOOT | | |
| SHEET 269 | | | | | | | | | | | | | | | | | | | | | | | | |
| 1 | 269 | L† | US-44 | 346+82 | | 1 | | 1 | 1 | | | | | | 124 | | 2 | | | | | | | |
| 2 | 269 | L† | US-44 | 346+82 to 349+44 | | | | | | 262 | | | | | | | | | | 1 | | 262 | | |
| 3 | 269 | L† | US-44 | 349+44 | | | | | | | | | | | | | | | | | | | | |
| 4 | 269 | L† | US-44 | 349+44 to 349+73 | | | | | | | | | | | | | | | | | | | | |
| 5 | 269 | L† | US-44 | 349+73 | | | | | | | | | | | | | | | | | | | | |
| 6 | 269 | L† | US-44 | 349+73 to 350+12 | | | | | | 39 | | | | | | | | | | | | | 39 | |
| 7 | 269 | L† | US-44 | 350+12 | | 1 | | 1 | 1 | | | | | | 124 | | 2 | | | | | | | |
| 8 | 269 | L† | US-44 | 350+12 to 353+17 | | | | | | 305 | | | | | | | | | | | 1 | | 305 | |
| 9 | 269 | L† | US-44 | 353+17 | | 1 | | 1 | 1 | | | | | | 124 | | 2 | | | | | | | |
| 10 | 269 | L/R | 44/D | 353+17 to 554+20 | | | | | | 212 | | | 146 | | | | | | | | 1 | | 212 | |
| 11 | 269 | R† | US-44 | 347+89 | | 1 | | 1 | 1 | | | | | | 124 | | 2 | | | | | | | |
| 12 | 269 | R† | US-44 | 347+89 to 348+51 | | | | | | 62 | | | | | | | | | | | 1 | | 62 | |
| 13 | 269 | R† | US-44 | 348+51 | | | | | | | | | | | | | | | | | | | | |
| 14 | 269 | R† | US-44 | 348+51 to 348+80 | | | | | | | | | | | | | | | | | | | | |
| 15 | 269 | R† | US-44 | 348+80 | | | | | | | | | | | | | | | | | | | | |
| 16 | 269 | R† | 44/D | 348+80 to 554+20 | | | | | | 540 | | | | | | | | | | | | | 540 | |
| 17 | 269 | R† | RAMP D | 554+20 | | 1 | | 1 | 1 | | | | | | 124 | | 1 | 1 | 2 | | | | | |
| 18 | 269 | R† | RAMP D | 554+20 to 556+15 | | | | | | 195 | | | | | | | | | | | 1 | | 195 | |
| 19 | 269 | R† | RAMP D | 556+15 | | 1 | | 1 | 1 | | | | | | 114 | | 1 | 1 | 2 | | | | | |
| 20 | 269 | R† | 44/D | 355+62 to 556+15 | | | | | | 85 | | | 39 | | | | | | | | 1 | | 85 | |
| 21 | 269 | R† | US-44 | 355+62 | | 1 | | 1 | 1 | | | | | | 124 | | 2 | | | | | | | |
| 22 | 269 | R† | RAMP D | 556+15 to 560+30 | | | | | | 415 | | | | | | | | | | | 1 | | 415 | |
| SHEET 270 | | | | | | | | | | | | | | | | | | | | | | | | |
| 23 | 270 | R† | SR-402 | 54+90 | | 1 | | 1 | 1 | | | | | | 114 | | 2 | | | | | | | |
| 24 | 270 | L/R | SR-402 | 53+88 to 54+90 | | | | | | 188 | | | 97 | | | | | | | | 1 | | 188 | |
| 25 | 270 | L† | SR-402 | 53+88 | | 1 | | 1 | 1 | | | | | | 124 | | 2 | | | | | | | |
| 26 | 270 | L† | SR-402 | 51+32 to 53+88 | | | | | | 256 | | | | | | | | | | | | | 256 | |
| 27 | 270 | L† | SR-402 | 51+32 | | | | | | | | | | | | | | | | | | | | |
| 28 | 270 | L† | SR-402 | 48+78 to 51+32 | | | | | | 20 | 254 | | 792 | | | | | | | | | 1 | 20 | |
| 29 | 270 | L† | SR-402 | 48+78 | | | | | | | | | | | | | | | | | | | | |
| 30 | 270 | L† | 128/402 | 45+10 to 48+78 | | | | | | 368 | | | 80 | | | | | | | | | | 368 | |
| 31 | 270 | L/R | D/128 | 560+30 to 45+20 | | | | | | 660 | | | | | | | | | | | | | 660 | |
| 32 | 270 | R† | SR-402 | 46+22 | | 1 | | 1 | 1 | | | | | | 114 | | 2 | | | | | | | |
| 33 | 270 | L/R | 128/402 | 45+10 to 46+22 | | | | | | 170 | | | 115 | | | | | | | | 1 | | 170 | |
| 34 | 270 | R† | 128/C | 45+20 to 475+86 | | | | | | 1030 | | | | | | | | | | | | | 1030 | |
| 35 | 270 | L† | CR-128 | 45+10 | | 1 | | 1 | 1 | | | | | | 114 | | 1 | 1 | 2 | | | | | |
| 36 | 270 | L† | CR-128 | 44+10 to 45+10 | | | | | | 100 | | | | | | | | | | | | | 100 | |
| 37 | 270 | L† | CR-128 | 44+10 | | | | | | | | | | | | | | | | | | | | |
| 38 | 270 | L† | CR-128 | 44+10 to 45+20 | | | | | | 110 | | | | | | | | | | | | | 110 | |
| 39 | 270 | L/R | CR-128 | 44+10 to 45+20 | | | | | | 159 | | | 49 | | | | | | | | | | 159 | |
| 40 | 270 | L† | RAMP B | 275+49 | | 1 | | 1 | 1 | | | | | | 114 | | 2 | | | | | | | |
| 41 | 270 | L† | USR-44 | 357+98 | | | | | | | | | | | | | | | | | | | | |
| 42 | 270 | L† | RAMP B | 275+49 to 276+01 | | | | | | 52 | | | | | | | | | | | 1 | | 52 | |
| 43 | 270 | L/R | B/44 | 275+49 to 357+98 | | | | | | 83 | | | 83 | | | | | | | | | | 83 | |
| SUBTOTALS CARRIED TO GENERAL SUMMARY | | | | | 6 | 7 | 5 | 8 | 13 | 6 | 5311 | 312 | 609 | 1026 | 1562 | 5471 | 23 | 3 | 6 | 12 | 1 | 13 | 1 | 5311 |

LIGHTING PLAN SUB-SUMMARY


CHP - 44 - 11.29



CALCULATED
MTG
CHECKED
CJM

LANDSCAPING PLAN


LUC-73-3.93



15'- 'NO TREE PLANTING' ZONE
FOR CLEARANCE TO CSP
DISTRIBUTION LINES.


SUB-SUMMARY

| ITEM | UNIT | DESCRIPTION | QTY. | KEY | COMMON NAME | COND. |
|------|------|---|------|-----|---------------------------------|--------------|
| 661 | Each | DECIDUOUS TREE, (1½"- 2" cal.), (ACER PLATANOSE) | 26 | Ap | Swedish Maple | B&B 20" min. |
| 661 | Each | DECIDUOUS TREE, (1½"- 2" cal.), (ACER REDUNDIS) | 5 | Ar | Secondary Maple | B&B 20" min. |
| 661 | Each | DECIDUOUS TREE, (1-1½" cal.), (CRATAEGUS ABRAHANUM) | 37 | Ca | Lincoln Hawthorn | B&B 16" min. |
| 661 | Each | EVERGREEN TREE, (4'-5' h.), (PINUS NUDISTFUNDIS) | 208 | Pn | Bare Cone Pine | B&B 14" min. |
| 661 | Each | DECIDUOUS TREE, (1½"- 2" cal.), (QUERCUS REDRUM) | 28 | Qr | Dead Oak | B&B 20" min. |
| 661 | Acre | PLANTING, MISC. | 5.43 | | Wildflower Seeding and Mulching | |




**SIGNAL SUPPORT SP-1
ELEVATION VIEW**

STA 898+69.9, 43' LT
LOOKING SOUTH




**SIGNAL SUPPORT SP-4
ELEVATION VIEW**

STA 899+60.6, 49' RT
LOOKING NORTH




**SIGNAL SUPPORT SP-2
ELEVATION VIEW**

STA 550+43.4, 48' RT
LOOKING EAST




**SIGNAL SUPPORT SP-3
ELEVATION VIEW**

STA 49+65.1, 43' LT
LOOKING WEST




| SUPPORT NO. | MAST ARM INDEX ANGLE | ORIENTATION ANGLES (DEG.) FROM MAST ARM | | | | | |
|-------------|----------------------|---|------------|----------|------------|------------|-------------------|
| | | POWER SERVICE | CONTROLLER | HANDHOLE | 3" CONDUIT | 2" CONDUIT | 2" CAPPED CONDUIT |
| SP-1 | 0° | | | 180° | 270° | 90° | |
| SP-2 | 0° | | | 180° | 283° | 180° | |
| SP-3 | 0° | | | 180° | 240° | 90° | |
| SP-4 | 0° | 90° | | 180° | 180° | 90° | |

I:\pr\35\tds\SamplePlans\2011\July\DGN\1314-13.dgn 13-JUL-2011 12:19PM mwawski



*** NOTES**
MAINTAIN THE EXISTING PAVEMENT
CROSS SLOPE. SHOULDER WIDTH
MAY VARY NEAR EXISTING RAMPS
AND CROSSOVERS.




LEGEND

- ① ITEM 254 - 1/2" PAVEMENT PLANING, ASPHALT CONCRETE
- ② ITEM 407 - TACK COAT
- ③ ITEM 441 - 1/2" ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (446), PG 64-22
- ④ ITEM 408 - PRIME COAT @ 0.4 GALLONS PER SQ. YD.
- ⑤ ITEM 617 - COMPACTED AGGREGATE


RESURFACING

MRW-71-3.17


CROSSOVER DETAIL



PARTIAL DEPTH PAVEMENT REPAIR AS PER PLAN









SHOULDER DETAIL



| LOCATION | | | | | PAVEMENT WIDTH | | | | | | | QUANTITIES | | | | | | REMARKS |
|-------------------------------------|-------|-------|-------|---------|----------------|------------------|----------|-----------------|-----------------|----------|------------------|------------------------------------|---------------|---------------------------------------|---|-------------------|---------------------------------|------------------------------|
| COUNTY | ROUTE | S L M | S L M | TYPICAL | NORTHBOUND | | | | SOUTHBOUND | | | 254 | 407 | 408 | 441 | 617 | 618 | REMARKS |
| | | | | | LENGTH | OUTSIDE SHOULDER | PAVEMENT | MEDIAN SHOULDER | MEDIAN SHOULDER | PAVEMENT | OUTSIDE SHOULDER | PAVEMENT PLANING, ASPHALT CONCRETE | TACK COAT | PRIME COAT (0.4 GAL/YD ²) | ASPHALT SURFACE COURSE, TYPE 1, (446), PG 64-22 | COMPACT AGGREGATE | RUMBLE STRIP (ASPHALT CONCRETE) | |
| | | | | | FT | FT | FT | FT | FT | FT | 1/2" DEPTH SY | GAL | GAL | 1/2" DEPTH CY | 2" DEPTH CY | FT | | |
| MRW | 71 | 3.17 | 12.07 | 1 | 46,992' | 10' | 24' | 5' | | | | 203,632 | 15,272 | 8,354 | 8,485 | 1,161 | 93,984 | MAINLINE (SOUTH OF SR-95) |
| MRW | 71 | 3.17 | 12.36 | 1 | 48,523' | | | | 5' | 24' | 10' | 210,267 | 15,770 | 8,626 | 8,761 | 1,198 | 97,046 | MAINLINE (SOUTH OF SR-95) |
| MRW | 71 | 13.44 | 19.38 | 1 | 31,363' | 10' | 24' | 5' | | | | 135,907 | 10,193 | 5,576 | 5,663 | 775 | 62,726 | MAINLINE (NORTH OF SR-95) |
| MRW | 71 | 13.57 | 19.38 | 1 | 30,677' | | | | 5' | 24' | 10' | 132,933 | 9,970 | 5,454 | 5,539 | 758 | 61,354 | MAINLINE (NORTH OF SR-95) |
| MRW | 71 | 10.99 | 11.14 | 1 | 792' | 10' | 32'* | | | | | 3,696 | 277 | | 154 | | | EXTRA AREA (RAMP TAPER) |
| MRW | 71 | 11.39 | 11.70 | 1 | 1,637' | 10' | 32'* | | | | | 7,638 | 573 | | 318 | | | EXTRA AREA (RAMP TAPER) |
| MRW | 71 | 11.33 | 11.48 | 1 | 792' | | | | | 32'* | 10' | 3,696 | 277 | | 154 | | | EXTRA AREA (RAMP TAPER) |
| MRW | 71 | 10.75 | 11.06 | 1 | 1,637' | | | | | 32'* | 10' | 7,638 | 573 | | 318 | | | EXTRA AREA (RAMP TAPER) |
| MRW | 71 | 4.41 | | | | | | | | | | 340 | 25 | | 14 | | | * AVERAGE PAVEMENT WIDTH |
| MRW | 71 | 6.67 | | | | | | | | | | | | | 10 | | | EXTRA AREA (PAVED CROSSOVER) |
| MRW | 71 | 7.40 | | | | | | | | | | 340 | 25 | | 14 | | | GRAVEL CROSSOVER |
| MRW | 71 | 10.37 | | | | | | | | | | 340 | 25 | | 14 | | | EXTRA AREA (PAVED CROSSOVER) |
| MRW | 71 | 11.98 | | | | | | | | | | 340 | 25 | | 14 | | | EXTRA AREA (PAVED CROSSOVER) |
| MRW | 71 | 13.63 | | | | | | | | | | 340 | 25 | | 14 | | | EXTRA AREA (PAVED CROSSOVER) |
| MRW | 71 | 14.67 | | | | | | | | | | | | | 10 | | | GRAVEL CROSSOVER |
| MRW | 71 | 15.06 | | | | | | | | | | | | | 10 | | | GRAVEL CROSSOVER |
| MRW | 71 | 15.60 | | | | | | | | | | | | | 10 | | | GRAVEL CROSSOVER |
| MRW | 71 | 16.75 | | | | | | | | | | 340 | 25 | | 14 | | | EXTRA AREA (PAVED CROSSOVER) |
| MRW | 71 | 17.52 | | | | | | | | | | | | | 10 | | | GRAVEL CROSSOVER |
| MRW | 71 | 18.03 | | | | | | | | | | | | | 10 | | | GRAVEL CROSSOVER |
| MRW | 71 | 5.96 | 6.01 | | 255' | 10' | 24' | 5' | 5' | 24' | 10' | -2,210 | -2 | -45 | -92 | -6 | -510 | DEDUCTIONS & EXTRA AREAS |
| MRW | 71 | 7.05 | 7.07 | | 120' | 10' | 24' | 5' | 5' | 24' | 10' | -1,039 | 4 | -21 | 2 | -3 | -240 | DEDUCTIONS & EXTRA AREAS |
| MRW | 71 | 7.56 | 7.59 | | 145' | 10' | 24' | 5' | 5' | 24' | 10' | -1,254 | 5 | -26 | 3 | -4 | -289 | DEDUCTIONS & EXTRA AREAS |
| MRW | 71 | 12.17 | 12.19 | | 103' | 10' | 24' | 5' | 5' | 24' | 10' | -892 | 3 | -18 | 2 | -3 | -206 | DEDUCTIONS & EXTRA AREAS |
| MRW | 71 | 15.50 | 15.52 | | 80' | 10' | 24' | 5' | 5' | 24' | 10' | -691 | 3 | -14 | 1 | -2 | -159 | DEDUCTIONS & EXTRA AREAS |
| MRW | 71 | 17.63 | 17.68 | | 257' | 10' | 24' | 5' | 5' | 24' | 10' | -2,224 | 9 | -46 | 5 | -6 | -513 | DEDUCTIONS & EXTRA AREAS |
| MRW | 71 | 18.77 | 18.80 | | 155' | 10' | 24' | 5' | 5' | 24' | 10' | -1,341 | 5 | -28 | 3 | -4 | -309 | DEDUCTIONS & EXTRA AREAS |
| TOTALS CARRIED TO SUBSUMMARY | | | | | | | | | | | | 697,797 | 53,082 | 27,812 | 29,400 | 3,924 | 312,883 | |

PAVEMENT SUBSUMMARY AND DETAILS


MRW-71-3.17



| PART | ROUTE | SLM | SIDE | DESCRIPTION | INTERSECTIONS | | | | PROPOSED ITEMS | | | | | | |
|------------------------------|--------|-------------|------|----------------------------|---------------|----|-----|--------|----------------|------------------|-----------------|-----------------|------------------|-------------------|--|
| | | | | | A | B | C | AREA | 407 | ASPHALT CONCRETE | | | EXISTING SURFACE | 408 | |
| | | | | | | | | | TACK COAT | THICKNESS | ITEM 441 TYPE 1 | ITEM 441 TYPE 2 | | THICKNESS | BITUMINOUS PRIME COAT (@ 0.40 GAL/YD²) |
| FT | FT | FT | YD² | GAL | INCHES | CY | CY | INCHES | GAL | | | | | | |
| | CR-444 | 0.00 - 5.88 | LT | ① POOR RD. (T-304) | 182 | 17 | 59 | 1,194 | | 1.00 | 33 | 58 | 1.75 | GRAVEL/TAR & CHIP | 478 |
| | | | LT | ② POOR RD. SPUR (T-304) | 43 | 17 | 43 | 206 | | 1.00 | 6 | 10 | 1.75 | GRAVEL/TAR & CHIP | 82 |
| | | | RT | ③ VISTA RD. (T-223) | 39 | 20 | 85 | 369 | 28 | 1.00 | 10 | 18 | 1.75 | ASPHALT | |
| | | | RT | ④ TURNER RD. (T-156) | 35 | 17 | 65 | 253 | | 1.00 | 7 | 12 | 1.75 | GRAVEL | 101 |
| | | | RT | ⑤ BASIL RD. (T-155/CRI56) | 70 | 18 | 120 | 934 | 70 | 1.00 | 26 | 45 | 1.75 | ASPHALT | |
| | | | LT | ⑥ WOODY RD. (T-155) | 30 | 16 | 54 | 180 | 14 | 1.00 | 5 | 9 | 1.75 | ASPHALT | |
| | | | LT | ⑦ McCORD RD. SPUR (T-155A) | 70 | 12 | 145 | 1,128 | | 1.00 | 31 | 55 | 1.75 | GRAVEL | 451 |
| | | | LT | ⑧ BUMP RD. (T-215) | 30 | 18 | 70 | 234 | 17 | 1.00 | 7 | 11 | 1.75 | ASPHALT | |
| | | | LT | ⑨ ROUND CIRCLE | 33 | 18 | 50 | 184 | 14 | 1.00 | 5 | 9 | 1.75 | ASPHALT | |
| | | | LT | ⑩ GRAPE RD. (T-485) | 30 | 18 | 95 | 317 | 24 | 1.00 | 9 | 15 | 1.75 | ASPHALT | |
| | | | RT | ⑪ SOUTHERN DR. | 24 | 18 | 40 | 107 | 8 | 1.00 | 3 | 5 | 1.75 | ASPHALT | |
| | | | RT | ⑫ CHIP RD. (T-316) | 60 | 18 | 96 | 640 | 48 | 1.00 | 18 | 31 | 1.75 | ASPHALT | |
| | | | LT | ⑬ HOLIDAY RD./SR 32 | 60 | 26 | 112 | 747 | 56 | 1.00 | 21 | 36 | 1.75 | ASPHALT | |
| TOTAL | | | | | | | | 6,493 | | | | | | | |
| TOTALS (CARRIED TO SHEET 10) | | | | | | | | | 279 | | 181 | 314 | | | 1,112 |

CALCULATIONS

KNO - 444 - 0.00



ESTIMATED QUANTITIES:


| | |
|--|-----------|
| ITEM 202 GUARDRAIL REMOVED | 337.50 FT |
| ITEM 606 GUARDRAIL, TYPE 5 | 600.00 FT |
| ITEM 606 ANCHOR ASSEMBLY, REBUILT E-98 | 2 EACH |
| ITEM 606 ANCHOR ASSEMBLY, TYPE T | 2 EACH |
| ITEM 606 ANCHOR ASSEMBLY, TYPE A | 1 EACH |

ALL QUANTITIES CARRIED TO SUBSUMMARY SHEET 8.

ALL QUANTITIES CARRIED TO GENERAL SUMMARY SHEET 7.

GR-16
MRW-309-2.37

NOTE:
REMOVE AS PER ITEM 202, GUARDRAIL REMOVED.
REPLACE WITH ITEM 606, GUARDRAIL, TYPE 5.



ESTIMATED QUANTITIES:

| | |
|---|-----------|
| ITEM 202 GUARDRAIL REMOVED | 200.00 FT |
| ITEM 606 GUARDRAIL, TYPE 5 | 875.00 FT |
| ITEM 606 ANCHOR ASSEMBLY, REBUILT TYPE B-98 | 1 EACH |
| ITEM 606 ANCHOR ASSEMBLY, TYPE T | 2 EACH |
| ITEM 606 ANCHOR ASSEMBLY, TYPE A | 1 EACH |
| ITEM 606 BRIDGE TERMINAL ASSEMBLY, TYPE 4 | 4 EACH |

ALL QUANTITIES CARRIED TO SUBSUMMARY SHEET 8.

ALL QUANTITIES CARRIED TO GENERAL SUMMARY SHEET 7.

GR-17
MRW-309-2.50