

## SECTION 1300 – PLAN COMPONENTS

- **SECTION 1302.4 – DESIGN EXCEPTIONS**  
The approval dates have been revised.
- **SECTION 1303.10 – WATERWAYS**  
Per the Office of Environmental Engineering, added *jurisdictional ditches* to the examples of waterways. Also, waterways shall now be show and *labeled*.
- **SECTION 1303.21 – WETLANDS**  
Per the Office of Environmental Engineering, existing wetland shall be shown *and labeled*.
- **SECTION 1304.8 - SUBSURFACE DRAINAGE**  
Added verbiage referring users to Section 205 of the Pavement Design Manual for guidance.\
- **SECTION 1307.2.3 – ITEM CODE, UNIT OF MEASURE, AND DESCRIPTION**
  - Refer to the Item Master page on the Office of Estimating’s website for guidance when requiring Water Work items using city specifications.
  - Guidance has been provided on how Alternate items shall be listed on the General Summary.
  - Item 814 has been added to the Traffic Control category.  
Item 896 has been added to the Maintenance of Traffic category.  
Revisions have been made to the Incidental category.
- **SECTION 1307.2.7 – ALTERNATE AND OPTIONAL ITEMS**  
This section has been revised to provide clarification on how Alternate items should be shown on the General Summary.
- **SECTION 1309.4.4 - DRAINAGE ITEMS**  
Added the requirement that the size and type of all conduit shall be shown in the Plan view. Contact the Office of Hydraulic Engineering with questions.
- **SECTION 1310.4 DRAINAGE ITEMS**  
Added examples of waterway features.
- **FIGURE 1302-3 – GUIDE FOR SHOWING DESIGN EXCEPTIONS IN PLAN**  
Figure has been revised per the Office of Roadway Engineering’s updated Design Exception guidelines found in **Section 105**, [Location and Design Manual, Volume 1](#).

## SECTION 1400 – REVIEW SUBMISSIONS

- **SECTION 1401.4 REVIEW CATEGORIES**  
Minor revisions to verbiage have been made. See section for details.
- **FIGURE 1402-1 – DESIGN INFORMATION SOURCES**  
This form has been revised to included updated information from ODOT’s technical offices. See figure for changes.

## SECTION 1500 – PLAN RELATED ACTIONS

- **SECTION 1503.2.2 – TYPICAL REQUIREMENTS FOR PROJECTS FOLLOWING PATHS 2, 3, 4, AND 5 OF THE PROJECT DEVELOPMENT PROCESS (PDP)**  
Removed the Cross Section Staking Report requirement to match its removal from the *CADD Manual's Appendix E – Electronic Submission Checklist* in the July 2016 DRRC update.

## APPENDIX B – SAMPLE PLAN NOTES

- **ENVIRONMENTAL CATEGORY**  
Per the Office of Environmental Engineering, deleted the following outdated notes:  
**V102 – Stream Channel Excavation**  
**V104 – Temporary Construction Fill**

## SAMPLE PLAN SHEETS

DRAINAGE DETAILS	
SHEET NUMBER	REVISION DESCRIPTION
SP 1312-2	Eliminated the CFN for Proposed structures. Contact the Office of Hydraulic Engineering with questions.
SP 1312-7	Eliminated the CFN for proposed Structures. Contact the Office of Hydraulic Engineering with questions.
GENERAL SUMMARY	
SHEET NUMBER	REVISION DESCRIPTION
SP 1307-3(a)	Updated to match the Item Master
SP 1307-3(b)	Updated to match the Item Master
SP 1307-4	Revised how Alternate Items and Participation Splits shall be shown on the General Summary. Updated to match the Item Master.
SP 1307-5	Updated to match Item Master. Revised how Alternate Items and Participation Splits shall be shown on the General Summary.
SP 1307-6	Updated to match the Item Master