



BEGIN PROJECT
ATB SR 7 SLM: 2.37

BEGIN PROJECT
ATB US 322 SLM: 22.46

LOCATION MAP
 LATITUDE: 41°33'54"N
 LONGITUDE: 80°34'14"W



PORTION TO BE IMPROVED	=====
INTERSTATE HIGHWAY	=====
FEDERAL ROUTES	=====
STATE ROUTES	=====
COUNTY & TOWNSHIP ROADS	=====
OTHER ROADS	=====

DESIGN DESIGNATION	US 322	SR 7	SR 85
CURRENT ADT (2023)	1432	2534	3957
DIRECTIONAL DISTRIBUTION	57	54	56
TRUCKS (24 HOUR B&C)	128	150	152
LEGAL SPEED	55	45	40
DESIGN FUNCTIONAL CLASSIFICATION:	RURAL MINOR ARTERIAL		
NHS PROJECT	NO		

DESIGN EXCEPTIONS

NONE

ADA DESIGN WAIVERS

NONE

UNDERGROUND UTILITIES
 Contact Two Working Days
 Before You Dig

OHIO811.org
 Before You Dig

OHIO811, 8-1-1, or 1-800-362-2764
 (Non members must be called directly)

PLAN PREPARED BY:
 ODOT DISTRICT 4, CAPITAL PLANNING
 2088 S. ARLINGTON ROAD
 AKRON, OH 44306

END PROJECT
ATB SR 85 SLM: 2.65

BEGIN PROJECT
ATB SR 85 SLM: 0.47

END PROJECT
ATB SR 7 SLM: 6.99

END PROJECT
ATB US 322 SLM: 25.13

STATE OF OHIO

DEPARTMENT OF TRANSPORTATION

ATB US 322/VAR 22.48/VAR

ANDOVER TOWNSHIP AND VILLAGE OF ANDOVER

ASHTABULA COUNTY

INDEX OF SHEETS:

TITLE SHEET	P.1
TYPICAL SECTIONS	P.2-3
GENERAL NOTES	P.4-5
MAINTENANCE OF TRAFFIC	P.6-7
GENERAL SUMMARY	P.8-9
PAVEMENT CALCULATIONS	P.10-12
RAISED PAVEMENT MARKINGS	P.13
PAVEMENT MARKINGS	P.14
STRUCTURES	P.15-28

FEDERAL PROJECT NUMBER

E240705

RAILROAD INVOLVEMENT

NONE

PROJECT DESCRIPTION

RESURFACING OF ATB US 322, ATB SR 7, AND ATB SR 85.
 MINOR BRIDGE WORK TO 10 STRUCTURES.

EARTH DISTURBED AREAS

PROJECT EARTH DISTURBED AREA:	4.62 ACRES
ESTIMATED CONTRACTOR EARTH DISTURBED AREA:	0.25 ACRES
NOTICE OF INTENT EARTH DISTURBED AREA:	N/A (NOI NOT REQUIRED)*

*ROUTINE MAINTENANCE PROJECT

2023 SPECIFICATIONS

THE STANDARD SPECIFICATIONS OF THE STATE OF OHIO, DEPARTMENT OF TRANSPORTATION, INCLUDING SUPPLEMENTAL SPECIFICATIONS LISTED IN THE PLANS, CHANGES LISTED IN THE PROPOSAL, AND THE SUPPLEMENTAL SPECIFICATION 800 VERSION INDICATED ON THE PROPOSAL SHALL GOVERN THIS IMPROVEMENT.

I HEREBY APPROVE THESE PLANS AND DECLARE THAT THE MAKING OF THIS IMPROVEMENT WILL NOT REQUIRE THE CLOSING TO TRAFFIC OF THE HIGHWAY AND THAT PROVISIONS FOR THE MAINTENANCE AND SAFETY OF TRAFFIC WILL BE AS SET FORTH ON THE PLANS AND ESTIMATES.

Arthur G. Noiro Jr.
 Arthur G. Noiro Jr., P.E.
 District 04 Deputy Director

Pamela Boratyn
 Pamela Boratyn
 Director, Department of Transportation

STANDARD CONSTRUCTION DRAWINGS				SUPPLEMENTAL SPECIFICATIONS		SPECIAL PROVISIONS	
BP-3.1	1/19/24	TC-41.20	10/18/13	800	7/19/24	WATERWAY	
BP-3.2	1/18/19	TC-52.10	10/18/13	821	4/20/12	PERMIT	1/22/25
BP-4.1	7/19/13	TC-52.20	1/15/21	832	7/19/24		
BP-7.1	7/19/24	TC-65.10	1/17/14	846	4/17/15		
		TC-65.11	1/19/24	872	1/21/22		
DM-4.3	1/15/16	TC-71.10	4/26/23	874	4/17/20		
DM-4.4	1/15/16	TC-74.10	7/21/23	875	1/18/19		
				921	7/19/24		
MT-97.10	4/19/19						
MT-97.12	1/20/17						
MT-99.20	4/19/19						
MT-101.90	7/17/20						
MT-105.10	1/17/20						
MT-110.10	7/19/13						
TC-41.10	7/19/13						

ENGINEER'S SEAL

ROADWAY

DESIGN AGENCY	
DESIGNER	CLG
REVIEWER	MJA 11/13/24
PROJECT ID	105203
SHEET	P.1
TOTAL	28