

ESTIMATED QUANTITIES

BRIDGE NO. / STRUCTURE FILE NO.								ITEM	EXTENSION	UNIT	DESCRIPTION	SEE SHEET
ATB-322-0528 406244 03/STR/BR												
ATB-11-2782R 401897 02/NHS/BR												
ATB-307-1987 406104 03/STR/BR												
LS	LS	LS					201	11001			CLEARING AND GRUBBING, AS PER PLAN	1/4
430		490					513	90000	LB		STRUCTURAL STEEL, MISC.: REPLACEMENT OF DAMAGED CROSSFRAMES	1/4
100		100					513	90000	LB		STRUCTURAL STEEL, MISC.: STEEL BEAM REPAIRS	2/4
5	5	5					513	95000	FT		STRUCTURAL STEEL, MISC.: REPAIR OF DAMAGED MAIN OR SECONDARY MEMBERS, FILLET WELDING	1/4
	3660						514	00050	SF		SURFACE PREPARATION OF EXISTING STRUCTURAL STEEL	Pay Item Added
LS		LS					514	00100			SURFACE PREPARATION OF EXISTING STRUCTURAL STEEL	
LS		LS					514	00200			FIELD PAINTING OF EXISTING STRUCTURAL STEEL, PRIME COAT	
LS		LS					514	00300			FIELD PAINTING STRUCTURAL STEEL, INTERMEDIATE COAT	
LS		LS					514	00400			FIELD PAINTING STRUCTURAL STEEL, FINISH COAT	
17	5	9					514	00504	MNHR		GRINDING FINES, TEARS, SLIVERS ON EXISTING STRUCTURAL STEEL	
7	2	4					514	10000	EACH		FINAL INSPECTION REPAIR	
	3660						514	27700	SF		FIELD PAINTING, MISC.: REPAIR PAINTING	1/4
34	9	15					SPECIAL	53000500	hour		STRUCTURES SALT REMEDIATION FOR STRUCTURE STEEL PAINTING	2/4

STRUCTURE ESTIMATED QUANTITIES

SFN
0
DESIGN AGENCY



DESIGNER: CMR CHECKER: MJA
 REVIEWER: RS 06-16-21
 PROJECT ID: 107248
 SUBSET TOTAL
 4 4
 SHEET TOTAL
 15 15