ESTIMATED QUANTITIES

BRIDGE NO. / STRUCTURE FILE NO.								ITEM	EXTENSION	UNIT	DESCRIPTION	SEE SHEET
ATB-322-0528 406244 03/STR/BR	ATB-11-2782R 401897 02/NHS/BR	ATB-307-1987 406104 03/STR/BR										
LS	LS	LS						201	11001		CLEARING AND GRUBBING, AS PER PLAN	1/4
430		490						513	90000	LB	STRUCTURAL STEEL, MISC.: REPLACEMENT OF DAMAGED CROSSFRAMES	1/4
100		100						513	90000	LB	STRUCTURAL STEEL, MISC.:STEEL BEAM REPAIRS	2/4
5	5	5						513	95000	FT	STRUCTURAL STEEL, MISC.: REPAIR OF DAMAGED MAIN OR SECONDARY MEMBERS, FILLET WELDING	1/4
	3660							514	00050	SF	SURFACE PREPARATION OF EXISTING STRUCTURAL STEEL	
LS		LS						514	00100		SURFACE PREPARATION OF EXISTING STRUCTURAL STEEL	
LS		LS						514	00200		FIELD PAINTING OF EXISTING STRUCTURAL STEEL, PRIME COAT	
LS		LS						514	00300		FIELD PAINTING STRUCTURAL STEEL, INTERMEDIATE COAT	
LS		LS						514	00400		FIELD PAINTING STRUCTURAL STEEL, FINISH COAT	
17	5	9						514	00504	MNHR	GRINDING FINS, TEARS, SLIVERS ON EXISTING STRUCTURAL STEEL	
7	2	4						514	10000	EACH	FINAL INSPECTION REPAIR	
	3660							514	27700	SF	FIELD PAINTING, MISC.: REPAIR PAINTING	1/4
34	9	15						SPECIAL	53000500	HOUR	STRUCTURES SALT REMEDIATION FOR STRUCTURE STEEL PAINTING	2/4

STRUCTURE ESTIMATED QUANTITIES

SFN 0

DESIGN AGENCY

DESIGNER	CHECKER
CMR	MJA

REVIEWER RS 06-16-21

PROJECT ID 107248

SUBSET	TOTAL
4	4

SHEET	TOTAL
15	15

ATB-BP-FY2022

MODEL: Sheet PAPERSIZE: 17x11 (in.) DATE: 8/19/2021 TIME: 2:00:17 PM USER: crees
pw:\\ohiodot-pw.bentley.com:ohiodot-pw-02\Documents\01 Active Projects\District 04\Ashtabula\107248\400-Engineering\Roadway\Sheets\107248_SQ002.dgn