

TYPICAL SECTION 1

ROUTE	SLM		LENGTH (MILES)	PW (FEET)
	FROM	TO		
ATB-193	14.57	15.23	0.66	28
ATB-193	15.23	15.31	0.08	30
ATB-193	15.31	18.17	2.86	26
ATB-193	18.17	18.19	0.02	35
ATB-193	18.19	18.76	0.57	26
ATB-193	18.76	18.78	0.02	34
ATB-193	18.78	20.15	1.37	26
ATB-193	20.15	20.18	0.03	32
ATB-193	20.19	20.25	0.06	32
ATB-193	20.25	20.73	0.48	26
ATB-193	20.73	20.78	0.05	32
ATB-193	20.78	22.27	1.49	26
ATB-193	22.27	22.28	0.01	36
ATB-193	22.28	22.54	0.26	26

LEGEND

- ① ITEM 254 PAVEMENT PLANING, ASPHALT CONCRETE (T = 1.75")
- ② ITEM 441 ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), AS PER PLAN, PG70-22M (T = 1.5")
- ③ ITEM 407, NON-TRACKING TACK @ 0.06 GAL/SY
- ④ ITEM 422 AGGREGATE, SINGLE CHIP SEAL, TYPE A (INTERLAYER), AS PER PLAN
- ⑤ ITEM 422 EMULSION, CHIP SEAL @ 0.4 GAL/SY
- ⑥ ITEM 617 COMPACTED AGGREGATE, AS PER PLAN (T = 2")
- ⑦ ITEM 408 PRIME COAT @ 0.40 GAL/SY, AS PER PLAN
- ⑧ SAFETY EDGE - SEE BP 3.2 FOR DETAILS
- Ⓐ EXISTING ASPHALT CONCRETE PAVEMENT (T = 9.75")
- Ⓑ EXISTING ASPHALT CONCRETE SHOULDER
- Ⓒ EXISTING AGGREGATE BASE

Corrected bubble label




SHEET NUM.										PART.			ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
3	4	5	6	9	10	11	12	14		01/STR/05	02/STR/47	03/STR/04						
ROADWAY																		
90										90			203	10000	90	CY	EXCAVATION	
	810									810			209	60200	810	STA	LINEAR GRADING	
				841						841			209	72000	841	STA	PREPARING SUBGRADE FOR SHOULDER PAVING	
	4									4			623	39501	4	EACH	MONUMENT ASSEMBLY ADJUSTED TO GRADE, AS PER PLAN	4
EROSION CONTROL																		
	22,500									22,500			659	10000	22,500	SY	SEEDING AND MULCHING	
	3.04									3.04			659	20000	3.04	TON	COMMERCIAL FERTILIZER	
	4.65									4.65			659	31000	4.65	ACRE	LIME	
	121.5									121.5			659	35000	121.5	MGAL	WATER	
										3,000			832	30000	3,000	EACH	EROSION CONTROL	
PAVEMENT																		
2,000										2,000			251	01000	2,000	SY	PARTIAL DEPTH PAVEMENT REPAIR (441)	
234										234			252	01500	234	FT	FULL DEPTH PAVEMENT SAWING	
539										539			253	01000	539	SY	PAVEMENT REPAIR	
				123,130	1,957					125,087			254	01000	125,087	SY	PAVEMENT PLANING, ASPHALT CONCRETE	
90										90			304	20000	90	CY	AGGREGATE BASE	
				7,462	118					7,580			407	20000	7,580	GAL	NON-TRACKING TACK COAT	
				7,472						7,472			408	10001	7,472	GAL	PRIME COAT, AS PER PLAN	4
				123,130	1,957					125,087			422	11001	125,087	SY	AGGREGATE, SINGLE CHIP SEAL, TYPE A, AS PER PLAN (INTERLAYER)	3
				49,252	783					50,035			422	25000	50,035	GAL	EMULSION, CHIP SEAL	
				5,172	82					5,254			441	50101	5,254	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), AS PER PLAN, PG70-22M	3
				1,038						1,038			617	10101	1,038	CY	COMPACTED AGGREGATE, AS PER PLAN	4
	7.97									7.97			618	43000	7.97	MILE	RUMBLE STRIPES, CENTER LINE (ASPHALT CONCRETE)	
	42,082									42,082			874	20000	42,082	FT	LONGITUDINAL JOINT PREPARATION	
TRAFFIC CONTROL																		
						566				566			621	00100	566	EACH	RPM	
						453				453			621	54000	453	EACH	RAISED PAVEMENT MARKER REMOVED	
							15.94			15.94			646	10010	15.94	MILE	EDGE LINE, 6"	
							7.97			7.97			646	10200	7.97	MILE	CENTER LINE	
							30			30			646	10400	30	FT	STOP LINE, 24"	
STRUCTURE REPAIRS																		
																	FOR ATB-193-1529 ESTIMATED QUANTITIES	14
																	FOR ATB-193-1818 ESTIMATED QUANTITIES	14
																	FOR ATB-193-1877 ESTIMATED QUANTITIES	14
																	FOR ATB-193-2018 ESTIMATED QUANTITIES	14
																	FOR ATB-193-2077 ESTIMATED QUANTITIES	14
																	FOR ATB-193-2227 ESTIMATED QUANTITIES	14
MAINTENANCE OF TRAFFIC																		
			75							75			614	11110	75	HOUR	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE	
		LS								LS			614	12420	LS		DETOUR SIGNING	
		12								12			614	12460	12	EACH	WORK ZONE MARKING SIGN, (ALL PHASES)	
		20								20			614	13000	20	CY	ASPHALT CONCRETE FOR MAINTAINING TRAFFIC	
			16							16			614	18601	16	SNMT	PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN	6
		15.94								15.94			614	21000	15.94	MILE	WORK ZONE CENTER LINE, CLASS I	
		7.97								7.97			614	21550	7.97	MILE	WORK ZONE CENTER LINE, CLASS III, 642 PAINT	
		15.94								15.94			614	22360	15.94	MILE	WORK ZONE EDGE LINE, CLASS III, 6" 642 PAINT	
		60								60			614	26000	60	FT	WORK ZONE STOP LINE, CLASS I	
		30								30			614	26610	30	FT	WORK ZONE STOP LINE, CLASS III, 642 PAINT	
INCIDENTALS																		
										LS			614	11000	LS		MAINTAINING TRAFFIC	
										6			619	16010	6	MNTH	FIELD OFFICE, TYPE B	
										LS			623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
										LS			624	10000	LS		MOBILIZATION	

Corrected quantity

Corrected quantity

GENERAL SUMMARY

DESIGN AGENCY

 DESIGNER: ROF
 REVIEWER: MJA 8-24-22
 PROJECT ID: 110629
 SHEET: P.8 TOTAL: 17

