

STATION		SIDE	LENGTH (L)	AVERAGE WIDTH (W)	SURFACE AREA (A) = LxW	202	204	252	301	304	407	441	441
						PAVEMENT REMOVED	SUBGRADE COMPACTION	FULL DEPTH PAVEMENT SAWING	ASPHALT CONCRETE BASE, PG64-22 (449) (T=6")	AGGREGATE BASE (T=6")	NON-TRACKING TACK COAT (@ 0.055 GAL/SY)	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (449), PG70-22M (T=1.25")	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (449) (T=1.75")
FROM	TO		FT	FT	SF	SY	SY	FT	CY	CY	GAL	CY	CY
W.48TH ST./S.R. 84 (COLLINS BOULEVARD)													
702+93.52	703+25.58	LT./RT.	CADD AREA		1984.30			109.47	36.75		24.25	7.66	10.72
702+93.52	703+25.58	LT./RT.	CADD AREA		2121.34		235.70			39.28			
703+25.58	706+59.66	LT./RT.	334.08	46.00	15367.68				284.59		187.83	59.29	83.00
703+25.58	706+59.66	LT./RT.	334.08	49.00	16369.92		1818.88			303.15			
706+59.66	706+84.66	LT.	25.00	23.05	576.25				10.67		7.04	2.22	3.11
706+59.66	706+84.66	LT.	25.00	24.55	613.75		68.19			11.37			
706+84.66	707+66.31	LT.	81.65	24.10	1967.76			165.06	36.44		24.05	7.59	10.63
706+84.66	707+66.31	LT.	81.65	24.10	1967.76		218.64			36.44			
707+66.31	707+91.31	LT.	25.00	23.05	576.25				10.67		7.04	2.22	3.11
707+66.31	707+91.31	LT.	25.00	24.55	613.75		68.19			11.37			
707+91.31	708+07.31	LT.	16.00	22.00	352.00				6.52		4.30	1.36	1.90
707+91.31	708+07.31	LT.	16.00	23.50	376.00		41.78			6.96			
706+59.66	706+63.41	RT.	3.75	24.00	90.00				1.67		1.10	0.35	0.49
706+59.66	706+63.41	RT.	3.75	25.50	95.63		10.63			1.77			
706+63.41	706+68.41	RT.	5.00	24.05	120.25				2.23		1.47	0.46	0.65
706+63.41	706+68.41	RT.	5.00	25.55	127.75		14.19			2.37			
706+68.41	708+02.31	RT.	133.90	23.90	3200.21			144.47	59.26		39.11	12.35	17.29
706+68.41	708+02.31	RT.	133.90	23.90	3200.21		355.58			59.26			
708+02.31	708+07.31	RT.	5.00	23.85	119.25				2.21		1.46	0.46	0.64
708+02.31	708+07.31	RT.	5.00	25.35	126.75		14.08			2.35			
708+07.31	715+71.68	LT./RT.	764.37	46.00	35161.02				651.13		429.75	135.65	189.91
708+07.31	715+71.68	LT./RT.	764.37	49.00	37454.13		4161.57			693.59			
715+71.68	717+45.96	LT./RT.	CADD AREA		9277.63				171.81		113.39	35.79	50.11
715+71.68	717+45.96	LT./RT.	CADD AREA		9802.18		1089.13			181.52			
717+45.96	717+83.98	LT./RT.	CADD AREA		2978.64			144.76	55.16		36.41	11.49	16.09
717+45.96	717+83.98	LT./RT.	CADD AREA		3160.35		351.15			58.53			
702+93.52	703+25.58	LT./RT.	CADD AREA		2040.00	226.67							
703+25.58	706+59.66	LT./RT.	334.08	48.00	16035.84	1781.76							
706+59.66	706+84.66	LT.	25.00	24.05	601.25	66.81							
706+84.66	707+66.31	LT.	81.65	24.10	1967.76	218.64							
707+66.31	707+91.31	LT.	25.00	24.00	600.00	66.67							
707+91.31	708+07.31	LT.	16.00	24.00	384.00	42.67							
706+59.66	706+63.41	RT.	3.75	24.00	90.00	10.00							
706+63.41	706+68.41	RT.	5.00	24.05	120.25	13.36							
706+68.41	708+02.31	RT.	133.90	23.90	3200.21	355.58							
708+02.31	708+07.31	RT.	5.00	23.85	119.25	13.25							
708+07.31	715+71.68	LT./RT.	764.37	48.00	36689.76	4076.64							
715+71.68	717+45.96	LT./RT.	CADD AREA		9519.71	1057.75							
717+45.96	717+83.98	LT./RT.	CADD AREA		3029.69	336.63							
MAIN AVENUE													
19+60.32	19+76.10	LT./RT.	CADD AREA		1384.37	153.82			25.64		16.92	5.34	7.48
19+60.32	19+76.10	LT./RT.	CADD AREA		1384.37		153.82			25.64			
SUB-TOTALS						8420.23	8601.54	563.76	1354.73	1433.59	894.12	282.24	395.13
TOTALS						8420.23	8601.54	563.76	1354.73	1433.59	894.12	282.24	395.13
TOTALS CARRIED TO THE GENERAL SUMMARY						8420	8602	564	1355	1434	894	282	395