


SHEET NUM.												PART.		ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.		
8	9	10	14	15	18	19	20	21	22	23	01/NHS/PV										
														PAVEMENT (CONT.)							
					19,788							19,788	442	10300	19,788	CY	ASPHALT CONCRETE SURFACE COURSE, 12.5 MM, TYPE A (447)				
16,000												16,000	451	15020	16,000	SY	10" REINFORCED CONCRETE PAVEMENT, CLASS QC 1P WITH QC/QA	8,36			
427												427	452	14020	427	SY	10" NON-REINFORCED CONCRETE PAVEMENT, CLASS QC 1P WITH QC/QA	8,36			
						80						80	609	24500	80	FT	CURB, TYPE 4-B				
					4,095							4,095	617	10100	4,095	CY	COMPACTED AGGREGATE				
					39.93							39.93	618	40600	39.93	MILE	RUMBLE STRIPS, SHOULDER (ASPHALT CONCRETE)				
								58.67				58.67	850	10010	58.67	MILE	GROOVING FOR 6" RECESSED PAVEMENT MARKING, (ASPHALT)				
								12,445				12,445	850	10130	12,445	FT	GROOVING FOR 12" RECESSED PAVEMENT MARKING, (ASPHALT)				
														TRAFFIC CONTROL							
												1,631	621	00100	1,631	EACH	RPM				
												1,631	621	54000	1,631	EACH	RAISED PAVEMENT MARKER REMOVED				
							160					160	626	00102	160	EACH	BARRIER REFLECTOR, TYPE 1, BIDIRECTIONAL				
		0.91	2.84									3.75	642	30030	3.75	MILE	REMOVAL OF PAVEMENT MARKING				
									0.88			0.88	644	00100	0.88	MILE	EDGE LINE, 4"				
								1.08	0.3			1.38	644	00104	1.38	MILE	EDGE LINE, 6"				
									0.7			0.7	644	00300	0.7	MILE	CENTER LINE				
									1,055			1,055	644	00400	1,055	FT	CHANNELIZING LINE, 8"				
								110	548			658	644	00500	658	FT	STOP LINE				
									96			96	644	00630	96	FT	CROSSWALK LINE, 24"				
								1,720				1,720	644	00720	1,720	FT	CHEVRON MARKING				
								39	10			49	644	01300	49	EACH	LANE ARROW				
									125			125	644	01500	125	FT	DOTTED LINE, 4"				
								39.5				39.5	807	14010	39.5	MILE	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING, EDGE LINE, 6"				
								19.17				19.17	807	14110	19.17	MILE	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING, LANE LINE, 6"				
								10,065				10,065	807	14310	10,065	FT	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING, CHANNELIZING LINE, 12"				
								2,380				2,380	807	14430	2,380	FT	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING, DOTTED LINE, 12"				
														MAINTENANCE OF TRAFFIC							
		80										80	614	11110	80	HOUR	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE				
			1									1	614	12380	1	EACH	WORK ZONE IMPACT ATTENUATOR, 24" WIDE HAZARDS, (UNIDIRECTIONAL)				
8												8	614	12410	8	EACH	SPEED ZONE AHEAD SYMBOL SIGN, W3-HB				
20												20	614	12484	20	EACH	WORK ZONE INCREASED PENALTIES SIGN, R11-H5A-48				
8												8	614	12490	8	EACH	RESUME LEGAL SPEED SIGN, R2-1				
			24									24	614	13310	24	EACH	BARRIER REFLECTOR, TYPE 1, BIDIRECTIONAL				
						242						242	614	13312	242	EACH	BARRIER REFLECTOR, TYPE 2, BIDIRECTIONAL				
		10										10	614	18600	10	SNMT	PORTABLE CHANGEABLE MESSAGE SIGN				
										37.5		37.5	614	20110	37.5	MILE	WORK ZONE LANE LINE, CLASS I, 6", 642 PAINT				
										37.5		37.5	614	20510	37.5	MILE	WORK ZONE LANE LINE, CLASS II, 6", 642 PAINT				
										1.34		1.34	614	21500	1.34	MILE	WORK ZONE CENTER LINE, CLASS II, 642 PAINT				
										1.34		1.34	614	21550	1.34	MILE	WORK ZONE CENTER LINE, CLASS III, 642 PAINT				
			0.84	6.05						77.32		84.21	614	22110	84.21	MILE	WORK ZONE EDGE LINE, CLASS I, 6", 642 PAINT				
										1.76		1.76	614	22350	1.76	MILE	WORK ZONE EDGE LINE, CLASS III, 4", 642 PAINT				
										2.68		2.68	614	22360	2.68	MILE	WORK ZONE EDGE LINE, CLASS III, 6", 642 PAINT				
				735						20,130		20,865	614	23210	20,865	FT	WORK ZONE CHANNELIZING LINE, CLASS I, 12", 642 PAINT				
										1,510		1,510	614	23680	1,510	FT	WORK ZONE CHANNELIZING LINE, CLASS III, 8", 642 PAINT				
				2,880						2,880		2,880	614	24202	2,880	FT	WORK ZONE DOTTED LINE, CLASS I, 6", 642 PAINT				
										1,118		1,118	614	26610	1,118	FT	WORK ZONE STOP LINE, CLASS III, 642 PAINT				
	100											100	808	18700	100	SNMT	DIGITAL SPEED LIMIT (DSL) SIGN ASSEMBLY				
														INCIDENTALS							
											LS	614	11000	LS			MAINTAINING TRAFFIC	10			
											LS	614	12420	LS			DETOUR SIGNING	9			
LS	LS	LS									LS	623	10001	LS			CONSTRUCTION LAYOUT STAKES AND SURVEYING, AS PER PLAN	8			
											LS	624	10000	LS			MOBILIZATION				
											15	619	16020	15	MNTH		FIELD OFFICE, TYPE C				

GENERAL SUMMARY

DESIGN AGENCY



DESIGNER: KWK
 REVIEWER: MRF 08/08/22
 PROJECT ID: 102645
 SHEET: 17 TOTAL: 40