

BEL-149-23.64

MODEL: Sheet PAPER: A SIZE: 11x17 DATE: 3/7/2022 TIME: 11:36:02 AM USER: shorrisb  
 pw:\\ohiodot-pw\belmont\06789\02 Documents\01 Active Projects\District 1\Belmont\06789\400-Engineering\Roadway\Sheets\06789\_GG003.dgn

SHEET NUM.												PART. 01/ STR/OT	ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
			25		58	59												
																TRAFFIC CONTROL		
						33						33	621	00100	33	EACH	RPM	
					33							33	621	54000	33	EACH	RAISED PAVEMENT MARKER REMOVED	
			15			100.7						115.7	630	02100	115.7	FT	GROUND MOUNTED SUPPORT, NO. 2 POST	
						140.1						140.1	630	03100	140.1	FT	GROUND MOUNTED SUPPORT, NO. 3 POST	
						35						35	630	04100	35	FT	GROUND MOUNTED SUPPORT, NO. 4 POST	
						31.8						31.8	630	06400	31.8	FT	GROUND MOUNTED STRUCTURAL BEAM SUPPORT, S4X7.7	
						73.9						73.9	630	06500	73.9	FT	GROUND MOUNTED STRUCTURAL BEAM SUPPORT, W6X9	
						52.4						52.4	630	07600	52.4	FT	GROUND MOUNTED STRUCTURAL BEAM SUPPORT, W10X12	
						29.6						29.6	630	08004	29.6	FT	ONE WAY SUPPORT, NO. 3 POST	
						6						6	630	08600	6	EACH	SIGN POST REFLECTOR	
						4						4	630	09000	4	EACH	BREAKAWAY STRUCTURAL BEAM CONNECTION	
						2						2	630	79200	2	EACH	SIGN ATTACHMENT ASSEMBLY, MAST ARM	
						6						6	630	79500	6	EACH	SIGN SUPPORT ASSEMBLY, POLE MOUNTED	
			2			59.75						61.75	630	80100	61.75	SF	SIGN, FLAT SHEET	
						8						8	630	84500	8	EACH	GROUND MOUNTED STRUCTURAL BEAM SUPPORT FOUNDATION	
						5						5	630	84900	5	EACH	REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL	
						23						23	630	85100	23	EACH	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION	
						5						5	630	85600	5	EACH	REMOVAL OF GROUND MOUNTED MAJOR SIGN AND REERECTION	
						14						14	630	86002	14	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL	
						8						8	630	86102	8	EACH	REMOVAL OF GROUND MOUNTED STRUCTURAL BEAM SUPPORT AND DISPOSAL	
					0.35							0.35	646	10010	0.35	MILE	EDGE LINE, 6"	
					0.08							0.08	646	10110	0.08	MILE	LANE LINE, 6"	
					0.15							0.15	646	10200	0.15	MILE	CENTER LINE	
					410							410	646	10300	410	FT	CHANNELIZING LINE, 8"	
					250							250	646	10310	250	FT	CHANNELIZING LINE, 12"	
					97							97	646	10400	97	FT	STOP LINE	
					8							8	646	20300	8	EACH	LANE ARROW	
					1							1	646	50000	1	EACH	REMOVAL OF PAVEMENT MARKING	

GENERAL SUMMARY

DESIGN AGENCY



DESIGNER

SAH

REVIEWER

DAH 11-15-21

PROJECT ID

106789

SHEET

P.23

TOTAL

88

SHEET NO.	CALLOUT	LOCATION	SLM		621					646										COMMENTS						
					RPM				RAISED PAVEMENT MARKER REMOVED	CENTER LINE (DOUBLE SOLID)	EDGE LINE, 6" (YELLOW)	EDGE LINE, 6" (WHITE)	LANE LINE, 6"	CHANNELIZING LINE, 8"	CHANNELIZING LINE, 12"	STOP LINE	LANE ARROW	REMOVAL OF PAVEMENT MARKING								
					SPACING	YELLOW/RED	YELLOW/YELLOW	WHITE/RED											FT		EACH	EACH	EACH	EACH	MILE	MILE
60-61	EW-1	S.R. 149	117+10.0	123+70.4																						
60	EW-2	S.R. 149	117+10.0	119+15.8																						
60	LL-1	S.R. 149	117+50.0	120+70.0																						
60-61	CL-1	S.R. 149	117+10.0	124+80.0	80		11.0		11.0		0.15															
60	LL-2	S.R. 149	119+72.5	120+70.0																						
60	LA-1	S.R. 149	120+98.0																			1				
60-61	CH-1	S.R. 149	120+70.0	124+80.0										410												
60	LA-2	S.R. 149	121+86.0																			1				
60	LA-3	S.R. 149	122+98.0																			1				
61	EW-3	S.R. 149 TO RAMP A	123+70.4	15+73.0																						
61	LA-4	S.R. 149	123+62.0																			1				
61	EW-4	S.R. 149 TO RAMP B	124+78.0	1+35.6	80	3.0			3.0		0.03															
61	LA-5	S.R. 149	124+50.0																			1				
61	SL-1	S.R. 149	124+80.0																							
61	SL-2	RAMP A	15+75.0																							
61	SL-3	S.R. 149	125+97.0																							
61-62	CH-2	RAMP A	13+25.0	15+75.0	40			9.0	9.0																	
61-62	EY-1	RAMP A TO S.R. 149	12+75.0	125+97	80	5.0			5.0		0.06															
61-62	EW-5	RAMP A	12+75.0	15+73.0	80	5.0			5.0		0.06															
62	LA-6	RAMP A	13+69.0																			1				
62	LA-7	RAMP A	14+57.0																			1				
62	LA-8	RAMP A	15+45.0																			1				
62	R-1	RAMP A	15+10.0																					1		
<b>SUBTOTAL</b>						<b>13</b>	<b>11</b>	<b>9</b>			<b>0.06</b>	<b>0.29</b>														
<b>TOTALS CARRIED TO GENERAL SUMMARY</b>							<b>33</b>		<b>33</b>	<b>0.15</b>	<b>0.35</b>	<b>0.08</b>	<b>410</b>	<b>250</b>	<b>97</b>						<b>8</b>		<b>1</b>			

PAVEMENT MARKING QUANTITIES

DESIGN AGENCY  
  
 DESIGNER  
**SAH**  
 REVIEWER  
 DAH 11-15-21  
 PROJECT ID  
 106789  
 SHEET TOTAL  
 P.58 | 88