

LOCATION	SLM		LENGTH		WIDTH	TYPICAL	PAVEMENT AREA * Denotes CADD Area SQ YD	IN.	254		407				IN.	442		REMARKS
									PAVEMENT PLANING, ASPHALT CONCRETE		TACK COAT @ 0.075 GAL./S.Y.					ASPHALT CONCRETE SURFACE COURSE, 12.5MM, TYPE B (446), AS PER PLAN		
									SQ YD		GAL					CU YD		
SOUTHBOUND S.R. 7 MAINLINE	FROM	TO	MILE	FT	FT													
	20.08	20.45	0.37	1,953.60	29.00	1 & 2	6,295	1 1/2	6,295		472				1 1/2	262		
	20.45	20.47	0.02	105.60	31.00	2	364	1 1/2	364		27				1 1/2	15		
	20.47	20.49	0.02	105.60	31.00	2	364	1 1/2	364		27				1 1/2	15		
	20.49	20.73	0.24	1,267.20	30.75	2	4,330	1 1/2	4,330		325				1 1/2	180		
	20.73	20.84	0.11	580.80	27.60	2	1,781	1 1/2	1,781		134				1 1/2	74		
								1 1/2										
SUSPEND WORK - AETNA ST.	20.84	20.99																
RESUME WORK - S.R. 7	20.99	21.04	0.05	264.00	31.10	2	912	1 1/2	912		68				1 1/2	38		
	21.04	21.44	0.40	2,112.00	30.75	2	7,216	1 1/2	7,216		541				1 1/2	301		
	21.44	21.48	0.04	211.20	35.75	2	839	1 1/2	839		63				1 1/2	35		
	21.48	21.60	0.12	633.60	40.75	2	2,869	1 1/2	2,869		215				1 1/2	120		
	21.60	21.61	0.01	52.80	35.75	2	210	1 1/2	210		16				1 1/2	9		
	21.61	21.70	0.09	475.20	30.75	2	1,624	1 1/2	1,624		122				1 1/2	68		
	21.70	21.84	0.14	739.20	27.70	2	2,275	1 1/2	2,275		171				1 1/2	95		
	21.84	21.85	0.01	52.80	24.60	2	144	1 1/2	144		11				1 1/2	6		
SUSPEND WORK - HANOVER AVE.	21.85	22.01																
RESUME WORK - S.R. 7	22.01	22.16	0.15	792.00	32.40	2	2,851	1 1/2	2,851		214				1 1/2	119		
	22.16	22.60	0.44	2,323.20	30.75	2	7,938	1 1/2	7,938		595				1 1/2	331		
	22.60	22.66	0.06	316.80	28.12	2	990	1 1/2	990		74				1 1/2	41		
	22.66	22.68	0.02	105.60	25.50	2	299	1 1/2	299		22				1 1/2	12		
	22.68	22.70	0.02	105.60	28.13	2	330	1 1/2	330		25				1 1/2	14		
	22.70	22.84	0.14	739.20	30.75	2	2,526	1 1/2	2,526		189				1 1/2	105		
	22.84	22.90	0.06	316.80	28.13	2	990	1 1/2	990		74				1 1/2	41		
	22.90	22.92	0.02	105.60	28.30	2	332	1 1/2	332		25				1 1/2	14		
	22.92	23.03	0.11	580.80	30.75	2	1,984	1 1/2	1,984		149				1 1/2	83		
	23.03	23.09	0.06	316.80	28.13	2	990	1 1/2	990		74				1 1/2	41		
	23.09	23.11	0.02	105.60	27.50	2	323	1 1/2	323		24				1 1/2	13		