

UTILITIES

LISTED BELOW ARE ALL THE UTILITIES LOCATED WITHIN THE PROJECT CONSTRUCTION LIMITS TOGETHER WITH THEIR RESPECTIVE OWNERS:

AEP OHIO POWER COMPANY
ATTN: CLARKE SAUNDERS
777 HOPEWELL DRIVE
HEATH, OHIO 43056
614-460-4794
CMSAUNDERS@AEP.COM

MASSILLON CABLE TV
ATTN: JEREMY LEHMAN
444 W. MILLTOWN RRD
WOOSTER, OHIO 44691
330-804-0219
JLEHMAN@MCTVOHIO.COM

AT&T OHIO, INC.
ATTN: BARRETT J. TAMASOVICH
160 NORTH 6TH STREET
ZANESVILLE, OHIO 43701
740-454-3552
BT2178@ATT.COM

COLUMBIA GAS OF OHIO, INC.
ATTN: JONAH MOORE
300 LURAY DRIVE
WINTERSVILLE, OHIO 43953
740-457-3900
JMOORE@NISOURCE.COM

BELMONT COUNTY SANITARY SEWER DISTRICT
ATTN: BRIAN STREET
P.O. BOX 457
ST CLAIRSVILLE, OHIO 43950
740-695-3144
BRIAN.STREET@BELMONTCOUNTYWATER.COM

EXISTING PLANS

THE FOLLOWING EXISTING PLANS ARE AVAILABLE FOR REFERENCE AT THE DISTRICT 11 OFFICE OF THE OHIO DEPARTMENT OF TRANSPORTATION, 2201 REISER AVE. S.E., NEW PHILADELPHIA, OHIO 44663:

ORIGINAL CONSTRUCTION:
BEL-149-4.99 (1998)

IN ADDITION, THE EXISTING PLANS CAN BE FOUND ON THE DEPARTMENT'S WEBSITE AT THE FOLLOWING ADDRESS:

HTTP://FTP.DOT.STATE.OHIO.US/CONTRACTS/ATTACH

CLEARING AND GRUBBING, AS PER PLAN

ALL TREES, STUMPS, AND VEGETATION UNDERNEATH THE STRUCTURE AND/OR WITHIN 20 FEET BEYOND THE STRUCTURE WINGWALL LIMITS SHALL BE REMOVED AS DIRECTED BY THE ENGINEER.

ALTHOUGH THERE ARE NO TREES OR STUMPS SPECIFICALLY MARKED FOR REMOVAL WITHIN THE LIMITS OF THE PROJECT, A LUMP SUM QUANTITY IS INCLUDED IN THE GENERAL SUMMARY FOR ITEM 201, CLEARING AND GRUBBING. ALL PROVISIONS AS SET FORTH IN THE SPECIFICATIONS UNDER THIS ITEM ARE INCLUDED IN THE LUMP SUM PRICE BID FOR ITEM 201, CLEARING AND GRUBBING, AS PER PLAN.

WORK LIMITS

THE WORK LIMITS SHOWN ON THESE PLANS ARE FOR PHYSICAL CONSTRUCTION ONLY. PROVIDE THE INSTALLATION AND OPERATION OF ALL WORK ZONE TRAFFIC CONTROL AND WORK ZONE TRAFFIC CONTROL DEVICES REQUIRED BY THESE PLANS WHETHER INSIDE OR OUTSIDE THESE WORK LIMITS.

SURVEYING PARAMETERS

PRIMARY PROJECT CONTROL MONUMENTS GOVERN ALL POSITIONING ON ODOT PROJECTS. SEE THIS SHEET FOR A TABLE CONTAINING PROJECT CONTROL INFORMATION.

USE THE FOLLOWING PROJECT CONTROL, VERTICAL POSITIONING, AND HORIZONTAL POSITIONING PARAMETERS FOR ALL SURVEYING:

PROJECT CONTROL

POSITIONING METHOD: OHIO REAL TIME NETWORK (2011) and DIFFERENTIAL LEVELING
MONUMENT TYPE: TYPE B

VERTICAL POSTIONING

ORTHOMETRIC HEIGHT DATUM: NAVD 88
GEOID: GEOID 18

HORIZONTAL POSITIONING

REFERENCE FRAME: NAD 83 (2011 ADJ, 2010.0)
ELLIPSOID: GRS 1980
MAP PROJECTION: TRANSVERSE MERCATOR
COORDINATE SYSTEM: OHIO COUNTY COORDINATE SYSTEM BELMONT LDP
PROJECTION SCALE FACTOR: 1.000041
ORIGIN LATIITUDE: N 38° 30' 00"
ORIGIN LONGITUDE: E 279° 00' 00"
FALSE NORTHING (m): 0
FALSE EASTING (m): 50000

*THE LOW DISTORTION PROJECTION (LDP) IS A LOCAL COUNTY PROJECTION DEVELOPED BY ODOT. THE DISTORTION BETWEEN GROUND AND GRID IS SO MINIMAL THAT THERE IS NO NEED FOR A SCALE FACTOR TO ADJUST BETWEEN GRID AND GROUND COORDINATES. CONTACT THE DISTRICT SURVEY DEPARTMENT FOR FURTHER INFORMATION OR QUESTIONS.

USE THE POSITIONING METHODS AND MONUMENT TYPE USED IN THE ORIGINAL SURVEY TO RESTORE ALL MONUMENTS RELATED TO PRIMARY PROJECT CONTROL THAT ARE DAMAGED OR DESTROYED BY CONSTRUCTION ACTIVITIES. RESTORE THE DAMAGED OR DESTROYED MONUMENTS IN ACCORDANCE WITH CMS 623.

UNITS ARE IN U.S. SURVEY FEET

ENVIRONMENTAL WORK

BASED ON ENVIRONMENTAL STUDIES MATERIALS CONTAMINATED WITH PETROLEUM CONTAMINATED SOILS WILL BE ENCOUNTERED DURING THE EXCAVATIONS FOR CONSTRUCTION ACTIVITIES AT THE SITES LISTED BELOW. THE ESTIMATED QUANTITIES HAVE BEEN INCLUDED IN THE GENERAL SUMMARY FOR THIS WORK. ALL EXCAVATIONS AT THE AFOREMENTIONED LOCATION SHALL BE PAID FOR UNDER THE ORIGINAL PLAN BID ITEMS.

1. 53850 PIKE STREET, BELLAIRE, OH

ALL EXCAVATED MATERIALS WITHIN THE AFOREMENTIONED LIMITS MAY BE STOCKPILED IN AN AREA PROVIDED BY THE CONTRACTOR AND APPROVED BY THE ENGINEER. THE ENGINEER MAY PERMIT TEMPORARY STORAGE OF THE SUSPECTED CONTAMINATED SOILS ON AN IMPERMEABLE MEMBRANE. THE MEMBRANE WILL BE SURROUNDED BY BALES OF STRAW TO PREVENT THE SUSPECTED SOILS FROM COMING IN CONTACT WITH THE ORIGINAL SOILS. AN IMPERMEABLE MEMBRANE WILL BE PLACED OVER THE STOCKPILE TO PREVENT CONTACT WITH PRECIPITATION AND/OR SURFACE RUN-OFF. AS A TEMPORARY STORAGE ALTERNATIVE, THE ENGINEER MAY PERMIT THE CONTRACTOR TO DIRECT LOAD THE EXCAVATED SOILS INTO TRUCKS. OR AS A THIRD ALTERNATIVE, THE CONTRACTOR MAY PLACE THE MATERIAL IN LEAK-PROOF, COVERED CONTAINERS PROVIDED BY THE CONTRACTOR. THE MATERIAL WILL REMAIN ON-SITE UNTIL ANALYTICAL RESULTS ARE RECEIVED BY THE ENGINEER.

THIS MATERIAL WILL BE PROPERLY TESTED (FOR DISPOSAL), TRANSPORTED, AND DISPOSED OF IN A LICENSED (BY THE LOCAL HEALTH DEPARTMENT) AND PERMITTED (BY THE OHIO ENVIRONMENTAL PROTECTION AGENCY) SOLID WASTE FACILITY.

IF EXCAVATIONS WITHIN THE AFOREMENTIONED LIMITS REQUIRE DEWATERING FOR CONSTRUCTION PURPOSES, THE CONTRACTOR WILL DEWATER, CONTAINERIZE, TEST THE WATER (FOR DISPOSAL) AND DISPOSE OF BY METHODS APPROVED BY THE ENGINEER. THE CONTRACTOR WILL OBTAIN ALL THE REQUIRED PERMITS AND /OR AUTHORIZATIONS NEEDED TO STORE, TRANSPORT AND DISPOSE OF THE WATER IN ACCORDANCE WITH APPLICABLE LOCAL, STATE OR FEDERAL REGULATIONS.

THE CONTRACTOR WILL FURNISH ALL THE LABOR, EQUIPMENT, AND MATERIALS NECESSARY TO PROPERLY HANDLE, STORE, TEST (FOR DISPOSAL), TRANSPORT, AND DISPOSAL; INCLUDING ANY REQUIRED PERMITS, APPROVALS, OR FEES WITHIN THE AFOREMENTIONED LOCATION. PAYMENT FOR THIS WORK WILL BE MADE AT THE CONTRACT PRICE BID PER TON, PER GALLON, PER CUBIC YARD AND PER UST. THE FOLLOWING ESTIMATED QUANTITY HAS BEEN INCLUDED IN THE GENERAL SUMMARY FOR THE WORK NOTED ABOVE:

ITEM SPECIAL - WORK INVOLVING PETROLEUM CONTAMINATED SOIL
--- 131 TON

ITEM SPECIAL - WORK INVOLVING REGULATED WATER --- 15560 GAL

IN-STREAM WORK RESRICTIONS

WORK IN THE FOLLOWING SENSITIVE STREAMS IS FURTHER RESTRICTED AS FOLLOWS:

STREAM NAME	WORK RESTRICTION DATES (NO TEMPORARY FILLS PERMITTED)
LITTLE MCMAHON CREEK	NOVEMBER 30 THROUGH MAY 31

TEMPORARY FILL INCLUDES, BUT IS NOT LIMITED TO, TEMPORARY ACCESS FILL, DEWATERING FILL, CAUSEWAYS, COFFERDAMS, ACCESS PADS, AND TEMPORARY BRIDGES, BELOW THE OHWM. TEMPORARY FILL CANNOT BE PRESENT DURING THE TEMPORARY FILL RESTRICTION DATES REFERENCED ABOVE.

GENERAL NOTES

DESIGN AGENCY



DESIGNER

MVC

REVIEWER

LRB 05-19-25

PROJECT ID

119917



SHEET

P.02

TOTAL

14

MODEL: Sheet_SunFI PAPERSIZE: 34x22 (in.) DATE: 7/2/2025 TIME: 3:08:11 PM USER: mdlark3
 pw://vhbdi-pw.bentley.com:othidow-pw-02/Documents/01 Active Projects/District 11/Belmont/119917400-Engineering/Roadway/Sheets/119917_GG001.dgn

<div></div> <div>GENERAL SUMMARY</div>	
DESIGN AGENCY	
<div></div>	
DESIGNER	
MVC	
REVIEWER	
LRB	05-19-25
PROJECT ID	
119917	
SHEET	TOTAL
P.04	14