


BRO-505/756-6.72/0.00

MODEL: Sheet\_SurvFI\_PAPER SIZE: 17x11 (in.) DATE: 6/24/2024 TIME: 7:55:02 AM USER: jstarlin  
 p:\ohio\dot-pw-bentley.com\shahid\dot-pw-02\Documents\01 Active Projects\Distict 09\Brown\118753\40-Engineering\Roadway\Sheets\118753\_GG001.dgn

SHEET NUM.										PART.			ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
3	4	6	7	8						01/STR/05								
0.57										0.57			209	60500	0.57	MILE	ROADWAY LINEAR GRADING	
										1,000			832	30000	1,000	EACH	EROSION CONTROL	
1,500										1,500			251	01001	1,500	SY	PAVEMENT	
		54,129	25,772							79,901			254	01000	79,901	SY	PARTIAL DEPTH PAVEMENT REPAIR (441), AS PER PLAN PAVEMENT PLANING, ASPHALT CONCRETE 1.5"	3
26,769										26,769			254	01600	26,769	SY	PATCHING PLANED SURFACE	
		4,872	2,320							7,192			407	20000	7,192	GAL	NON-TRACKING TACK COAT	
		2,255	1,074							3,329			441	50000	3,329	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22	
56										56			617	10100	56	CY	COMPACTED AGGREGATE	
1										1			617	25000	1	MGAL	WATER	
																	TRAFFIC CONTROL	
				536						536			621	00100	536	EACH	RPM	
				536						536			621	54000	536	EACH	RAISED PAVEMENT MARKER REMOVED	
				11.28						11.28			644	00104	11.28	MILE	EDGE LINE, 6"	
				5.64						5.64			644	00300	5.64	MILE	CENTER LINE	
				34						34			644	00500	34	FT	STOP LINE	
																	MAINTENANCE OF TRAFFIC	
42										42			614	12460	42	EACH	WORK ZONE MARKING SIGN	
11.28										11.28			614	21550	11.28	MILE	WORK ZONE CENTER LINE, CLASS III, 642 PAINT	
22.56										22.56			614	22360	22.56	MILE	WORK ZONE EDGE LINE, CLASS III, 6", 642 PAINT	
																	INCIDENTALS	
										1			614	11000	1	LS	MAINTAINING TRAFFIC	
										1			623	10000	1	LS	CONSTRUCTION LAYOUT STAKES AND SURVEYING	
										1			624	10000	1	LS	MOBILIZATION	

GENERAL SUMMARY

DESIGN AGENCY  
  
 DESIGNER  
 JBS  
 REVIEWER  
 EMB MM-DD-YY  
 PROJECT ID  
 118753  
 SHEET TOTAL  
 P.5 8