FHWA REGION	STATE	PROJECT	
5	OHIO		

1/1

CHAMPAIGN COUNTY
CHP-29-15.02

CENTERLINE PLAT

0 100 200 300 400
Scale In Feet

NOTE: Centerline was set up between Sta. 793+00.81 & T.S. Sta. 810+00.32. Used R.R. spike (found) at Sta. 793+00.81 & split berm monuments at T.S. Sta. 810+00.32 as shown on CHP-29 (15.33-16.05) location plan. Bearing is also from that plan. This line checks with old concrete pavement.

P.K. Nail Set
Sta. 794+05±
Sta. 796+35±
Sta. 800+17.47
Sta. 805+35±
Sta. 808+63±

CURVE DATA
P.I. Sta. 818+96.15
Δ = 62°-17'-30" Rt.

D = 5°	Ls = 400.00'
R = 1145.92'	Xc = 398.78'
Lc = 845.83'	Yc = 23.22'
Ts = 895.82'	p = 5.81'
Es = 199.79'	k = 199.80'
L.T. = 267.09'	S.T. = 133.72'

I hereby certify that this plat is a true delineation of a survey made by the Ohio Department of Transportation in 1986.

Richard R. Helmlinger
Richard R. Helmlinger – Registered Surveyor #5421

RECORDED
CHAMPAIGN COUNTY
Date: _____
Vol. : _____
Page: _____