

I:\ProjectData\CLA\101090_US40_SR4\Design\Roadway\Sheets\101090_G0002.dgn_Sheet 2/7/2022 8:31:19 AM cweiss

SHEET NUM.											PART.			ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
8	10	13	14	15	16	17	18	19	20	01/NHS/PV	02/SAF/OT	03/S<2/PV							
									6	6			519	12300	6	SY	STRUCTURE REPAIR (CLA-40-1052 L) PATCHING CONCRETE BRIDGE DECK - TYPE B		
									6	6			519	12300	6	SY	STRUCTURE REPAIR (CLA-40-1052 R) PATCHING CONCRETE BRIDGE DECK - TYPE B		
									2	2			519	12300	2	SY	STRUCTURE REPAIR (CLA-4-1124) PATCHING CONCRETE BRIDGE DECK - TYPE B		
	200									200			614	11110	200	hour	MAINTENANCE OF TRAFFIC LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE		
	2									2			614	18601	2	SNMT	PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN	10	
					21.74					21.74			614	20056	21.74	MILE	WORK ZONE LANE LINE, CLASS I, 6", 807 PAINT		
						3.22	0.37			3.59			614	20560	3.59	MILE	WORK ZONE LANE LINE, CLASS III, 6", 642 PAINT		
						0.26	0.16			0.42			614	21550	0.42	MILE	WORK ZONE CENTER LINE, CLASS III, 642 PAINT		
					37.78					37.78			614	22056	37.78	MILE	WORK ZONE EDGE LINE, CLASS I, 6", 807 PAINT		
						5.68	0.47			6.15			614	22360	6.15	MILE	WORK ZONE EDGE LINE, CLASS III, 6", 642 PAINT		
					4,454					4,454			614	23110	4,454	FT	WORK ZONE CHANNELIZING LINE, CLASS I, 12", 807 PAINT		
						1,566	1,522			3,088			614	23680	3,088	FT	WORK ZONE CHANNELIZING LINE, CLASS III, 8", 642 PAINT		
						3,190				3,190			614	23690	3,190	FT	WORK ZONE CHANNELIZING LINE, CLASS III, 12", 642 PAINT		
					10,638					10,638			614	24102	10,638	FT	WORK ZONE DOTTED LINE, CLASS I, 6", 807 PAINT		
						4,310	280			4,590			614	24612	4,590	FT	WORK ZONE DOTTED LINE, CLASS III, 6", 642 PAINT		
						222	48			270			614	26610	270	FT	WORK ZONE STOP LINE, CLASS III, 642 PAINT		
						14	15			29			614	30650	29	EACH	WORK ZONE ARROW, CLASS III, 642 PAINT		
	8									8			808	18700	8	SNMT	DIGITAL SPEED LIMIT (DSL) SIGN ASSEMBLY		
										LS	LS	LS	614	11000	LS		INCIDENTALS MAINTAINING TRAFFIC		
										LS	LS	LS	624	10000	LS		MOBILIZATION		

GENERAL SUMMARY

CLA - 40 / 4-9.85 / 5.53